

County : Moore

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0001010000-N	200	SELECT TREE REMOVAL	64 EA		
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	170 TON		
0006	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	598 LF		
0007	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	858 LF		
0008	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	84 LF		
0009	0453000000-E	310	*** PIPE END SECTION (15")	1 EA		
001C	0995000000-E	340	PIPE REMOVAL	213 LF		
0011	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0012	1330000000-E	607	INCIDENTAL MILLING	200 SY		
0013	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	910 TON		
0014	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	975 TON		
0015	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	1,360 TON		
0016	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	170 TON		
0017	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	40 TON		

County : Moore

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	2000000000-N	806	RIGHT OF WAY MARKERS	13	EA	
001E	2253000000-E	840	PIPE COLLARS	0.45	CY	
002C	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	28	EA	
0021	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	43.69	LF	
0022	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	3	EA	
0023	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	5	EA	
0024	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	6	EA	
002E	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	10	EA	
002E	2396000000-N	840	FRAME WITH COVER, STD 840.54	5	EA	
0027	2542000000-E	846	1'-6" CONCRETE CURB & GUTTER	215	LF	
002E	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	315	LF	
002E	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	12	EA	
003C	2655000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)	40	SY	
0031	2738000000-E	SP	GENERIC PAVING ITEM 7" CONCRETE TRUCK APRON	205	SY	
0032	2752000000-E	SP	GENERIC PAVING ITEM 1'-6" CONCRETE CURB & GUTTER (SPECIAL)	4,765	LF	
0033	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	1	EA	
0034	2860000000-N	859	CONVERT EXISTING CATCH BASIN TO JUNCTION BOX	1	EA	

County : Moore

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	4589000000-N	SP	GENERIC TRAFFIC CONTROL ITEM TRAFFIC CONTROL	Lump Sum	L.S.	
003E	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	2,740 LF		
0037	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	6,550 LF		
003E	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	175 LF		
003E	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	215 LF		
004C	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	380 LF		
0041	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	59 EA		
0042	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	500 LF		
0043	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	50 LF		
0044	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	145 EA		
004E	6000000000-E	1605	TEMPORARY SILT FENCE	2,800 LF		
004E	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	25 TON		
0047	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	40 TON		
004E	6012000000-E	1610	SEDIMENT CONTROL STONE	155 TON		
004E	6015000000-E	1615	TEMPORARY MULCHING	1.5 ACR		
005C	6042000000-E	1632	1/4" HARDWARE CLOTH	720 LF		
0051	6084000000-E	1660	SEEDING & MULCHING	1.65 ACR		

County : Moore

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0052	6135000000-E	SP	GENERIC EROSION CONTROL ITEM TOP SOIL - STOCKPILED & REAPPLIED	0.4 ACR		
0053	6138000000-E	SP	GENERIC EROSION CONTROL ITEM TOPSOIL - FURNISHED	110 CY		
0054	6640000000-N	1670	GENERIC PLANTING ITEM HEMEROCALLIS 'MARY TODD'	118 EA		
0055	6645000000-N	SP	GENERIC PLANTING ITEM MULCH - PINE STRAW BALES	874 EA		
0056	6645000000-N	SP	GENERIC PLANTING ITEM RELOCATION OF POST TOP LIGHTS	2 EA		
0057	6650000000-E	1670	MULCH FOR PLANTING	17 CY		
0058	6655000000-E	1670	WATER FOR PLANTING	1 M/G		
0059	6665000000-E	1670	POSTEMERGENT HERBICIDAL TREAT- MENT FOR PLANT BEDS	46 SY		
0060	6670000000-E	1670	PREEMERGENT HERBICIDAL TREAT- MENT FOR PLANT BEDS	46 SY		
0061	6674000000-N	SP	GENERIC PLANTING ITEM (LS) IRRIGATION SYSTEM	Lump Sum	L.S.	
0062	6675000000-E	SP	GENERIC PLANTING ITEM SOD (BERMUDA - TIFWAY 419)	1,916 SY		
0063	6675000000-E	SP	GENERIC PLANTING ITEM SOD (FESCUE)	465 SY		
0064	6676000000-E	SP	GENERIC PLANTING ITEM BRICK SIDEWALK	1,523 SF		
0065	6685000000-E	SP	GENERIC PLANTING ITEM WATER FOR SOD	13 M/G		
0066	6690000000-E	SP	GENERIC PLANTING ITEM TREE PROTECTION FENCE	5,080 LF		
0067	7060000000-E	1705	SIGNAL CABLE	750 LF		

County : Moore

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
006E	7300000000-E	1715	UNPAVED TRENCHING (*****) (1 CONDUIT, 2")	1,920 LF		
006E	7301000000-E	1715	DIRECTIONAL DRILL (*****) (2 CONDUITS, 2")	255 LF		
007C	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	8 EA		
0071	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	970 LF		
0072	7456000000-E	1726	LEAD-IN CABLE (*****) (18-2 PAIR)	1,480 LF		
0073	7590000000-N	SP	METAL POLE WITH DUAL MAST ARM	2 EA		
0074	7613000000-N	SP	SOIL TEST	2 EA		
007E	7614100000-E	SP	DRILLED PIER FOUNDATION	16 CY		
0076	7631000000-N	SP	MAST ARM WITH METAL POLE DE- SIGN	2 EA		
0077	7980000000-N	SP	GENERIC SIGNAL ITEM VEHICLE SIGNAL HEAD INSTALLATION	8 EA		
007E	8594000000-E	876	RIP RAP, CLASS B	10 TON		
007E	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	28 SY		

1304/Aug16/Q41635.69/D343507210000/E79

Total Amount Of Bid For Entire Project :

**Contract No: C201861**

**County: Moore**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General