



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

MICHAEL F. EASLEY
GOVERNOR

LYNDO TIPPETT
SECRETARY

October 4, 2007

Addendum No. 1

RE: Contract ID: C201883

WBS# 2CR.10541.7

Lenoir County

NC-11 From Pitt County Line to Beginning of
Curb and Gutter in Kinston

October 16, 2007 Letting

To Whom It May Concern:

Reference is made to the Proposal Form recently furnished to you on this project.

The following revision has been made to the proposal form:

On Page No. 23, a revision has been made to the eighth paragraph of that page within the Project Special Provision entitled "Traffic Control". Please void Page No. 23 in your proposal and staple the revised Page No. 23 thereto.

Sincerely,

R. A. Garris, PE
Contract Officer

RAG/jag/blr
Attachment

cc: Mr. W. S. Varnedoe, PE
Mr. E. C. Powell, PE
Mr. C. E. Lassiter, PE
Ms. D. M. Barbour, PE
Mr. Art McMillan, PE
Mr. J. V. Barbour, PE
Mr. Stuart Bourne, PE
Mr. Mark Staley (2)

Mr. Robert Memory
Mr. R. E. Davenport, Jr., PE
Ms. Norma Smith
Mr. Ronnie Higgins
Ms. Taylor Mishoe
Project File (2)

MAILING ADDRESS:
NC DEPARTMENT OF TRANSPORTATION
DESIGN SERVICES UNIT
1591 MAIL SERVICE CENTER
RALEIGH NC 27699-1591

TELEPHONE: 919-250-4128
FAX: 919-250-4119

WEBSITE: WWW.NCDOT.ORG/

LOCATION:
CENTURY CENTER COMPLEX
ENTRANCE B2
1020 BIRCH RIDGE DRIVE
RALEIGH NC

Do not exceed a difference of 2 inches in elevation between open lanes of traffic for nominal lifts of 1.5 inches. Install advance warning UNEVEN LANES signs (W8-11 at 48" X 48") 500 feet in advance and a minimum of once every half mile throughout the uneven area.

Backfill at a 6:1 slope up to the edge and elevation of existing pavement in areas adjacent to an open travel lane that has an edge of pavement drop-off as follows:

(A) Drop-off that exceeds 2 inches on roadways with posted speed limits of 45 mph or greater

(B) Drop-off that exceeds 3 inches on roadways with posted speed limit less than 45 mph.

Backfill the unacceptable drop-off with suitable compacted material, as approved by the Engineer, at no expense to the Department. This work is not considered part of shoulder reconstruction.

When utilizing a slow-moving operation for such items as pavement marking placement, pavement marker installation and pesticide spraying, the slow moving operation caravan shall consist, as a minimum, of the vehicles and devices shown on the Moving Operation Caravan Detail(s) herein. Traffic cones may be used when necessary to provide additional protection of wet pavement markings. Ballast all traffic cones so they will not be blown over by traffic.

Submit a sequence of operation for all maps to the Engineer at the first pre-construction meeting for approval by the Engineer. Approved sequence can not be altered without written permission of the Engineer.

Notify the Engineer 48 hours before milling or resurfacing will interfere with the existing Signal Loops. Loops may need to be placed in milled surface before resurfacing occurs. Coordinate all signal loop operations with the Engineer.

Notify the Engineer 15 consecutive calendar days before resurfacing a bridge or its approaches. Patch and make repairs to bridge surface and its approaches before resurfacing occurs. Coordinate all operations on the bridge and its approaches with the Engineer.

Notify the Engineer 48 hours before resurfacing the areas of existing pavement that require patching. Patch these areas before resurfacing occurs. Allow full depth asphalt patching to cool to the point of supporting traffic without displacement or rutting before reopening closed lane. Coordinate the resurfacing operations of the patched areas with the Engineer.

During a resurfacing only operation, bring all newly resurfaced lanes to the same elevation **by the end of the next day.**

For partial or wheel track milling operations on two-way, two-lane facilities, mill and pave back by the end of each work day. For partial or wheel track milling operations on multi-lane facilities, the lane being milled may be left closed and paved back within 72 hours.

The following option is acceptable during Resurfacing/milling operations on two-way, two-lane facilities when the entire roadway or entire lane is to be milled: