

County : Vance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0004	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0022000000-E	225	UNCLASSIFIED EXCAVATION	13,100 CY		
0006	0036000000-E	225	UNDERCUT EXCAVATION	25,000 CY		
0007	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	44,000 TON		
0008	0106000000-E	230	BORROW EXCAVATION	47,100 CY		
0009	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	60,500 SY		
0010	0163000000-E	250	REMOVAL OF EXISTING CONCRETE PAVEMENT	26,520 SY		
0011	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	81,000 SY		
0012	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	50 TON		
0013	0588000000-E	310	18" CS PIPE CULVERTS, 0.064" THICK	1,864 LF		
0014	0594000000-E	310	24" CS PIPE CULVERTS, 0.064" THICK	144 LF		
0015	0995000000-E	340	PIPE REMOVAL	2,008 LF		
0016	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
0017	1110000000-E	510	STABILIZER AGGREGATE	500 TON		
0018	1220000000-E	545	INCIDENTAL STONE BASE	200 TON		

County : Vance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	6,680 SY		
0020	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 3")	990 SY		
0021	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	12,570 TON		
0022	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	39,000 TON		
0023	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	2,760 TON		
0024	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	22,410 TON		
0025	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	4,450 TON		
0026	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	8,690 TON		
0027	1539000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S12.5C	17,750 TON		
0028	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	4,100 TON		
0029	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	1,500 TON		
0030	1567000000-E	SP	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-28	50 TON		
0031	1671000000-E	652	PERMEABLE ASPHALT DRAINAGE COURSE, TYPE P-78M	14,400 TON		
0032	1839110000-E	661	ULTRATHIN HOT MIX ASPHALT, TYPE B	960 TON		
0033	1839200000-E	661	APPLICATION OF ULTRATHIN HOT MIX ASPHALT	27,300 SY		
0034	1840000000-E	665	MILLED RUMBLE STRIPS (ASPHALT CEMENT CONCRETE)	137,300 LF		

County : Vance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035	1847000000-E	710	***** PORT CEM CONC PAVEMENT, THROUGH LANES (WITH DOWELS) (11")	101,200 SY		
0036	1847000000-E	710	***** PORT CEM CONC PAVEMENT, THROUGH LANES (WITH DOWELS) (13")	25,500 SY		
0037	1869000000-E	710	***** PORT CEM CONC PAVEMENT, MISCELLANEOUS (WITHOUT DOWELS) (11")	16,300 SY		
0038	1880000000-E	SP	GENERIC PAVING ITEM AGGREGATE BASE COURSE FOR BACKFILL	850 TON		
0039	1891000000-E	SP	GENERIC PAVING ITEM CRC PAVEMENT REPAIR	2,500 SY		
0040	1902000000-N	710	SURFACE TESTING CONCRETE PAVEMENT	Lump Sum	L.S.	
0041	1924000000-N	725	FIELD LABORATORY RENTAL, PORT CEM CONC PAVEMENT	Lump Sum	L.S.	
0042	2022000000-E	815	SUBDRAIN EXCAVATION	336 CY		
0043	2033000000-E	815	SUBDRAIN FINE AGGREGATE	252 CY		
0044	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	1,500 LF		
0045	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	45 EA		
0046	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	3 EA		
0047	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	18 LF		
0048	2099000000-E	816	SHOULDER DRAIN	45,400 LF		
0049	2110000000-E	816	4" SHOULDER DRAIN PIPE	45,400 LF		
0050	2121000000-E	816	4" OUTLET PIPE FOR SHOULDER DRAINS	2,550 LF		
0051	2132000000-N	816	CONCRETE PAD FOR SHOULDER DRAIN PIPE OUTLET	95 EA		

County : Vance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0052	2190000000-N	828	TEMPORARY STEEL PLATE COVERS FOR MASONRY DRAINAGE STRUCTURE	1 EA		
0053	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3 EA		
0054	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	1.25 LF		
0055	2365000000-N	840	FRAME WITH TWO GRATES, STD 840.22	30 EA		
0056	2472000000-N	840	GENERIC DRAINAGE ITEM REMOVE & REPLACE DI APRON	29 EA		
0057	2472000000-N	840	GENERIC DRAINAGE ITEM REPLACE FRAME ONLY, STD 840.22	1 EA		
0058	2472000000-N	840	GENERIC DRAINAGE ITEM REPLACE GRATE ONLY, STD 840.22	3 EA		
0059	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	75 LF		
0060	2619000000-E	850	4" CONCRETE PAVED DITCH	620 SY		
0061	2724000000-E	857	PRECAST REINFORCED CONCRETE BARRIER, SINGLE FACED	310 LF		
0062	2739000000-E	852	GENERIC PAVING ITEM REMOVE CONCRETE PAVED DITCH	600 SY		
0063	2815000000-N	858	ADJUSTMENT OF DROP INLETS	24 EA		
0064	3000000000-N	SP	IMPACT ATTENUATOR UNIT, TYPE 350	2 EA		
0065	3030000000-E	862	STEEL BM GUARDRAIL	15,675 LF		
0066	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	25 EA		
0067	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	17 EA		
0068	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	12 EA		
0069	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	20 EA		

County : Vance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0070	3285000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE M-350	3 EA		
0071	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0072	3345000000-E	864	REMOVE & RESET EXISTING GUARDRAIL	1,800 LF		
0073	3360000000-E	863	REMOVE EXISTING GUARDRAIL	15,555 LF		
0074	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	6 EA		
0075	3389400000-E	865	DOUBLE FACED CABLE GUIDERAIL	9,000 LF		
0076	3389500000-N	SP	ADDITIONAL GUIDERAIL POSTS	6 EA		
0077	3389600000-N	865	CABLE GUIDERAIL ANCHOR UNITS	16 EA		
0078	3420000000-E	SP	GENERIC GUARDRAIL ITEM REMOVE EXISTING CABLE GUIDE-RAIL	17,400 LF		
0079	3595000000-E	869	RELAPPING GUARDRAIL	5,362.5 LF		
0080	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	375 SY		
0081	4048000000-E	902	REINFORCED CONCRETE SIGN FOUNDATIONS	18 CY		
0082	4057000000-E	SP	OVERHEAD FOOTING	36 CY		
0083	4060000000-E	903	SUPPORTS, BREAKAWAY STEEL BEAM	13,904 LB		
0084	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	2,095 LF		
0085	4078000000-E	903	SUPPORTS, 2-LB STEEL U-CHANNEL	12 EA		
0086	4082100000-N	SP	SUPPORTS, OVERHEAD SIGN STRUCTURE AT STA ***** (285+65 -LMED-)	Lump Sum	L.S.	
0087	4082100000-N	SP	SUPPORTS, OVERHEAD SIGN STRUCTURE AT STA ***** (295+00 -LMED-)	Lump Sum	L.S.	

County : Vance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0088	4082100000-N	SP	SUPPORTS, OVERHEAD SIGN STRUCTURE AT STA ***** (299+00 -LMED-)	Lump Sum	L.S.	
0089	4082100000-N	SP	SUPPORTS, OVERHEAD SIGN STRUCTURE AT STA ***** (302+00 -LMED-)	Lump Sum	L.S.	
0090	4096000000-N	904	SIGN ERECTION, TYPE D	21 EA		
0091	4102000000-N	904	SIGN ERECTION, TYPE E	58 EA		
0092	4108000000-N	904	SIGN ERECTION, TYPE F	20 EA		
0093	4110000000-N	904	SIGN ERECTION, TYPE *** (GROUND MOUNTED) (A)	18 EA		
0094	4110000000-N	904	SIGN ERECTION, TYPE *** (GROUND MOUNTED) (B)	10 EA		
0095	4114000000-N	904	SIGN ERECTION, MILEMARKERS	12 EA		
0096	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (D)	2 EA		
0097	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (E)	1 EA		
0098	4152000000-N	907	DISPOSAL OF SIGN SYSTEM, STEEL BEAM	19 EA		
0099	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	97 EA		
0100	4158000000-N	907	DISPOSAL OF SIGN SYSTEM, WOOD	2 EA		
0101	4192000000-N	907	DISPOSAL OF SUPPORT, U-CHANNEL	2 EA		
0102	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	5,314 SF		
0103	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	2,023 SF		
0104	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	480 SF		

County : Vance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0105	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	4 EA		
0106	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	12 EA		
0107	4430000000-N	1130	DRUMS	700 EA		
0108	4435000000-N	1135	CONES	22 EA		
0109	4445000000-E	1145	BARRICADES (TYPE III)	664 LF		
0110	4450000000-N	1150	FLAGGER	200 HR		
0111	4480000000-N	1165	TMIA	4 EA		
0112	4485000000-E	1170	PORTABLE CONCRETE BARRIER	26,000 LF		
0113	4495000000-E	1170	PORTABLE CONCRETE BARRIER (DRAINAGE)	9,000 LF		
0114	4500000000-E	1170	RESET PORTABLE CONCRETE BAR- RIER	52,000 LF		
0115	4506000000-E	1170	RESET PORTABLE CONCRETE BAR- RIER (DRAINAGE)	18,000 LF		
0116	4510000000-N	SP	POLICE	2,100 HR		
0117	4516000000-N	1180	SKINNY DRUM	44 EA		
0118	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	5,930 EA		
0119	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (4)	18,180 LF		
0120	4780000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (8") (4)	3,300 LF		
0121	4805000000-N	1205	COLD APPLIED PLASTIC PAVEMENT MARKING SYMBOL, TYPE ** (4)	6 EA		
0122	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	1,197,600 LF		

County : Vance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0123	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	46,000 LF		
0124	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	288 LF		
0125	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	90 EA		
0126	4847000000-E	1205	POLYUREA PAVEMENT MARKING LINES (4", *****) (STANDARD GLASS BEADS)	173,626 LF		
0127	4847110000-E	1205	POLYUREA PAVEMENT MARKING LINES (8", *****) (STANDARD GLASS BEADS)	6,000 LF		
0128	4847140000-E	1205	POLYUREA PAVEMENT MARKING LINES (24", *****) (STANDARD GLASS BEADS)	120 LF		
0129	4847220000-N	1205	POLYUREA PAVEMENT MARKING SYMBOL (*****) (STANDARD GLASS BEADS)	38 EA		
0130	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	595,000 LF		
0131	4860000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (8")	23,500 LF		
0132	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	216 LF		
0133	4875000000-N	1205	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS	96 EA		
0134	4880000000-E	1205	CURING COMPOUND REMOVAL, LINES	111,834 LF		
0135	4885000000-N	1205	CURING COMPOUND REMOVAL, SYMBOLS & CHARACTERS	15 EA		
0136	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	12 EA		
0137	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	1,624 EA		
0138	4935000000-N	1267	FLEXIBLE DELINEATORS (CRYSTAL)	170 EA		
0139	4940000000-N	1267	FLEXIBLE DELINEATORS (YELLOW)	68 EA		

County : Vance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0140	4945000000-N	1267	FLEXIBLE DELINEATORS (CRYSTAL & RED)	30 EA		
0141	4950000000-N	1267	FLEXIBLE DELINEATORS (YELLOW & RED)	30 EA		
0142	6000000000-E	1605	TEMPORARY SILT FENCE	500 LF		
0143	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	125 TON		
0144	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	125 TON		
0145	6012000000-E	1610	SEDIMENT CONTROL STONE	125 TON		
0146	6015000000-E	1615	TEMPORARY MULCHING	5 ACR		
0147	6036000000-E	1631	MATTING FOR EROSION CONTROL	500 SY		
0148	6042000000-E	1632	1/4" HARDWARE CLOTH	250 LF		
0149	6084000000-E	1660	SEEDING & MULCHING	5 ACR		
0150	6090000000-E	1661	SEED FOR REPAIR SEEDING	250 LB		
0151	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	1.25 TON		
0152	6114000000-N	SP	SPECIALIZED HAND MOWING	5 HR		
0153	7300000000-E	1715	UNPAVED TRENCHING (*****) (1, 2")	30 LF		
0154	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	1 EA		
0155	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	350 LF		
0156	7456000000-E	1726	LEAD-IN CABLE (*****) (18-2)	35 LF		

County : Vance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
***** BEGIN SCHEDULE AA ***** ***** (3 ALTERNATES) *****						
0157 AA1	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	376		LF
*** OR ***						
0158 AA2	0536000000-E	SP	***** HDPE PIPE CULVERTS (15")	376		LF
*** OR ***						
0159 AA3	0540000000-E	SP	***** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, ***** THICK (15", 0.064")	376		LF
***** END SCHEDULE AA *****						
STRUCTURE ITEMS						
0160	8161000000-E	420	GROOVING BRIDGE FLOORS	24,466		SF
0161	8538000000-E	SP	CLASS I, SURFACE PREPARATION	3,169		SY
0162	8552000000-E	SP	CLASS IB, SURFACE PREPARATION	2,200		SY
0163	8559000000-E	SP	CLASS II, SURFACE PREPARATION	647		SY
0164	8566000000-E	SP	CLASS III, SURFACE PREPARATION	268		SY
0165	8573000000-E	SP	LATEX MODIFIED CONC OVERLAY	186		CY
0166	8580000000-E	SP	PLACING & FINISHING OF LATEX MODIFIED CONC OVERLAY	3,169		SY
0167	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum		L.S.

1343/Sep13/Q3266039.8/D591654480000/E167

Total Amount Of Bid For Entire Project :

Contract No: C201791

County: Vance

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General