

**PROJECT SPECIAL PROVISIONS****ROADWAY****SHOULDER DROP OFF REPAIR W/ WIDENING MACHINE:**

(1-18-00) (Rev. 9-10-07)

R1 R07 Rev

**Description**

The work covered by this provision consists of repairing earth shoulders in accordance with the *Roadway Standard Drawing Nos. 560.01, 560.02, and shoulder drop-off typical* from the edge of pavement to the existing shoulder point as directed by the Engineer and as shown on the typical section. Perform this work immediately after the resurfacing operations are completed as directed by the Engineer. *Any seeding and mulching required will be performed by State Forces.*

**Materials**

Use all suitable *soil based* material *excluding ABC, and gravel* to construct the shoulder. Provide earth material meeting the approval of the Engineer. No testing will be necessary.

**Construction Methods**

Perform shoulder *drop off repair* in the following order, add the earth material *with widening machine* to the shoulder; and compact the reconstructed shoulder to the satisfaction of the Engineer.

Backfill at a 6:1 slope up to the edge and elevation of existing pavement in areas adjacent to an open travel lane that has an edge of pavement drop-off as follows:

- (A) Drop-off that exceeds 2 inches on roadways with posted speed limits of 45 mph or greater
- (B) Drop-off that exceeds 3 inches on roadways with posted speed limit less than 45 mph.

Backfill the unacceptable drop-off with suitable compacted material, as approved by the Engineer.

**Measurement and Payment**

*Shoulder Drop off repair* will be measured and paid for as the actual number of shoulder miles that have been constructed. Measurement will be made along the edge of each shoulder. Measurement will be made to the nearest 0.01 of a mile. Such price and payment will be full compensation for furnishing earth material, hauling, placing, compaction, and all incidentals necessary to complete *repair* of the shoulders.

Payment will be made under:

**Pay Item**

Shoulder Drop Off Repair

**Pay Unit**

Shoulder Mile

**INCIDENTAL STONE BASE:**

(7-1-95) (Rev.7-18-06)

R5 R28

**Description**

Place incidental stone base on driveways, mailboxes, etc. immediately after paving and do not have the paving operations exceed stone base placement by more than one week without written permission of the Engineer.

**Materials and Construction**

Provide and place incidental stone base in accordance with the requirements of Section 545 of the *2006 Standard Specifications*.

**Measurement and Payment**

*Incidental Stone Base* will be measured and paid for in accordance with Article 545-6 of the *2006 Standard Specifications*.

**ASPHALT PAVEMENTS - SUPERPAVE:**

(7-18-06) (Rev 9-19-06)

R6 R01

Revise the *2006 Standard Specifications* as follows:

**Page 6-2, Article 600-9 Measurement and Payment**

Delete the second paragraph.

**Page 6-12, 609-5(C)2(c) add after (AASHTO T 209):**

*or ASTM D 2041*

**Page 6-13, last line on page & Page 6-14, Subarticle 609-5(C)(2)(e)**, delete and substitute the following:

(e) Retained Tensile Strength (TSR) - (AASHTO T 283 Modified), add subarticle (1) Option 1 before the first paragraph.

(1) Option 1

Add subarticle (2) Option 2 and the following sentence as the first sentence of the second paragraph:

(2) Option 2

Mix sampled from truck at plant with one set of specimens prepared by the Contractor and then tested jointly by QA and QC at a mutually agreed upon lab site within the first 7 calendar days after beginning production of each new mix design.

**Page 6-28, 610-3(A) Mix Design-General**, third sentence of the fourth paragraph:

Substitute 20% for 15%

First, second and third sentences of the fifth paragraph:

Substitute 20% for 15%

**Page 6-44, 610-8**, third full paragraph, replace the first sentence with the following:

Use the 30 foot minimum length mobile grade reference system or the non-contacting laser or sonar type ski *with at least four referencing stations mounted on the paver at a minimum length of 24 feet* to control the longitudinal profile when placing the initial lanes and all adjacent lanes of all layers, including resurfacing and asphalt in-lays, unless otherwise specified or approved.

**Page 6-54, Article 620-4**, add the following pay item:

<b>Pay Item</b>	<b>Pay Unit</b>
Asphalt Binder for Plant Mix, Grade PG 70-28	Ton

**Page 6-69, Table 660-1 Material Application Rates and Temperatures**, add the following:

Type of Coat	Grade of Asphalt	Asphalt Rate gal/yd <sup>2</sup>	Application Temperature °F	Aggregate Size	Aggregate Rate lb./sq. yd. Total
Sand Seal	CRS-2 or CRS-2P	0.22-0.30	150-175	Blotting Sand	12-15

**Page 6-75, 660-9(B)**, add the following as sub-item (5)

(5) Sand Seal

Place the fully required amount of asphalt material in one application and immediately cover with the seal coat aggregate. Uniformly spread the fully required amount of aggregate in one application and correct all non-uniform areas prior to rolling.

Immediately after the aggregate has been uniformly spread, perform rolling.

When directed, broom excess aggregate material from the surface of the seal coat.

When the sand seal is to be constructed for temporary sealing purposes only and will not be used by traffic, other grades of asphalt material meeting the requirements of Articles 1020-6 and 1020-7 may be used in lieu of the grade of asphalt required by Table 660-1 when approved.

Page 10-41, Table 1012-1, add the following:

Mix Type	Course Aggregate Angularity <sup>(b)</sup> ASTM D5821	Fine Aggregate Angularity % Minimum AASHTO T304 Method A	Sand Equivalent % Minimum AASHTO T176	Flat & Elongated 5:1 Ratio % Maximum ASTM D4791 Section 8.4
S 9.5 D	100/100	45	50	10

Page 10-45, Replace Table 1012-2 with the following:

**TABLE 1012-2**  
**NEW SOURCE RAP GRADATION and BINDER TOLERANCES**  
(Apply Tolerances to Mix Design Data)

Mix Type	0-20% RAP			21-25% RAP			26%+ RAP		
	Base	Inter.	Surf.	Base	Inter.	Surf.	Base	Inter.	Surf.
P <sub>b</sub> , %		± 0.7%			± 0.4%			± 0.3%	
1 1/2" (37.5)	±10	-	-	±7	-	-	±5	-	-
3/4" (19.0)	±10	±10	-	±7	±7	-	±5	±5	-
1/2" (12.5)	-	±10	±6	-	±7	±3	-	±5	±2
3/8" (9.5)	-	-	±8	-	-	±5	-	-	±4
No. 4 (4.75)	±10	-	±10	±7	-	±7	±5	-	±5
No. 8 (2.36)	±8	±8	±8	±5	±5	±5	±4	±4	±4
No.16 (1.18)	±8	±8	±8	±5	±5	±5	±4	±4	±4
No. 30 (0.600)	±8	±8	±8	±5	±5	±5	±4	±4	±4
No. 50 (0.300)	-	-	±8	-	-	±5	-	-	±4
No. 200 (0.075)	±4	±4	±4	±2	±2	±2	±1.5	±1.5	±1.5

**ASPHALT BINDER CONTENT OF ASPHALT PLANT MIXES:**

(1-1-02)

R6 R15

The approximate asphalt binder content of the asphalt concrete plant mixtures used on this project will be as follows:

Asphalt Concrete Base Course	Type B 25.0 __	4.3 %
Asphalt Concrete Intermediate Course	Type I 19.0 __	4.7 %
Asphalt Concrete Surface Course	Type S 4.75A	7.0 %
Asphalt Concrete Surface Course	Type SF 9.5A	6.5 %
Asphalt Concrete Surface Course	Type S 9.5 __	6.0 %
Asphalt Concrete Surface Course	Type S 12.5 __	5.5 %

The actual asphalt binder content will be established during construction by the Engineer within the limits established in the *2006 Standard Specifications*.

**PRICE ADJUSTMENT - ASPHALT BINDER FOR PLANT MIX:**

(11-21-00)

R6 R25

Price adjustments for asphalt binder for plant mix will be made in accordance with Section 620 of the *2006 Standard Specifications*.

The base price index for asphalt binder for plant mix is \$ **318.93** per ton.

This base price index represents an average of F.O.B. selling prices of asphalt binder at supplier's terminals on **October 1, 2007**.

**RESURFACING EXISTING BRIDGES:**

(7-1-95) (Rev. 6-11-07)

R6 R61 Rev

The Contractor's attention is directed to the fact that he will be required to resurface the bridges on this project if directed by the Engineer.

Place the surface so as to follow a grade line set by the Engineer with the minimum thickness as shown on the sketch herein or as directed by the Engineer (See "**Davie County 2008 Resurfacing Bridge Data Listing**" in the **Detail Drawings Section of the Contract**.) State Forces will make all necessary repairs to the bridge floors prior to the time that the Contractor places the proposed surfacing. Give the Engineer at least 15 days notice prior to the expected time to begin operations, **unless otherwise instructed**, so that State Forces will have sufficient time to complete their work.

At all bridges that are not to be resurfaced, taper out the proposed resurfacing layer adjacent to the bridges to insure a proper tie-in with the bridge surface.

**ASPHALT CONCRETE SURFACE COURSE, TYPE xxx (Leveling Course):**

(7-1-95)

R6 R85

Place a leveling course of *Asphalt Concrete Surface Course, Type* \_\_ at locations shown on the sketch maps and as directed by the Engineer. The rate of this leveling course is not established

but will be determined by allowing the screed to *drag* the high points of the section. It is anticipated that some map numbers will be leveled from beginning to end while others may only require a leveling course for short sections.

The Asphalt Concrete Surface Course, Type \_\_ (Leveling Course) shall meet the requirements of Section 610 of the *Standard Specifications* except payment will be made at the contract unit price per ton for *Asphalt Concrete Surface Course, Type \_\_ (Leveling Course)*.

### **PATCHING EXISTING PAVEMENT W/ MILLING MACHINE:**

(1-15-02) (Rev.7-18-06) (Rev.9-10-07)

R6 R88 Rev

#### **Description**

The Contractor's attention is directed to the fact that there are areas of existing pavement on this project that will require repair prior to resurfacing. Patch the areas that, in the opinion of the Engineer, need repairing. The areas to be patched will be delineated by the Engineer prior to the Contractor performing repairs.

#### **Materials**

The patching consists of Asphalt Concrete Base Course, Asphalt Concrete Intermediate Course, Asphalt Concrete Surface Course, or a combination of base, binder and surface course.

#### **Construction Methods**

Remove existing pavement at locations directed by the Engineer. **This shall include the use of a milling machine to remove the existing pavement providing a neat vertical joint and uniform line. Repair area to be tacked before placement of asphalt plant mix. The removal and disposal of all pavement millings and sub-grade material is incidental to the work.**

Place Asphalt Concrete Base Course, in lifts not exceeding 5 1/2 inches. Utilize compaction equipment suitable for compacting patches as small as 3.5 feet by 6 feet on each lift. Use an approved compaction pattern to achieve proper compaction. If patched pavement is to be open to traffic for more than 48 hours prior to overlay, use Asphalt Surface Course in the top 1.25 inches of the patch.

Schedule operations so that all areas where pavement has been removed, will be repaired on the same day of the pavement removal and all lanes of traffic restored.

#### **Measurement and Payment**

*Patching Existing Pavement* will be measured and paid for as the actual number of tons of asphalt plant mix complete in place, that has been used to make completed and accepted repairs. The asphalt plant mixed material will be measured by being weighed in trucks on certified platform scales or other certified weighing devices. The above price and payment will be full compensation for all work covered by this provision, including but not limited to **the use of a milling machine for the removal of pavement, the disposal of pavement millings and any**

**sub-grade material;** furnishing and applying tack coat; furnishing, placing, and compacting of asphalt plant mix; furnishing of asphalt binder for the asphalt plant mix; and furnishing scales.

Patching Existing Pavement will be considered a minor item. In the event that the item of Patching Existing Pavement overruns the original bid quantity by more than 100 percent, the provisions of Article 104-5 of the *Standard Specifications* pertaining to revised contract unit price for overrunning minor items will not apply to this item. Any provisions included in the contract that provides for adjustments in compensation due to variations in the price of asphalt binder will not be applicable to payment for the work covered by this provision.

Payment will be made under:

<b>Pay Item</b>	<b>Pay Unit</b>
Patching Existing Pavement	Ton

**ADJUSTMENT OF MANHOLES, METER BOXES, AND VALVE BOXES:**

(7-1-95) (REV 7-8-07)

R8 R97 Rev

The Contractor's attention is directed to Article 858-3 of the *2006 Standard Specifications*. Cast iron or steel fittings will not be permitted for the adjustment of manholes, meter boxes, and valve boxes on this project.

*Valve boxes, manholes, and meter boxes shall be adjusted in accordance with Section 858 of the Standard Specifications and the detail in the sketch maps. This item consists of raising or lowering existing manholes and valve boxes to match the finished surface grade. The Contractor will be required to effectively mark the locations of existing manholes and/or valve boxes and meter boxes, to pave over those devices, return after paving operations are completed, and adjust same to finished surface grade.*

*Adjustment to manholes, meter boxes, and valve boxes on this project shall be made by the use of an approved Black Tinted Concrete that will take a full set and become load bearing within sixty minutes of placement. A list of approved materials will be furnished to the Contractor by the Resident Engineer upon request.*

*The Contractor shall replace worn manhole rings and covers, worn meter box frames and covers, and worn valve box frames and covers, as directed by the Engineer, with a new ring/frame and cover assembly. These assemblies will be furnished, at no cost to the Contractor, by the Department or utility owner.*

*Basis of payment will be under "Adjustment of Manholes", or "Adjustment of Meter Boxes or Valve Boxes", per each.*

**AGGREGATE PRODUCTION:**

(11-20-01) (Rev. 11-21-06)

R10 R05

Provide aggregate from a producer who uses the current Aggregate Quality Control/Quality Assurance Program which is in effect at the time of shipment.

No price adjustment is allowed to contractors or producers who use the program. Participation in the program does not relieve the producer of the responsibility of complying with all requirements of the *2006 Standard Specifications*. Copies of this procedure are available upon request from the Materials and Test Unit.

**CONCRETE BRICK AND BLOCK PRODUCTION:**

(11-20-01) (Rev. 11-21-06)

R10 R10

Provide concrete brick and block from a producer who uses the current Solid Concrete Masonry Brick/Unit Quality Control/Quality Assurance Program that is in effect on the date that material is received on the project.

No price adjustment is allowed to contractors or producers who use the program. Participation in the program does not relieve the producer of the responsibility of complying with all requirements of the *2006 Standard Specifications*. Copies of this procedure are available upon request from the Materials and Test Unit.

**PORTLAND CEMENT CONCRETE (Alkali-Silica Reaction):**

2-20-07

R10 R16

Revise the *2006 Standard Specifications* as follows:

**Article 1024-1(A)**, replace the 2nd paragraph with the following:

Certain combinations of cement and aggregate exhibit an adverse alkali-silica reaction. The alkalinity of any cement, expressed as sodium-oxide equivalent, shall not exceed 1.0 percent. For mix designs that contain non-reactive aggregates and cement with an alkali content less than 0.6%, straight cement or a combination of cement and fly ash, cement and ground granulated blast furnace slag or cement and microsilica may be used. The pozzolan quantity shall not exceed the amount shown in Table 1024-1. For mixes that contain cement with an alkali content between 0.6% and 1.0%, and for mixes that contain a reactive aggregate documented by the Department, regardless of the alkali content of the cement, use a pozzolan in the amount shown in Table 1024-1.

Obtain the list of reactive aggregates documented by the Department at:<http://www.ncdot.org/doh/operations/materials/pdf/quarryasrprob.pdf>

<i>Pozzolan</i>	<i>Rate</i>
Class F Fly Ash	20% by weight of required cement content, with 1.2 lbs Class F fly ash per lb of cement replaced
Ground Granulated Blast Furnace Slag	35%-50% by weight of required cement content with 1 lb slag per lb of cement replaced
Microsilica	4%-8% by weight of required cement content, with 1 lb microsilica per lb of cement replaced

**GLASS BEADS:**

(7-18-06)

R10 R35

Revise the *2006 Standard Specifications* as follows:

**Page 10-223, 1087-4(C) Gradation & Roundness**

Replace the second sentence of the first paragraph with the following:

*All Drop-On and Intermixed Glass Beads shall be tested in accordance with ASTM D1155.*

Delete the last paragraph.

**CHANGEABLE MESSAGE SIGNS**

(11-21-06)

R11 R11

Revise the *2006 Standard Specifications* as follows:

**Page 11-9, Article 1120-3, Replace the 3rd sentence with the following:**

Sign operator will adjust flash rate so that no more than two messages will be displayed and be legible to a driver when approaching the sign at the posted speed.

**PAVEMENT MARKING LINES:**

(11-21-06) (Rev. 9-18-07)

RR12R01

Revise the *2006 Standard Specifications* as follows:

**Page 12-2, 1205-3(D) Time Limitations for Replacement**, add the following at the beginning of the chart:

Facility Type	Marking Type	Replacement Deadline
Full-control-of-access multi-lane roadway (4 or more total lanes) and ramps, including Interstates	All markings including symbols	By the end of each workday's operation if the lane is opened to traffic

**Page 12-14, Subarticle 1205-10, Measurement and Payment**, delete the first sentence of the first paragraph and replace with the following:

*Pavement Marking Lines* will be measured and paid for as the actual number of linear feet of pavement marking lines per application that has been satisfactorily placed and accepted by the Engineer.