

County : Davie

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0264000000-E	SP	GENERIC GRADING ITEM SHOULDER DROP OFF REPAIR	6.9	SMI	
0003	1220000000-E	545	INCIDENTAL STONE BASE	787	TON	
0004	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (2")	160	SY	
0005	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 1-1/2")	11,383	SY	
0006	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 2")	1,084	SY	
0007	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	6,697	TON	
0008	1520000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE S9.5B (LEVELING COURSE)	70	TON	
0009	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	24,360	TON	
0010	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	408	TON	
0011	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	1,461	TON	
0012	1704000000-E	SP	PATCHING EXISTING PAVEMENT	235	TON	
0013	2830000000-N	858	ADJUSTMENT OF MANHOLES	15	EA	
0014	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	9	EA	
0015	4510000000-N	SP	POLICE	20	HR	
0016	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	185,157	LF	

County : Davie

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0017	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	227,205	LF	
0018	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	686	LF	
0019	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	20	EA	
0020	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	95	EA	
0021	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	1,600	LF	
0022	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	672	EA	
1201/Sep28/Q462131.9/D58215100000/E22			Total Amount Of Bid For Entire Project :			

Contract No: C201908

County: Davie

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General