

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0022000000-E	225	UNCLASSIFIED EXCAVATION	1,700 CY		
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (21+01.50)	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0006	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0007	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	100 TON		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	2 CY		
0009	0195000000-E	265	SELECT GRANULAR MATERIAL	100 CY		
0010	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	100 SY		
0011	0199000000-E	SP	TEMPORARY SHORING	245 SF		
0012	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	74 TON		
0013	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	520 LF		
0014	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	20 LF		
0015	0390000000-E	310	36" RC PIPE CULVERTS, CLASS III	136 LF		
0016	0995000000-E	340	PIPE REMOVAL	106 LF		
0017	1220000000-E	545	INCIDENTAL STONE BASE	250 TON		
0018	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO *****" DEPTH (0" TO 1-1/2")	3,830 SY		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	490 TON		
0020	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	330 TON		
0021	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	630 TON		
0022	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	75 TON		
0023	2022000000-E	815	SUBDRAIN EXCAVATION	44.8 CY		
0024	2033000000-E	815	SUBDRAIN FINE AGGREGATE	33.6 CY		
0025	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	200 LF		
0026	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	6 EA		
0027	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0028	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0029	2190000000-N	828	TEMPORARY STEEL PLATE COVERS FOR MASONRY DRAINAGE STRUCTURE	5 EA		
0030	2253000000-E	840	PIPE COLLARS	0.84 CY		
0031	2264000000-E	840	PIPE PLUGS	0.25 CY		
0032	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	18 EA		
0033	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	9.1 LF		
0034	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	2 EA		
0035	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0036	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	2 EA		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	4 EA		
0038	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	5 EA		
0039	2396000000-N	840	FRAME WITH COVER, STD 840.54	3 EA		
0040	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	1,500 LF		
0041	2591000000-E	848	4" CONCRETE SIDEWALK	350 SY		
0042	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	3 EA		
0043	2612000000-E	848	6" CONCRETE DRIVEWAY	120 SY		
0044	3030000000-E	862	STEEL BM GUARDRAIL	37.5 LF		
0045	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	50 LF		
0046	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0047	3180000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** (TYPE III, SHOP CURVED)	1 EA		
0048	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		
0049	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	1 EA		
0050	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	1 EA		
0051	3345000000-E	864	REMOVE & RESET EXISTING GUARD- RAIL	156.25 LF		
0052	3360000000-E	863	REMOVE EXISTING GUARDRAIL	225 LF		
0053	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	100 LF		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (III)	2 EA		
0055	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	2 EA		
0056	3628000000-E	876	RIP RAP, CLASS I	15 TON		
0057	3649000000-E	876	RIP RAP, CLASS B	8 TON		
0058	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	730 SY		
0059	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	581 SF		
0060	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	444 SF		
0061	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	120 SF		
0062	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	2 EA		
0063	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	3 EA		
0064	4430000000-N	1130	DRUMS	67 EA		
0065	4435000000-N	1135	CONES	131 EA		
0066	4445000000-E	1145	BARRICADES (TYPE III)	154 LF		
0067	4450000000-N	1150	FLAGGER	2,736 HR		
0068	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	4 EA		
0069	4470000000-N	1160	RESET TEMPORARY CRASH CUSHIONS	2 EA		
0070	4480000000-N	1165	TMIA	2 EA		
0071	4485000000-E	1170	PORTABLE CONCRETE BARRIER	440 LF		
0072	4490000000-E	1170	PORTABLE CONCRETE BARRIER (ANCHORED)	360 LF		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0073	4495000000-E	1170	PORTABLE CONCRETE BARRIER (DRAINAGE)	260	LF	
0074	4510000000-N	SP	POLICE	50	HR	
0075	4516000000-N	1180	SKINNY DRUM	131	EA	
0076	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	316	EA	
0077	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (IV)	912	LF	
0078	4805000000-N	1205	COLD APPLIED PLASTIC PAVEMENT MARKING SYMBOL, TYPE ** (IV)	5	EA	
0079	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	18,125	LF	
0080	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	212	LF	
0081	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	242	LF	
0082	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	24	EA	
0083	4847000000-E	1205	POLYUREA PAVEMENT MARKING LINES (4", *****) (STANDARD GLASS BEADS)	3,345	LF	
0084	4847110000-E	1205	POLYUREA PAVEMENT MARKING LINES (8", *****) (STANDARD GLASS BEADS)	232	LF	
0085	4847140000-E	1205	POLYUREA PAVEMENT MARKING LINES (24", *****) (STANDARD GLASS BEADS)	74	LF	
0086	4847220000-N	1205	POLYUREA PAVEMENT MARKING SYMBOL (*****) (STANDARD GLASS BEADS)	17	EA	
0087	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	7,899	LF	
0088	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	24	LF	

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0089	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	73 EA		
0090	5648000000-N	1515	RELOCATE WATER METER	3 EA		
0091	5672000000-N	1515	RELOCATE FIRE HYDRANT	1 EA		
0092	6000000000-E	1605	TEMPORARY SILT FENCE	1,630 LF		
0093	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	115 TON		
0094	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	125 TON		
0095	6012000000-E	1610	SEDIMENT CONTROL STONE	375 TON		
0096	6015000000-E	1615	TEMPORARY MULCHING	0.5 ACR		
0097	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0098	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.25 TON		
0099	6029000000-E	SP	SAFETY FENCE	350 LF		
0100	6030000000-E	1630	SILT EXCAVATION	330 CY		
0101	6036000000-E	1631	MATTING FOR EROSION CONTROL	550 SY		
0102	6042000000-E	1632	1/4" HARDWARE CLOTH	380 LF		
0103	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	70 SY		
0104	6070000000-N	SP	SPECIAL STILLING BASINS	10 EA		
0105	6071030000-E	SP	COIR FIBER BAFFLES	90 LF		
0106	6084000000-E	1660	SEEDING & MULCHING	0.67 ACR		
0107	6087000000-E	1660	MOWING	0.5 ACR		
0108	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0109	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0110	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0111	6108000000-E	1665	FERTILIZER TOPDRESSING	0.25 TON		
0112	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
0113	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	8 EA		
WALL ITEMS						
0114	8436000000-E	453	GRAVITY RETAINING WALLS	210 SF		
STRUCTURE ITEMS						
0115	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (21+01.50-L-)	Lump Sum	L.S.	
0116	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (21+01.50-L-)	Lump Sum	L.S.	
0117	8105540000-E	SP	3'-6" DIA DRILLED PIERS IN SOIL	70 LF		
0118	8105640000-E	SP	3'-6" DIA DRILLED PIERS NOT IN SOIL	35 LF		
0119	8111400000-E	SP	PERMANENT STEEL CASING FOR 3'-6" DIA DRILLED PIER	75 LF		
0120	8113000000-N	SP	SID INSPECTION	1 EA		
0121	8115000000-N	SP	CROSSHOLE SONIC LOGGING	1 EA		
0122	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (21+01.50-L-)	Lump Sum	L.S.	

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0123	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	9,744 SF		
0124	8161000000-E	420	GROOVING BRIDGE FLOORS	9,888 SF		
0125	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	146.1 CY		
0126	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (21+01.50-L-)	Lump Sum	L.S.	
0127	8217000000-E	425	REINFORCING STEEL (BRIDGE)	27,384 LB		
0128	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	2,864 LB		
0129	8280000000-E	440	APPROX LBS STRUCTURAL STEEL	215,300 LS		
0130	8364000000-E	450	HP12X53 STEEL PILES	640 LF		
0131	8475000000-E	460	TWO BAR METAL RAIL	233.72 LF		
0132	8517000000-E	460	1'-***X ***** CONCRETE PARA- PET (1'-2" X 3'-3 7/16")	249.56 LF		
0133	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	447 TON		
0134	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	497 SY		
0135	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0136	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	

1351/Oct11/Q321532.14/D588441280000/E136

Total Amount Of Bid For Entire Project :

Contract No: C201564

County: Guilford

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General