

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0264000000-E	SP	GENERIC GRADING ITEM SHOULDER DROP OFF REPAIR	12.42	SMI	
0003	1220000000-E	545	INCIDENTAL STONE BASE	1,242	TON	
0004	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	1,592	SY	
0005	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 1-1/2")	3,477	SY	
0006	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	20,522	TON	
0007	1520000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE S9.5B (LEVELING COURSE)	438	TON	
0008	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	20,225	TON	
0009	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	1,261	TON	
001C	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	1,261	TON	
0011	1704000000-E	SP	PATCHING EXISTING PAVEMENT	150	TON	
0012	4510000000-N	SP	POLICE	20	HR	
0013	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	332,067	LF	
0014	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	351,322	LF	
001E	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	243	LF	
001E	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	307	LF	

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0017	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	10	EA	
001E	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	29	EA	
001E	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	598	EA	
1521/Sep28/Q734777.42/D51117100000/E19			Total Amount Of Bid For Entire Project :			

Contract No: C201909

County: Rowan

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General