

County : Wilkes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0022000000-E	225	UNCLASSIFIED EXCAVATION	165,000 CY		
0003	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	2 ACR		
0004	0057000000-E	226	UNDERCUT EXCAVATION	300 CY		
0005	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0006	0080000000-E	SP	CLASS IV SUBGRADE STABILIZATION	100 TON		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	60,100 CY		
0008	0141000000-E	240	BERM DITCH CONSTRUCTION	310 LF		
0009	0195000000-E	265	SELECT GRANULAR MATERIAL	100 CY		
0010	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	100 SY		
0011	0234000000-E	SP	GENERIC GRADING ITEM ENGINEERED SOIL MIX	2,163 CY		
0012	0241000000-E	SP	GENERIC GRADING ITEM GEOTEXTILE FABRIC	40,700 SY		
0013	0241000000-E	SP	GENERIC GRADING ITEM POLYPROPLENE WOVEN MONOFILA- MENT GEOTEXTILE FABRIC	22,500 SY		
0014	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	530 TON		
0015	0536000000-E	SP	**** HDPE PIPE CULVERTS (6")	160 LF		
0016	0684000000-E	310	*** BIT COAT CS PIPE CULVERTS, TYPE B ***** THICK (8", 0.064")	264 LF		
0017	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	588 LF		
0018	0714000000-E	310	18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	108 LF		

County : Wilkes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0732000000-E	310	36" BIT COAT CS PIPE CULVERTS, TYPE B 0.079" THICK	44 LF		
0020	0738000000-E	310	42" BIT COAT CS PIPE CULVERTS, TYPE B 0.109" THICK	40 LF		
0021	0744000000-E	310	48" BIT COAT CS PIPE CULVERTS, TYPE B 0.109" THICK	48 LF		
0022	0756000000-E	310	60" BIT COAT CS PIPE CULVERTS, TYPE B 0.138" THICK	36 LF		
0023	0804000000-E	310	*** BIT COAT CS PIPE ELBOWS, TYPE B ***** THICK (36", 0.079")	2 EA		
0024	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	14 EA		
0025	0807000000-E	310	18" BIT COAT CS PIPE ELBOWS, T YPE B 0.064" THICK	2 EA		
0026	0986000000-E	SP	GENERIC PIPE ITEM 6" HDPE PIPE CULVERTS, PERFOR- ATED	660 LF		
0027	0992000000-E	SP	GENERIC PIPE ITEM 6" 45 DEG ELBOWS HDPE	14 EA		
0028	0992000000-E	SP	GENERIC PIPE ITEM 6" CAPS HDPE	7 EA		
0029	0992000000-E	SP	GENERIC PIPE ITEM 6" COUPLERS HDPE	9 EA		
0030	0992000000-E	SP	GENERIC PIPE ITEM 6" Y JOINT HDPE	4 EA		
0031	0995000000-E	340	PIPE REMOVAL	374 LF		
0032	1077000000-E	SP	#57 STONE	950 TON		
0033	1121000000-E	520	AGGREGATE BASE COURSE	11,800 TON		
0034	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0035	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	3,950 TON		

County : Wilkes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	5,000 TON		
0037	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	3,700 TON		
0038	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	630 TON		
0039	2000000000-N	806	RIGHT OF WAY MARKERS	15 EA		
0040	2022000000-E	815	SUBDRAIN EXCAVATION	44.8 CY		
0041	2033000000-E	815	SUBDRAIN FINE AGGREGATE	33.6 CY		
0042	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	200 LF		
0043	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	6 EA		
0044	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0045	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0046	2209000000-E	838	ENDWALLS	1.5 CY		
0047	2253000000-E	840	PIPE COLLARS	2.85 CY		
0048	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	51 EA		
0049	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	48.57 LF		
0050	2352000000-N	840	FRAME WITH GRATE, STD 840.**** (840.20)	12 EA		
0051	2354000000-N	840	FRAME WITH GRATE, STD 840.22	8 EA		
0052	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	2 EA		
0053	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	4 EA		

County : Wilkes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	4 EA		
0055	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	10 EA		
0056	2396000000-N	840	FRAME WITH COVER, STD 840.54	5 EA		
0057	2462000000-E	SP	*** SLUICE GATE (24")	2 EA		
0058	2473000000-N	SP	GENERIC DRAINAGE ITEM RETICULINE FRAME & GRATE	4 EA		
0059	2535000000-E	846	***X *** CONCRETE CURB (6" X 12")	80.5 LF		
0060	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	5,600 LF		
0061	2556000000-E	846	SHOULDER BERM GUTTER	2,660 LF		
0062	2591000000-E	848	4" CONCRETE SIDEWALK	1,253 SY		
0063	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	3 EA		
0064	2612000000-E	848	6" CONCRETE DRIVEWAY	460 SY		
0065	2619000000-E	850	4" CONCRETE PAVED DITCH	11 SY		
0066	3030000000-E	862	STEEL BM GUARDRAIL	2,650 LF		
0067	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	37.5 LF		
0068	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
0069	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		
0070	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	2 EA		
0071	3360000000-E	863	REMOVE EXISTING GUARDRAIL	1,930 LF		

County : Wilkes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	3503000000-E	866	WOVEN WIRE FENCE, 47" FABRIC	4,910 LF		
0073	3509000000-E	866	4" TIMBER FENCE POSTS, 7'-6" LONG	310 EA		
0074	3515000000-E	866	5" TIMBER FENCE POSTS, 8'-0" LONG	80 EA		
0075	3628000000-E	876	RIP RAP, CLASS I	700 TON		
0076	3635000000-E	876	RIP RAP, CLASS II	320 TON		
0077	3642000000-E	876	RIP RAP, CLASS A	55 TON		
0078	3649000000-E	876	RIP RAP, CLASS B	330 TON		
0079	3651000000-E	SP	BOULDERS	60 TON		
0080	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	4,150 SY		
0081	4048000000-E	902	REINFORCED CONCRETE SIGN FOUN- DATIONS	4 CY		
0082	4060000000-E	903	SUPPORTS, BREAKAWAY STEEL BEAM	986 LB		
0083	4066000000-E	903	SUPPORTS, SIMPLE STEEL BEAM	2,398 LB		
0084	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	352 LF		
0085	4078000000-E	903	SUPPORTS, 2-LB STEEL U-CHANNEL	1 EA		
0086	4096000000-N	904	SIGN ERECTION, TYPE D	1 EA		
0087	4102000000-N	904	SIGN ERECTION, TYPE E	21 EA		
0088	4110000000-N	904	SIGN ERECTION, TYPE *** (GROUND MOUNTED) (A)	4 EA		
0089	4114000000-N	904	SIGN ERECTION, MILEMARKERS	1 EA		
0090	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (A)	2 EA		

County : Wilkes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0091	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (B)	1 EA		
0092	4138000000-N	907	DISPOSAL OF SUPPORT, STEEL BEAM	2 EA		
0093	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	1 EA		
0094	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	112 SF		
0095	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96 SF		
0096	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	20 SF		
0097	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	1 EA		
0098	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	1 EA		
0099	4430000000-N	1130	DRUMS	125 EA		
0100	4445000000-E	1145	BARRICADES (TYPE III)	24 LF		
0101	4480000000-N	1165	TMIA	1 EA		
0102	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	3,911 LF		
0103	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	2,343 LF		
0104	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	218 LF		
0105	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	9 EA		
0106	4847100000-E	1205	POLYUREA PAVEMENT MARKING LINES (6", *****) (STANDARD GLASS BEADS)	4,339 LF		
0107	4847120000-E	1205	POLYUREA PAVEMENT MARKING LINES (12", *****) (STANDARD GLASS BEADS)	672 LF		

County : Wilkes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0108	4847220000-N	1205	POLYUREA PAVEMENT MARKING SYMBOL (***** (STANDARD GLASS BEADS)	3 EA		
0109	4855000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (6")	1,000 LF		
0110	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	91 EA		
0111	5070000000-N	1405	STANDARD FOUNDATION ***** (R1)	29 EA		
0112	5155000000-E	1409	ELECTRICAL DUCT, TYPE BD, SIZE ***** (2")	60 LF		
0113	5155000000-E	1409	ELECTRICAL DUCT, TYPE BD, SIZE ***** (3")	135 LF		
0114	5155000000-E	1409	ELECTRICAL DUCT, TYPE BD, SIZE ***** (4")	45 LF		
0115	5185000000-E	1410	** #2 W/G FEEDER CIRCUIT (2)	140 LF		
0116	5205000000-E	1410	** #8 W/G FEEDER CIRCUIT IN ***** CONDUIT (2, 1-1/2")	1,880 LF		
0117	5215000000-E	1410	** #4 W/G FEEDER CIRCUIT IN ***** CONDUIT (2, 1-1/2")	775 LF		
0118	5220000000-E	1410	** #2 W/G FEEDER CIRCUIT IN ***** CONDUIT (2, 1-1/2")	3,615 LF		
0119	5240000000-N	1411	ELECTRICAL JUNCTION BOXES ***** (PC12)	4 EA		
0120	5240000000-N	1411	ELECTRICAL JUNCTION BOXES ***** (PC18)	9 EA		
0121	5240000000-N	1411	ELECTRICAL JUNCTION BOXES ***** (PC30)	2 EA		

County : Wilkes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0122	5260000000-N	SP	GENERIC LIGHTING ITEM LOW VOLTAGE LIGHT SYSTEM	Lump Sum	L.S.	
0123	5270000000-N	SP	GENERIC LIGHTING ITEM DAVIT STYLE LIGHT STANDARD, MH 35' SA 6'	29 EA		
0124	5270000000-N	SP	GENERIC LIGHTING ITEM LGT STD LUMINAIRE, 250W, HPS, TYPE C2	21 EA		
0125	5270000000-N	SP	GENERIC LIGHTING ITEM LGT STD LUMINAIRE, 250W, HPS, TYPE C3	8 EA		
0126	5270000000-N	SP	GENERIC LIGHTING ITEM LIGHT CONTROL EQUIPMENT, TYPE RA 120/208V 80A	1 EA		
0127	5270000000-N	SP	GENERIC LIGHTING ITEM POST TOP LGT STD	23 EA		
0128	5270000000-N	SP	GENERIC LIGHTING ITEM POST TOP LUMINAIRE, 100W, MH, TYPE C3	11 EA		
0129	5270000000-N	SP	GENERIC LIGHTING ITEM POST TOP LUMINAIRE, 100W, MH, TYPE C5	12 EA		
0130	5270000000-N	SP	GENERIC LIGHTING ITEM STD FOUNDATION, TYPE R1S	23 EA		
0131	6000000000-E	1605	TEMPORARY SILT FENCE	3,500 LF		
0132	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	300 TON		
0133	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	1,085 TON		
0134	6012000000-E	1610	SEDIMENT CONTROL STONE	665 TON		
0135	6015000000-E	1615	TEMPORARY MULCHING	20 ACR		
0136	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	400 LB		
0137	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1.75 TON		

County : Wilkes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0138	6024000000-E	1622	TEMPORARY SLOPE DRAINS	900 LF		
0139	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	14 EA		
0140	6029000000-E	SP	SAFETY FENCE	1,050 LF		
0141	6030000000-E	1630	SILT EXCAVATION	7,210 CY		
0142	6036000000-E	1631	MATTING FOR EROSION CONTROL	5,600 SY		
0143	6037000000-E	SP	COIR FIBER MAT	115 SY		
0144	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	1,685 SY		
0145	6042000000-E	1632	1/4" HARDWARE CLOTH	750 LF		
0146	6071030000-E	SP	COIR FIBER BAFFLES	630 LF		
0147	6071050000-E	SP	*** SKIMMER (1-1/2")	5 EA		
0148	6071050000-E	SP	*** SKIMMER (2-1/2")	4 EA		
0149	6071050000-E	SP	*** SKIMMER (5")	1 EA		
0150	6084000000-E	1660	SEEDING & MULCHING	18 ACR		
0151	6087000000-E	1660	MOWING	6.5 ACR		
0152	6090000000-E	1661	SEED FOR REPAIR SEEDING	100 LB		
0153	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0154	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	275 LB		
0155	6102000000-E	1664	SODDING	3,860 SY		
0156	6108000000-E	1665	FERTILIZER TOPDRESSING	13 TON		
0157	6114000000-N	SP	SPECIALIZED HAND MOWING	5.5 HR		

County : Wilkes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0158	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	54 EA		
0159	6135000000-E	SP	GENERIC EROSION CONTROL ITEM NATIVE GRASS APPLICATION	6.3 ACR		
0160	6210000000-N	1670	ACER RUBRUM, RED MAPLE, 2-2 1/2 " CAL., B&B	20 EA		
0161	6210000000-N	1670	ACER RUBRUM, RED MAPLE, 6-8', MIN. 3/4" CAL., B&B OR CONT.	14 EA		
0162	6215000000-N	1670	ACER SACCHARUM, SUGAR MAPLE, 2-2 1/2 " CAL., B&B	12 EA		
0163	6215000000-N	1670	ACER SACCHARUM, SUGAR MAPLE, 6-8', MIN. 3/4" CAL., B&B OR CONT.	14 EA		
0164	6245000000-N	1670	CERCIS CANADENSIS, REDBUD, 3-4' B&B OR CONT.	7 EA		
0165	6245000000-N	1670	CERCIS CANADENSIS, REDBUD, 5-6', B&B OR CONT.	8 EA		
0166	6255000000-N	1670	CHIONANTHUS VIRGINICUS, FRINGE TREE, 3-4' B&B OR CONT.	3 EA		
0167	6305000000-N	1670	FAGUS GRANDIFOLIA, AMERICAN BEECH, 6-8', MIN. 3/4" CAL., B&B OR CONT.	12 EA		
0168	6335000000-N	1670	HALESIA CAROLINA, CAROLINA SILVERBELL, 6-8', MIN. 3/4" CAL., B&B OR CONT.	31 EA		
0169	6380000000-N	1670	ILEX OPACA, AMERICAN HOLLY, 4-5', N	20 EA		
0170	6410000000-N	1670	JUNIPERUS VIRGINIANA, EASTERN RED CEDAR, 3-4' LS	20 EA		
0171	6410000000-N	1670	JUNIPERUS VIRGINIANA, EASTERN RED CEDAR, 6-7', B&B, LS	14 EA		

County : Wilkes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0172	6445000000-N	1670	LIQUIDAMBAR STYRACIFLUA, SWEETGUM, 'ROTUNDILOBA' 2-2 1/2 " CAL., B&B	12	EA	
0173	6445000000-N	1670	LIQUIDAMBAR STYRACIFLUA, SWEETGUM, 'ROTUNDILOBA' 6-8', MIN. 3/4" CAL., B&B OR CONT.	12	EA	
0174	6510000000-N	1670	OXYDENDRUM ARBOREUM, SOURWOOD, 1 1/2-2" CAL, B&B OR CONT	34	EA	
0175	6510000000-N	1670	OXYDENDRUM ARBOREUM, SOURWOOD, 5-6', B&B OR CONT.	38	EA	
0176	6555000000-N	1670	QUERCUS ALBA, WHITE OAK, 2-2 1/2 " CAL., B&B	3	EA	
0177	6560000000-N	1670	QUERCUS COCCINEA, SCARLET OAK, 1-1 1/4" CAL., B&B OR CONT.	13	EA	
0178	6575000000-N	1670	QUERCUS PHELLOS, WILLOW OAK, 1-1 1/4" CAL., B&B OR CONT.	17	EA	
0179	6640000000-N	1670	GENERIC PLANTING ITEM ABIES FRASERI, FRASER FIR 7-8', B&B, LS	3	EA	
0180	6640000000-N	1670	GENERIC PLANTING ITEM AMELANCHIER X GRANDIFLORA 'AUTUMN BRILLIANCE', 2-2 1/2 " CAL., B&B	11	EA	
0181	6640000000-N	1670	GENERIC PLANTING ITEM AMSONIA HUBRICHTII, WILLOW BLUESTAR 4" POT OR QT. CONT., -DEEP	68	EA	
0182	6640000000-N	1670	GENERIC PLANTING ITEM ANDROPOGON GLOMERATUS, BUSHY BLUESTEM, 2 1/4" SQ.POT, TRAY OF 32	286	EA	
0183	6640000000-N	1670	GENERIC PLANTING ITEM ANDROPOGON GLOMERATUS, BUSHY BLUESTEM, 3 1/2" - 4" POT, TRAY OF 18	12	EA	

County : Wilkes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0184	6640000000-N	1670	GENERIC PLANTING ITEM ANDROPOGON TENARIUS, SPLIT BEARD BROOMSEDGE, 2 1/4" SQ.POT, TRAY OF 32	256 EA		
0185	6640000000-N	1670	GENERIC PLANTING ITEM ARCTOSTAPHYLOS UVA-URSI 'MASS ACHUSETTS' KINNIKINNICK 12"MIN, #1CONT. MIN., N	18 EA		
0186	6640000000-N	1670	GENERIC PLANTING ITEM ARONIA ARBUTIFOLIA 'BRILLIANT- ISSIMA', RED CHOKEBERRY, 2-3', MIN. #3 CONT.	124 EA		
0187	6640000000-N	1670	GENERIC PLANTING ITEM ASCLEPIAS TUBEROSA, BUTTERFLY WEED 4" POT OR QT. CONT. -DEEP	288 EA		
0188	6640000000-N	1670	GENERIC PLANTING ITEM ASTER LAEVIS, SMOOTH BLUE ASTER 4" POT OR QT. CONT. -DEEP	75 EA		
0189	6640000000-N	1670	GENERIC PLANTING ITEM ASTER NOVAE-ANGLIAE, NEW ENGLAND ASTER 4" POT OR QT. CONT -DEEP	163 EA		
0190	6640000000-N	1670	GENERIC PLANTING ITEM BOLTONIA ASTEROIDES, FALSE ASTER 4" POT OR QT. CONT -DEEP	90 EA		
0191	6640000000-N	1670	GENERIC PLANTING ITEM CALLICARPA AMERICANA, BEAUTYBERRY, 2-3', MIN. #3 CONT	141 EA		
0192	6640000000-N	1670	GENERIC PLANTING ITEM CALYCANTHUS FLORIDUS, CAROLINA ALLSPICE 18-24", MIN. #3 CONT.	6 EA		
0193	6640000000-N	1670	GENERIC PLANTING ITEM CARPINUS CAROLINIANA, HORNBEAM 5-6', B&B OR CONT.	10 EA		
0194	6640000000-N	1670	GENERIC PLANTING ITEM CARYA OVATA, SHAGBARK HICKORY 6-8', MIN. 3/4" CAL., B&B OR CONT.	17 EA		

County : Wilkes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0195	6640000000-N	1670	GENERIC PLANTING ITEM CARYA TOMENTOSA, MOCKERNUT HICKORY 6-8', MIN. 3/4" CAL., B&B OR CONT.	11 EA		
0196	6640000000-N	1670	GENERIC PLANTING ITEM CEANOTHUS AMERICANUS, NEW JERSEY TEA 15-18", MIN. #3 CONT.	101 EA		
0197	6640000000-N	1670	GENERIC PLANTING ITEM CEPHALANTHUS OCCIDENTALIS 'SPUTNIK' BUTTONBUSH, 2-3', MIN. #3 CONT N	9 EA		
0198	6640000000-N	1670	GENERIC PLANTING ITEM CERCIS CANADENSIS 'FOREST PANSY' REDBUD 2-2 1/2" CAL., B&B	3 EA		
0199	6640000000-N	1670	GENERIC PLANTING ITEM CHASMANTHIUM LATIFOLIUM, RIVER OATS 2 1/4" SQ.POT, TRAY OF 32	160 EA		
0200	6640000000-N	1670	GENERIC PLANTING ITEM CHASMANTHIUM LATIFOLIUM, RIVER OATS 3 1/2" - 4" POT, TRAY OF 18	19 EA		
0201	6640000000-N	1670	GENERIC PLANTING ITEM CIMICIFUGA RACEMOSA, BUGBANE 4" POT OR QT. CONT. -DEEP	3 EA		
0202	6640000000-N	1670	GENERIC PLANTING ITEM CLETHRA ALNIFOLIA 'HUMMING- BIRD' SWEET PEPPERBUSH, 15-18", MIN. #3 CONT.	176 EA		
0203	6640000000-N	1670	GENERIC PLANTING ITEM CLETHRA ALNIFOLIA, SWEET PEPPERBUSH, 18-24", MIN. #3 CONT.	10 EA		
0204	6640000000-N	1670	GENERIC PLANTING ITEM COREOPSIS LANCEOLATA, TICKSEED 4" POT OR QT. CONT. -DEEP	90 EA		
0205	6640000000-N	1670	GENERIC PLANTING ITEM CORNUS FLORIDA 'CHEROKEE BRAVE' FLOWERING DOGWOOD 2-2 1/2 " CAL., B&B	3 EA		

County : Wilkes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0206	6640000000-N	1670	GENERIC PLANTING ITEM CORNUS FLORIDA 'CHEROKEE PRINCESS', FLOWERING DOGWOOD 2-2 1/2 " CAL., B&B	11 EA		
0207	6640000000-N	1670	GENERIC PLANTING ITEM CORNUS SERICEA 'CARDINAL' REDOSIER DOGWOOD 2-3', MIN. #3 CONT	9 EA		
0208	6640000000-N	1670	GENERIC PLANTING ITEM DESCHAMPSIA CESPITOSA, TUFTED HAIR GRASS 2 1/4" SQ.POT, TRAY OF 32	64 EA		
0209	6640000000-N	1670	GENERIC PLANTING ITEM DESCHAMPSIA CESPITOSA, TUFTED HAIR GRASS 3 1/2" - 4" POT, TRAY OF 18	15 EA		
0210	6640000000-N	1670	GENERIC PLANTING ITEM DIERVILLA SESSILIFOLIA 'BUTTER FLY', BUSH HONEYSUCKLE, 15-18", MIN. #3 CONT.	161 EA		
0211	6640000000-N	1670	GENERIC PLANTING ITEM DRYOPTERIS MARGINALIS, MARGINAL SHIELD FERN, 4" POT OR QT. CONT.-DEEP	17 EA		
0212	6640000000-N	1670	GENERIC PLANTING ITEM ECHINACEA PALLIDA, PALE PURPLE CONEFLOWER, 4" POT OR QT. CONT -DEEP	90 EA		
0213	6640000000-N	1670	GENERIC PLANTING ITEM ECHINACEA PURPUREA, PURPLE CONEFLOWER, 4" POT OR QT. CONT.-DEEP	411 EA		
0214	6640000000-N	1670	GENERIC PLANTING ITEM ECHINACEA PURPUREA, 'RUBY STAR' CONEFLOWER, 4" POT OR QT. CONT.-DEEP	27 EA		
0215	6640000000-N	1670	GENERIC PLANTING ITEM EUPATORIUM MACULATUM, JOE PYE WEED 4" POT OR QT. CONT.-DEEP	26 EA		
0216	6640000000-N	1670	GENERIC PLANTING ITEM FOTHERGILLA GARDENII, DWARF FOTHERGILLA, 15-18", MIN. #3 CONT.	11 EA		

County : Wilkes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0217	6640000000-N	1670	GENERIC PLANTING ITEM FRAXINUS AMERICANA, WHITE ASH 2-2 1/2 " CAL., B&B	4 EA		
0218	6640000000-N	1670	GENERIC PLANTING ITEM GAURA LINDHEIMERI, GAURA 4" POT OR QT. CONT. -DEEP	75 EA		
0219	6640000000-N	1670	GENERIC PLANTING ITEM HAMAMELIS VIRGINIANA, AUTUMN WITCH HAZEL 2-3', MIN. #3 CONT	15 EA		
0220	6640000000-N	1670	GENERIC PLANTING ITEM HELIANTHUS ANGUSTIFOLIUS SWAMP SUNFLOWER, 4" POT OR QT. CONT.	58 EA		
0221	6640000000-N	1670	GENERIC PLANTING ITEM HELIOPSIS HELIANTHOIDES FALSE SUNFLOWER, 4" POT OR QT. CONT.	78 EA		
0222	6640000000-N	1670	GENERIC PLANTING ITEM HYDRANGEA ARBORESCENS 'DARDOM' WHITE DOME HYDRANGEA, 15-18", MIN. #3 CONT.	147 EA		
0223	6640000000-N	1670	GENERIC PLANTING ITEM HYDRANGEA QUERCIFOLIA 'SIKES DWARF' OAKLEAF HYDRANGEA 18-24", MIN. #3 CONT.	2 EA		
0224	6640000000-N	1670	GENERIC PLANTING ITEM HYPERICUM FRONDOSUM 'SUNBURST' GOLDEN ST. JOHN'S WORT, 12-15", MIN. #1 CONT, N	284 EA		
0225	6640000000-N	1670	GENERIC PLANTING ITEM ILEX GLABRA 'DENSEA' INKBERRY HOLLY 15-18", MIN. #3 CONT., N	14 EA		
0226	6640000000-N	1670	GENERIC PLANTING ITEM ILEX VERTICILLATA 'RED SPRITE' WINTERBERRY 15-18", MIN. #3 CONT.	207 EA		
0227	6640000000-N	1670	GENERIC PLANTING ITEM ILEX VERTICILLATA 'WINTER RED' WINTERBERRY 18-24", MIN. #3 CONT.	17 EA		

County : Wilkes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0228	6640000000-N	1670	GENERIC PLANTING ITEM ILLICIAM FLORIDANUM, FLORIDA ANISE, 18-24", MIN. #3 CONT. N	21 EA		
0229	6640000000-N	1670	GENERIC PLANTING ITEM ITEA VIRGINICA 'HENRYS GARNET' VIRGINIA SWEETSPIRE, 15-18", MIN. #3 CONT.	191 EA		
0230	6640000000-N	1670	GENERIC PLANTING ITEM JUNCUS EFFUSUS, SOFT RUSH 2 1/4" SQ.POT, TRAY OF 32	450 EA		
0231	6640000000-N	1670	GENERIC PLANTING ITEM JUNCUS EFFUSUS, SOFT RUSH 3 1/2" - 4" POT, TRAY OF 18	19 EA		
0232	6640000000-N	1670	GENERIC PLANTING ITEM JUNIPERUS VIRGINIANA 'BRODIE' EASTERN RED CEDAR 5-6', LS	12 EA		
0233	6640000000-N	1670	GENERIC PLANTING ITEM KALMIA LATIFOLIA, MOUNTAIN LAUREL, 18-24", MIN. #3 CONT. N	54 EA		
0234	6640000000-N	1670	GENERIC PLANTING ITEM LEUCOTHOE FONTANESIANA DROOPING LEUCOTHOE 12-15", MIN. #1 CONT N	341 EA		
0235	6640000000-N	1670	GENERIC PLANTING ITEM LIRIODENDRON TULIPIFERA, TULIP POPLAR 2-2 1/2 " CAL., B&B	19 EA		
0236	6640000000-N	1670	GENERIC PLANTING ITEM LIRIODENDRON TULIPIFERA, TULIP POPLAR 6-8', MIN. 3/4" CAL., B&B OR CONT.	41 EA		
0237	6640000000-N	1670	GENERIC PLANTING ITEM MAGNOLIA ACUMINATA, CUCUMBER TREE 6-8', MIN. 3/4" CAL., B&B OR CONT.	10 EA		
0238	6640000000-N	1670	GENERIC PLANTING ITEM MONARDA DIDYMA, BEE-BALM 4" POT OR QT. CONT. -DEEP	92 EA		

County : Wilkes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0239	6640000000-N	1670	GENERIC PLANTING ITEM MONARDA FISTULOSA, WILD BERGAMOT 4" POT OR QT. CONT. -DEEP	90 EA		
0240	6640000000-N	1670	GENERIC PLANTING ITEM OSTRYA VIRGINIANA, HOPHORNBEAM 1 1/2-2" CAL, B&B OR CONT	17 EA		
0241	6640000000-N	1670	GENERIC PLANTING ITEM PANICUM VIRGATUM 'CLOUD NINE', SWITCHGRASS, 3 1/2" - 4" POT, TRAY OF 18	63 EA		
0242	6640000000-N	1670	GENERIC PLANTING ITEM PANICUM VIRGATUM 'HANSE HERMS' SWITCHGRASS, 3 1/2" - 4" POT, TRAY OF 18	11 EA		
0243	6640000000-N	1670	GENERIC PLANTING ITEM PANICUM VIRGATUM 'HEAVY METAL' SWITCHGRASS, 3 1/2" - 4" POT, TRAY OF 18	5 EA		
0244	6640000000-N	1670	GENERIC PLANTING ITEM PANICUM VIRGATUM 'SHENANDOAH' SWITCHGRASS, 3 1/2" - 4" POT, TRAY OF 18	7 EA		
0245	6640000000-N	1670	GENERIC PLANTING ITEM PANICUM VIRGATUM, SWITCHGRASS 2 1/4" SQ.POT, TRAY OF 32	128 EA		
0246	6640000000-N	1670	GENERIC PLANTING ITEM PHYSOCARPUS OPULIFOLIUS 'SUMMER WINE', NINEBARK, 15-18", MIN. #3 CONT.	110 EA		
0247	6640000000-N	1670	GENERIC PLANTING ITEM PHYSOSTEGIA VIRGINIANA, OBEDIENT PLANT, 4" POT OR QT. CONT.-DEEP	75 EA		
0248	6640000000-N	1670	GENERIC PLANTING ITEM PINUS STROBUS 'CONEY ISLAND', WHITE PINE 18-24", LS	1 EA		
0249	6640000000-N	1670	GENERIC PLANTING ITEM PINUS STROBUS, WHITE PINE 4-5', B&B, LS	29 EA		
0250	6640000000-N	1670	GENERIC PLANTING ITEM PINUS STROBUS, WHITE PINE 6-7', B&B, LS	16 EA		

County : Wilkes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0251	6640000000-N	1670	GENERIC PLANTING ITEM QUERCUS FALCATA, SOUTHERN RED OAK 2-2 1/2 " CAL., B&B	6 EA		
0252	6640000000-N	1670	GENERIC PLANTING ITEM QUERCUS IMBRICARIA, SHINGLE OAK, 6-8', MIN. 3/4" CAL., B&B OR CONT.	7 EA		
0253	6640000000-N	1670	GENERIC PLANTING ITEM QUERCUS LYRATA, OVERCUP OAK 1-1 1/4" CAL., B&B OR CONT.	4 EA		
0254	6640000000-N	1670	GENERIC PLANTING ITEM QUERCUS MACROCARPA, BUR OAK 1-1 1/4" CAL., B&B	4 EA		
0255	6640000000-N	1670	GENERIC PLANTING ITEM QUERCUS NUTTALLII, NUTTALL OAK 2-2 1/2 " CAL., B&B	25 EA		
0256	6640000000-N	1670	GENERIC PLANTING ITEM QUERCUS PRINUS, CHESTNUT OAK 2-2 1/2 " CAL., B&B	10 EA		
0257	6640000000-N	1670	GENERIC PLANTING ITEM RHODODENDRON CALENDULACEUM, FLAME AZALEA, MIN. #3 CONT.	28 EA		
0258	6640000000-N	1670	GENERIC PLANTING ITEM RHODODENDRON CATAWBIENSE, CATAWBA RHOD. 18-24", MIN. #3 CONT, N	159 EA		
0259	6640000000-N	1670	GENERIC PLANTING ITEM RHUS AROMATICA 'GRO-LOW' FRAGRANT SUMAC, 9-15", MIN. #1 CONT.	5 EA		
0260	6640000000-N	1670	GENERIC PLANTING ITEM RHUS GLABRA, SMOOTH SUMAC 9-15", MIN. #1 CONT.	102 EA		
0261	6640000000-N	1670	GENERIC PLANTING ITEM RUDBECKIA FULGIDA 'GOLDSTRUM' ORANGE CONEFLOWER, 4" POT OR QT. CONT.	20 EA		
0262	6640000000-N	1670	GENERIC PLANTING ITEM RUDBECKIA FULGIDA, ORANGE CONEFLOWER, 4" POT OR QT. CONT -DEEP	90 EA		

County : Wilkes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0263	6640000000-N	1670	GENERIC PLANTING ITEM RUDBECKIA SUBTOMENTOSA, SWEET BLACK-EYED SUSAN, 4" POT OR QT. CONT. -DEEP	78 EA		
0264	6640000000-N	1670	GENERIC PLANTING ITEM RUDBECKIA TRILOBA, BROWN-EYED SUSAN 4" POT OR QT. CONT. -DEEP	15 EA		
0265	6640000000-N	1670	GENERIC PLANTING ITEM SAMBUCUS CANADENSIS, AMERICAN ELDER 12-18", MIN. #1 CONT.	7 EA		
0266	6640000000-N	1670	GENERIC PLANTING ITEM SCHIZACHYRIUM SCOPARIUM 'THE BLUES' LITTLE BLUESTEM 3 1/2 - 4" POT 18 TRAY	45 EA		
0267	6640000000-N	1670	GENERIC PLANTING ITEM SCIRPUS CYPERINUS, WOOL GRASS 2 1/4" SQ.POT, TRAY OF 32	311 EA		
0268	6640000000-N	1670	GENERIC PLANTING ITEM SISYRINCHIUM ANGUSTIFOLIUM BLUE-EYED GRASS, 4" POT OR QT. CONT. -DEEP	45 EA		
0269	6640000000-N	1670	GENERIC PLANTING ITEM SOLIDAGO CANADENSIS, COMMON GOLDENROD 4" POT OR QT. CONT. -DEEP	197 EA		
0270	6640000000-N	1670	GENERIC PLANTING ITEM SOLIDAGO 'FIREWORKS', FIREWORKS GOLDENROD 4" POT OR QT. CONT. -DEEP	6 EA		
0271	6640000000-N	1670	GENERIC PLANTING ITEM SOLIDAGO RIGIDA, STIFF GOLDENROD 4" POT OR QT. CONT. -DEEP	75 EA		
0272	6640000000-N	1670	GENERIC PLANTING ITEM SORGHASTRUM NUTANS, INDIAN GRASS 2 1/4" SQ.POT, TRAY OF 32	128 EA		
0273	6640000000-N	1670	GENERIC PLANTING ITEM SORGHASTRUM NUTANS, INDIAN GRASS 3 1/2" - 4" POT, TRAY OF 18	45 EA		

County : Wilkes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0274	6640000000-N	1670	GENERIC PLANTING ITEM SPARTINA BAKERI, CORD GRASS 2 1/4" SQ.POT, TRAY OF 32	206	EA	
0275	6640000000-N	1670	GENERIC PLANTING ITEM SPOROBOLIS HETEROLEPIS, PRAIRIE DROPSEED, 2 1/4" SQ.POT, TRAY OF 32	1,444	EA	
0276	6640000000-N	1670	GENERIC PLANTING ITEM SPOROBOLIS HETEROLEPIS, PRAIRIE DROPSEED, 3 1/2" - 4" POT, TRAY OF 18	11	EA	
0277	6640000000-N	1670	GENERIC PLANTING ITEM STEWARTIA OVATA, MOUNTAIN STEWARTIA, 5-6', B&B OR CONT.	1	EA	
0278	6640000000-N	1670	GENERIC PLANTING ITEM STYRAX AMERICANA, AMERICAN SNOWBELL 6-8', MIN. 3/4" CAL., B&B OR CONT.	1	EA	
0279	6640000000-N	1670	GENERIC PLANTING ITEM THUJA OCCIDENTALIS 'DEGROOT'S SPIRE' AMERICAN ARBORVITAE, 5-6', LS	2	EA	
0280	6640000000-N	1670	GENERIC PLANTING ITEM THUJA OCCIDENTALIS 'GOLDEN TUFFET' AMERICAN ARBORVITAE, 15-18", LS	3	EA	
0281	6640000000-N	1670	GENERIC PLANTING ITEM THUJA OCCIDENTALIS 'TECHY GOLD' AMERICAN ARBORVITAE, 5-6', LS	1	EA	
0282	6640000000-N	1670	GENERIC PLANTING ITEM THUJA OCCIDENTALIS, AMERICAN ARBORVITAE 6-7', B&B, LS	4	EA	
0283	6640000000-N	1670	GENERIC PLANTING ITEM TRADESCANTIA VIRGINIANA, VIRGINIA SPIDERWORT, 4" POT OR QT. CONT -DEEP	15	EA	
0284	6640000000-N	1670	GENERIC PLANTING ITEM TSUGA CANADENSIS 'COLE'S PROSTRATE' CANADIAN HEMLOCK 18-24", LS	3	EA	

County : Wilkes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0285	6640000000-N	1670	GENERIC PLANTING ITEM TSUGA CANADENSIS 'JEDDELOH' CANADIAN HEMLOCK 18-24", LS	1 EA		
0286	6640000000-N	1670	GENERIC PLANTING ITEM TSUGA CANADENSIS 'STOCKMAN'S DWARF' CANADIAN HEMLOCK 18-24", LS	2 EA		
0287	6640000000-N	1670	GENERIC PLANTING ITEM TSUGA CANADENSIS, CANADIAN HEMLOCK 3-4' LS	19 EA		
0288	6640000000-N	1670	GENERIC PLANTING ITEM TSUGA CANADENSIS, CANADIAN HEMLOCK 6-7', B&B, LS	8 EA		
0289	6640000000-N	1670	GENERIC PLANTING ITEM ULMUS ALATA, WINGED ELM 6-8', MIN. 3/4" CAL., B&B OR CONT.	13 EA		
0290	6640000000-N	1670	GENERIC PLANTING ITEM VERNONIA NOVEBORACENSIS, NEW YORK IRONWEED, 4" POT OR QT. CONT. -DEEP	107 EA		
0291	6640000000-N	1670	GENERIC PLANTING ITEM VIBURNUM ACERIFOLIUM, MAPLELEAF VIBURNUM, 18-24", MIN. #3 CONT	134 EA		
0292	6650000000-E	1670	MULCH FOR PLANTING	1,229 CY		
0293	6655000000-E	1670	WATER FOR PLANTING	186 M/G		
0294	6665000000-E	1670	POSTEMERGENT HERBICIDAL TREAT- MENT FOR PLANT BEDS	7,755 SY		
0295	6670000000-E	1670	PREEMERGENT HERBICIDAL TREAT- MENT FOR PLANT BEDS	7,755 SY		
0296	6677000000-E	SP	GENERIC PLANTING ITEM CREEK STONE FOR FOREBAY	110 TON		
0297	6677000000-E	SP	GENERIC PLANTING ITEM SPILLWAY CREEK STONE	54 TON		

County : Wilkes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0298	6680000000-E	SP	GENERIC PLANTING ITEM 12 MONTH AGED HARDWOOD MULCH	295 CY		
0299	6900000000-E	SP	TOPSOIL	343 CY		
0300	6905000000-N	SP	PICNIC TABLE, TERRAZZO & STEEL	5 EA		
0301	6910000000-N	SP	PICNIC SHELTER, SINGLE PICNIC TABLE	3 EA		
0302	6945000000-E	SP	3/4" POST TYPE YARD HYDRANT	4 EA		
0303	6970000000-N	SP	GENERIC REST AREA ITEM 1" GATE VALVE AND BOX	7 EA		
0304	6970000000-N	SP	GENERIC REST AREA ITEM 3" GATE VALVE AND BOX	1 EA		
0305	6970000000-N	SP	GENERIC REST AREA ITEM 3/4" GATE VALVE AND BOX	9 EA		
0306	6970000000-N	SP	GENERIC REST AREA ITEM 4" SANITARY SEWER CLEANOUT	4 EA		
0307	6970000000-N	SP	GENERIC REST AREA ITEM DEPRESSED CURB	4 EA		
0308	6970000000-N	SP	GENERIC REST AREA ITEM FLAGPOLE	1 EA		
0309	6970000000-N	SP	GENERIC REST AREA ITEM IRRIGATION HYDRANT	3 EA		
0310	6970000000-N	SP	GENERIC REST AREA ITEM LOG BENCH	7 EA		
0311	6970000000-N	SP	GENERIC REST AREA ITEM NATURE TRAIL LANDING CONSTRUCTION	5 EA		
0312	6970000000-N	SP	GENERIC REST AREA ITEM NATURE TRAIL STEPS	15 EA		
0313	6970000000-N	SP	GENERIC REST AREA ITEM PLACEMENT OF BOULDER OR LARGE FLAT STONE	189 EA		
0314	6970000000-N	SP	GENERIC REST AREA ITEM SPOT LIGHT	3 EA		

County : Wilkes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0315	6970000000-N	SP	GENERIC REST AREA ITEM TELEPHONE PEDESTAL	1 EA		
0316	6970000000-N	SP	GENERIC REST AREA ITEM TRASH RECEPTACLE	16 EA		
0317	6975000000-N	SP	GENERIC REST AREA ITEM ELECTRICAL INSTALLATION FOR THE REST AREA/VISITOR CENTER BUILDING	Lump Sum	L.S.	
0318	6975000000-N	SP	GENERIC REST AREA ITEM GEN. CONSTRUCTION OF REST AREA/VISITOR CENTER BUILDING	Lump Sum	L.S.	
0319	6975000000-N	SP	GENERIC REST AREA ITEM HVAC INSTALLATION FOR THE REST AREA/VISITOR CENTER BUILDING	Lump Sum	L.S.	
0320	6975000000-N	SP	GENERIC REST AREA ITEM LANDSCAPE GRADING	Lump Sum	L.S.	
0321	6975000000-N	SP	GENERIC REST AREA ITEM MAINTENANCE BUILDING	Lump Sum	L.S.	
0322	6975000000-N	SP	GENERIC REST AREA ITEM NATURE TRAIL CROSSING (TOTAL OF 4 CROSSINGS)	Lump Sum	L.S.	
0323	6975000000-N	SP	GENERIC REST AREA ITEM PLUMBING INSTALLATION FOR THE REST AREA/VISITOR CENTER BUILDING	Lump Sum	L.S.	
0324	6975000000-N	SP	GENERIC REST AREA ITEM SPECIAL REST AREA SIGNAGE	Lump Sum	L.S.	
0325	6975000000-N	SP	GENERIC REST AREA ITEM STONE RETAINING WALL	Lump Sum	L.S.	
0326	6975000000-N	SP	GENERIC REST AREA ITEM STORAGE BUILDING	Lump Sum	L.S.	
0327	6980000000-E	SP	GENERIC REST AREA ITEM 1" PVC WATER PIPE, SCH-80	1,874 LF		
0328	6980000000-E	SP	GENERIC REST AREA ITEM 1" SLEEVE FOR UNDERGROUND ELEC/PHONE SERVICE (SCH-40 PVC)	485 LF		

County : Wilkes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0329	6980000000-E	SP	GENERIC REST AREA ITEM 3" PVC WATER PIPE, SCH-80	152 LF		
0330	6980000000-E	SP	GENERIC REST AREA ITEM 3/4" PVC WATER PIPE, SCH-80	35 LF		
0331	6980000000-E	SP	GENERIC REST AREA ITEM 4" PVC DUCT	292 LF		
0332	6980000000-E	SP	GENERIC REST AREA ITEM 4" PVC/ABS -DWV, SCH 40 DRAIN PIPE	555 LF		
0333	6980000000-E	SP	GENERIC REST AREA ITEM 6" DUCTILE IRON GRAVITY SEWER	140 LF		
0334	6980000000-E	SP	GENERIC REST AREA ITEM 6" PVC (SDR-35) GRAVITY SEWER	89 LF		
0335	6980000000-E	SP	GENERIC REST AREA ITEM 6" PVC/ABS -DWV, SCH 40 DRAIN PIPE	96 LF		
0336	6980000000-E	SP	GENERIC REST AREA ITEM NATURE TRAIL CONSTRUCTION	2,985 LF		
0337	6980000000-E	SP	GENERIC REST AREA ITEM TREE PROTECTION FENCE	1,750 LF		
0338	6982000000-E	SP	GENERIC REST AREA ITEM COBBLESTONE WALKWAY	376 SF		

***** BEGIN SCHEDULE AA *****
 ***** (3 ALTERNATES) *****

0339 AA1	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	1,704 LF		
0340 AA1	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	1,380 LF		
0341 AA1	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	892 LF		
*** OR ***						
0342 AA2	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	208 LF		
0343 AA2	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	76 LF		

County : Wilkes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0344 AA2	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	104 LF		
0345 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (15")	1,496 LF		
0346 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (18")	1,304 LF		
0347 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (24")	788 LF		
*** OR ***						
0348 AA3	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	208 LF		
0349 AA3	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	76 LF		
0350 AA3	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	104 LF		
0351 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (15")	1,496 LF		
0352 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (18")	1,304 LF		
0353 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (24")	788 LF		
**** END SCHEDULE AA ****						
0354	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	

Contract No: C201679

County: Wilkes

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General