

County : Cumberland, Harnett

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	1220000000-E	545	INCIDENTAL STONE BASE	1,073 TON		
0003	1245000000-E	SP	SHOULDER RECONSTRUCTION	94.74 SMI		
0004	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 1")	34,109 SY		
0005	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 1-1/2")	65,125 SY		
0006	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 1-1/4")	1,484 SY		
0007	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	2,649 TON		
0008	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	33,953 TON		
0009	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	33,992 TON		
0010	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	4,361 TON		
0011	1704000000-E	SP	PATCHING EXISTING PAVEMENT	989 TON		
0012	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	2 EA		
0013	2830000000-N	858	ADJUSTMENT OF MANHOLES	200 EA		
0014	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	126 EA		
0015	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	129,850 LF		
0016	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	199,350 LF		
0017	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	2,075 LF		

County : Cumberland, Harnett

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	1,300 LF		
0019	4705000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (16", 120 MILS)	400 LF		
0020	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	1,580 LF		
0021	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	48 EA		
0022	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	590 EA		
0023	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	1,635,800 LF		
0024	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	25 LF		
0025	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	1,715 EA		
0026	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	2,880 EA		
0027	6084000000-E	1660	SEEDING & MULCHING	121.28 ACR		
0028	7288000000-E	1715	PAVED TRENCHING (*****) (1, 2")	90 LF		
0029	7300000000-E	1715	UNPAVED TRENCHING (*****) (1, 2")	550 LF		
0030	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	18 EA		
0031	7420000000-E	1722	2" RISER WITH WEATHERHEAD	18 EA		
0032	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	9,800 LF		
0033	7456000000-E	1726	LEAD-IN CABLE (*****) (14-2)	1,000 LF		
0034	7990000000-E	SP	GENERIC SIGNAL ITEM 1" PVC CONDUIT	270 LF		

County : Cumberland, Harnett

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035	7990000000-E	SP	GENERIC SIGNAL ITEM 2" PVC CONDUIT	500 LF		

0800/Nov06/Q2166139.02/D145836100000/E35

Total Amount Of Bid For Entire Project :

Contract No: C201947

County: Cumberland & Harnett

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General