

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (18+72.50-L-)	Lump Sum	L.S.	
0003	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0004	0057000000-E	226	UNDERCUT EXCAVATION	1,075 CY		
0005	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0006	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	150 TON		
0007	0106000000-E	230	BORROW EXCAVATION	3,700 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	250 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	250 SY		
001C	0343000000-E	310	15" SIDE DRAIN PIPE	72 LF		
0011	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	96 LF		
0012	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	64 LF		
0013	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	48 LF		
0014	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	84 LF		
001E	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	16 LF		
0016	0995000000-E	340	PIPE REMOVAL	53 LF		
0017	0996000000-N	350	PIPE CLEAN-OUT	1 EA		
001E	1121000000-E	520	AGGREGATE BASE COURSE	90 TON		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	1220000000-E	545	INCIDENTAL STONE BASE	500 TON		
002C	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	980 TON		
0021	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	760 TON		
0022	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	92 TON		
0023	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	12 TON		
0024	2000000000-N	806	RIGHT OF WAY MARKERS	29 EA		
002E	2022000000-E	815	SUBDRAIN EXCAVATION	22.4 CY		
002E	2033000000-E	815	SUBDRAIN FINE AGGREGATE	16.8 CY		
0027	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		
002E	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	3 EA		
002E	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
003C	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0031	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	6 EA		
0032	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	3 EA		
0033	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0034	2396000000-N	840	FRAME WITH COVER, STD 840.54	1 EA		
003E	2556000000-E	846	SHOULDER BERM GUTTER	79 LF		
003E	3030000000-E	862	STEEL BM GUARDRAIL	225 LF		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
003E	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
003E	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
004C	3360000000-E	863	REMOVE EXISTING GUARDRAIL	322 LF		
0041	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (W-BEAM)	1 EA		
0042	3628000000-E	876	RIP RAP, CLASS I	8 TON		
0043	3635000000-E	876	RIP RAP, CLASS II	190 TON		
0044	3649000000-E	876	RIP RAP, CLASS B	8 TON		
004E	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	890 SY		
004E	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	43 SF		
0047	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	110 LF		
004E	4102000000-N	904	SIGN ERECTION, TYPE E	8 EA		
004E	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	18 EA		
005C	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	700 SF		
0051	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	100 SF		
0052	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	150 SF		
0053	4430000000-N	1130	DRUMS	70 EA		
0054	4435000000-N	1135	CONES	40 EA		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	4445000000-E	1145	BARRICADES (TYPE III)	75 LF		
005E	4455000000-N	1150	FLAGGER	200 MD		
0057	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	1 EA		
005E	4485000000-E	1170	PORTABLE CONCRETE BARRIER	250 LF		
005E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	22,700 LF		
006C	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	100 LF		
0061	6000000000-E	1605	TEMPORARY SILT FENCE	1,200 LF		
0062	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	220 TON		
006E	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	305 TON		
0064	6012000000-E	1610	SEDIMENT CONTROL STONE	420 TON		
006E	6015000000-E	1615	TEMPORARY MULCHING	3 ACR		
006E	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0067	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.5 TON		
006E	6024000000-E	1622	TEMPORARY SLOPE DRAINS	65 LF		
006E	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	1 EA		
007C	6029000000-E	SP	SAFETY FENCE	285 LF		
0071	6030000000-E	1630	SILT EXCAVATION	2,315 CY		
0072	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,460 SY		
007E	6037000000-E	SP	COIR FIBER MAT	40 SY		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	2,750	SY	
0075	6042000000-E	1632	1/4" HARDWARE CLOTH	50	LF	
0076	6070000000-N	SP	SPECIAL STILLING BASINS	12	EA	
0077	6071030000-E	SP	COIR FIBER BAFFLES	660	LF	
007E	6071050000-E	SP	*** SKIMMER (1-1/2")	2	EA	
007E	6071050000-E	SP	*** SKIMMER (2")	1	EA	
008C	6071050000-E	SP	*** SKIMMER (2-1/2")	1	EA	
0081	6084000000-E	1660	SEEDING & MULCHING	3	ACR	
0082	6087000000-E	1660	MOWING	2	ACR	
0083	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	
0084	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
008E	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	75	LB	
008E	6108000000-E	1665	FERTILIZER TOPDRESSING	2.25	TON	
0087	6114000000-N	SP	SPECIALIZED HAND MOWING	2	HR	
008E	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12	EA	
008E	6123000000-E	1670	REFORESTATION	0.2	ACR	

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>STRUCTURE ITEMS</b>						
009C	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (18 + 72.50 -L- )	Lump Sum	L.S.	
0091	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (18 + 72.50 -L-)	Lump Sum	L.S.	
0092	8105540000-E	SP	3'-6" DIA DRILLED PIERS IN SOIL	17 LF		
0093	8105640000-E	SP	3'-6" DIA DRILLED PIERS NOT IN SOIL	42 LF		
0094	8111400000-E	SP	PERMANENT STEEL CASING FOR 3'-6" DIA DRILLED PIER	11.5 LF		
009E	8113000000-N	SP	SID INSPECTION	3 EA		
0096	8115000000-N	SP	CROSSHOLE SONIC LOGGING	1 EA		
0097	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	126.7 CY		
009E	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (18 + 72.50 -L-)	Lump Sum	L.S.	
009E	8217000000-E	425	REINFORCING STEEL (BRIDGE)	23,520 LB		
010C	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	2,416 LB		
0101	8364000000-E	450	HP12X53 STEEL PILES	140 LF		
0102	8391000000-N	450	STEEL PILE POINTS	14 EA		
0103	8503000000-E	460	CONCRETE BARRIER RAIL	388.83 LF		
0104	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	389 TON		
010E	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	432 SY		
010E	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0107	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	2,138.58 LF		

1517/Oct30/Q74469.01/D465171860000/E107

Total Amount Of Bid For Entire Project :

**Contract No: C201398**

**County: Guilford**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General