

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	1220000000-E	545	INCIDENTAL STONE BASE	198 TON		
0003	1245000000-E	SP	SHOULDER RECONSTRUCTION	8.44 SMI		
0004	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	17,452 SY		
000E	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/4")	19,882 SY		
000E	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (3")	6,486 SY		
0007	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 1-1/2")	12,389 SY		
000E	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 1-1/4")	8,049 SY		
000E	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 2-1/2")	902 SY		
001C	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 5/8")	4,440 SY		
0011	1330000000-E	607	INCIDENTAL MILLING	2,673 SY		
0012	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	1,382 TON		
0013	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	2,424 TON		
0014	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	11,890 TON		
001E	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	13,286 TON		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	1,068 TON		
0017	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	715 TON		
001E	1567000000-E	SP	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-28	362 TON		
001E	1704000000-E	SP	PATCHING EXISTING PAVEMENT	30 TON		
002C	1775000000-E	660	ASPHALT SURFACE TREATMENT, MAT COAT, #78M STONE	45,771 SY		
0021	1839110000-E	661	ULTRATHIN HOT MIX ASPHALT, TYPE B	6,258 TON		
0022	1839200000-E	661	APPLICATION OF ULTRATHIN HOT MIX ASPHALT	178,764 SY		
002E	2600000000-N	SP	RETROFIT EXISTING WHEELCHAIR RAMPS	98 EA		
0024	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	23 EA		
002E	2830000000-N	858	ADJUSTMENT OF MANHOLES	182 EA		
002E	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	125 EA		
0027	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	130,870 LF		
002E	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	119,300 LF		
002E	4688000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 90 MILS)	380 LF		
003C	4690000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 120 MILS)	669 LF		
0031	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	9,076 LF		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0032	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	3,445	LF	
0033	4700000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (12", 90 MILS)	148	LF	
0034	4702000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (12", 120 MILS)	1,176	LF	
003E	4705000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (16", 120 MILS)	50	LF	
003E	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	3,114	LF	
0037	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	74	EA	
003E	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	393	EA	
003E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	207,429	LF	
004C	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	761	EA	
0041	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	
0042	6084000000-E	1660	SEEDING & MULCHING	2.45	ACR	
0043	6110000000-E	SP	RESIDENTIAL SEEDING	1.11	ACR	
0044	7300000000-E	1715	UNPAVED TRENCHING (*****) (1, 2")	370	LF	
0045	7312000000-N	1716	JUNCTION BOX (*****) (STANDARD PULL BOX)	5	EA	
0046	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	18,031	LF	
0047	7456000000-E	1726	LEAD-IN CABLE (*****) (14-2)	450	LF	

Contract No: C201956

County: Guilford

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General