

County : Hoke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	1220000000-E	545	INCIDENTAL STONE BASE	305	TON	
0003	1245000000-E	SP	SHOULDER RECONSTRUCTION	17.35	SMI	
0004	1330000000-E	607	INCIDENTAL MILLING	528	SY	
0005	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	2,955	TON	
0006	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	14,021	TON	
0007	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	4,280	TON	
0008	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	406	TON	
0009	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	841	TON	
0010	1704000000-E	SP	PATCHING EXISTING PAVEMENT	361	TON	
0011	2830000000-N	858	ADJUSTMENT OF MANHOLES	1	EA	
0012	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	2	EA	
0013	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	111,010	LF	
0014	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	7,920	LF	
0015	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	440	LF	
0016	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	80	LF	
0017	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	170	LF	
0018	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	14	EA	

County : Hoke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	225 EA		
0020	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	129,636 LF		
0021	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	878 EA		
0022	6084000000-E	1660	SEEDING & MULCHING	9.95 ACR		
1356/Nov07/Q274101.3/D67549100000/E22			Total Amount Of Bid For Entire Project :			

Contract No: C201949

County: Hoke

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General