

County : Lincoln

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0005	0134000000-E	240	DRAINAGE DITCH EXCAVATION	40 CY		
0006	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	250 TON		
0007	0343000000-E	310	15" SIDE DRAIN PIPE	72 LF		
0008	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	504 LF		
0009	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	224 LF		
0010	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	492 LF		
0011	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	48 LF		
0012	0720000000-E	310	24" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	16 LF		
0013	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	4 EA		
0014	0808000000-E	310	24" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	2 EA		
0015	0995000000-E	340	PIPE REMOVAL	288 LF		
0016	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	2,287 TON		
0017	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE 119.0C	1,634 TON		

County : Lincoln

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	1539000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S12.5C	2,650 TON		
001E	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	180 TON		
002C	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	150 TON		
0021	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	40 TON		
0022	1704000000-E	SP	PATCHING EXISTING PAVEMENT	100 TON		
0023	2000000000-N	806	RIGHT OF WAY MARKERS	11 EA		
0024	2253000000-E	840	PIPE COLLARS	0.4 CY		
002E	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	37 EA		
002E	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	14 LF		
0027	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	7 EA		
002E	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	5 EA		
002E	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	9 EA		
003C	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	16 EA		
0031	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	5,230 LF		
0032	2612000000-E	848	6" CONCRETE DRIVEWAY	70 SY		
003E	2655000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)	170 SY		
0034	3030000000-E	862	STEEL BM GUARDRAIL	212.5 LF		

County : Lincoln

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	162.5	LF	
003E	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5	EA	
0037	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1	EA	
003E	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	1	EA	
003E	3628000000-E	876	RIP RAP, CLASS I	40	TON	
004C	3649000000-E	876	RIP RAP, CLASS B	20	TON	
0041	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	85	SY	
0042	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	144	SF	
004E	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96	SF	
0044	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	2	EA	
004E	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	2	EA	
004E	4430000000-N	1130	DRUMS	280	EA	
0047	4435000000-N	1135	CONES	50	EA	
004E	4455000000-N	1150	FLAGGER	120	MD	
004E	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	4	EA	
005C	4480000000-N	1165	TMIA	1	EA	
0051	4485000000-E	1170	PORTABLE CONCRETE BARRIER	1,215	LF	
0052	4510000000-N	SP	POLICE	132	HR	
0053	4516000000-N	1180	SKINNY DRUM	280	EA	

County : Lincoln

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	245 EA		
005E	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	1,608 LF		
005E	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	10,121 LF		
0057	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	204 LF		
005E	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	150 LF		
005E	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	8 EA		
006C	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	41 EA		
0061	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	15,713 LF		
0062	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	160 LF		
006E	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	8 EA		
0064	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	204 EA		
006E	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	
006E	6000000000-E	1605	TEMPORARY SILT FENCE	4,375 LF		
0067	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	100 TON		
006E	6012000000-E	1610	SEDIMENT CONTROL STONE	50 TON		
006E	6042000000-E	1632	1/4" HARDWARE CLOTH	1,000 LF		
007C	6084000000-E	1660	SEEDING & MULCHING	3.2 ACR		
0071	6111000000-E	SP	IMPERVIOUS DIKE	100 LF		

County : Lincoln

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	8126000000-N	414	CULVERT EXCAVATION, STA ***** (22+94.00-L-)	Lump Sum	L.S.	
0073	8133000000-E	414	FOUNDATION CONDITIONING MATERIAL, BOX CULVERT	15	TON	
0074	8196000000-E	420	CLASS A CONCRETE (CULVERT)	32.4	CY	
0075	8245000000-E	425	REINFORCING STEEL (CULVERT)	3,076	LB	
0076	8436000000-E	453	GRAVITY RETAINING WALLS	1,825	SF	

***** BEGIN SCHEDULE AA *****
 ***** (3 ALTERNATES) *****

0077 AA1	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	980	LF	
*** OR ***						
0078 AA2	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	500	LF	
0079 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (30")	480	LF	
*** OR ***						
008C AA3	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	500	LF	
0081 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, ***** THICK (30", 0.079")	480	LF	

***** END SCHEDULE AA *****

1112/Nov14/Q59388.0/D260426500000/E81

Total Amount Of Bid For Entire Project :

Contract No: C201913

County: Lincoln

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General