

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (16+19.00)	Lump Sum	L.S.	
0003	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0004	0057000000-E	226	UNDERCUT EXCAVATION	600 CY		
0005	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0006	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	600 TON		
0007	0106000000-E	230	BORROW EXCAVATION	2,000 CY		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	350 CY		
0009	0195000000-E	265	SELECT GRANULAR MATERIAL	500 CY		
0010	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
0011	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	20 TON		
0012	0343000000-E	310	15" SIDE DRAIN PIPE	100 LF		
0013	0344000000-E	310	18" SIDE DRAIN PIPE	24 LF		
0014	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	48 LF		
0015	0995000000-E	340	PIPE REMOVAL	120 LF		
0016	1220000000-E	545	INCIDENTAL STONE BASE	50 TON		
0017	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	296 TON		
0018	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	350 TON		

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	40 TON		
0020	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	25 TON		
0021	2000000000-N	806	RIGHT OF WAY MARKERS	10 EA		
0022	2022000000-E	815	SUBDRAIN EXCAVATION	300 CY		
0023	2033000000-E	815	SUBDRAIN FINE AGGREGATE	220 CY		
0024	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	1,300 LF		
0025	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	39 EA		
0026	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	3 EA		
0027	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	18 LF		
0028	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
0029	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0030	2556000000-E	846	SHOULDER BERM GUTTER	40 LF		
0031	3030000000-E	862	STEEL BM GUARDRAIL	375 LF		
0032	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0033	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0034	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0035	3649000000-E	876	RIP RAP, CLASS B	5 TON		
0036	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	160 SY		
0037	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1 EA		

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	10 SF		
0039	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	26 LF		
0040	4102000000-N	904	SIGN ERECTION, TYPE E	2 EA		
0041	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	6 EA		
0042	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	321 SF		
0043	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	94 SF		
0044	4430000000-N	1130	DRUMS	6 EA		
0045	4435000000-N	1135	CONES	6 EA		
0046	4445000000-E	1145	BARRICADES (TYPE III)	80 LF		
0047	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	6,400 LF		
0048	6000000000-E	1605	TEMPORARY SILT FENCE	925 LF		
0049	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75 TON		
0050	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	230 TON		
0051	6012000000-E	1610	SEDIMENT CONTROL STONE	85 TON		
0052	6015000000-E	1615	TEMPORARY MULCHING	2.5 ACR		
0053	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0054	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.5 TON		
0055	6029000000-E	SP	SAFETY FENCE	200 LF		
0056	6030000000-E	1630	SILT EXCAVATION	655 CY		

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	6036000000-E	1631	MATTING FOR EROSION CONTROL	520 SY		
0058	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	325 SY		
0059	6042000000-E	1632	1/4" HARDWARE CLOTH	40 LF		
0060	6071030000-E	SP	COIR FIBER BAFFLES	240 LF		
0061	6084000000-E	1660	SEEDING & MULCHING	2.5 ACR		
0062	6087000000-E	1660	MOWING	1.5 ACR		
0063	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0064	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0065	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	75 LB		
0066	6108000000-E	1665	FERTILIZER TOPDRESSING	1.75 TON		
0067	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
0068	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
<b>STRUCTURE ITEMS</b>						
0069	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (16+19.00-L-)	Lump Sum	L.S.	
0070	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (16+19.00-L-)	Lump Sum	L.S.	
0071	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	32.7 CY		
0072	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (16+19.00-L-)	Lump Sum	L.S.	
0073	8217000000-E	425	REINFORCING STEEL (BRIDGE)	5,215 LB		

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	8364000000-E	450	HP12X53 STEEL PILES	425 LF		
0075	8391000000-N	450	STEEL PILE POINTS	18 EA		
0076	8503000000-E	460	CONCRETE BARRIER RAIL	171.6 LF		
0077	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	201 TON		
0078	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	223 SY		
0079	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0080	8753100000-E	430	3'-0" X 2'-9" PRESTRESSED CONC BOX BEAMS	942.33 LF		
<b>1613/Dec11/Q25841.63/D327049230000/E80</b>			<b>Total Amount Of Bid For Entire Project :</b>			

**Contract No: C201754**

**County: Burke**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General