

County : Caldwell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (12+46.00)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	1 CY		
0007	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	10 TON		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	70 CY		
0009	0195000000-E	265	SELECT GRANULAR MATERIAL	10 CY		
0010	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	10 SY		
0011	0199000000-E	SP	TEMPORARY SHORING	424 SF		
0012	0234000000-E	SP	GENERIC GRADING ITEM EXCAVATION & STOCKPILING OF CONTAMINATED SOIL	25 CY		
0013	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	30 TON		
0014	0343000000-E	310	15" SIDE DRAIN PIPE	148 LF		
0015	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	28 LF		
0016	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	2 EA		
0017	0995000000-E	340	PIPE REMOVAL	40 LF		
0018	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0019	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	279 TON		

County : Caldwell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0020	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	315 TON		
0021	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	35 TON		
0022	2000000000-N	806	RIGHT OF WAY MARKERS	12 EA		
0023	2022000000-E	815	SUBDRAIN EXCAVATION	12 CY		
0024	2033000000-E	815	SUBDRAIN FINE AGGREGATE	9 CY		
0025	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	50 LF		
0026	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	2 EA		
0027	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0028	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0029	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
0030	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	1 EA		
0031	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1 EA		
0032	2556000000-E	846	SHOULDER BERM GUTTER	14 LF		
0033	2612000000-E	848	6" CONCRETE DRIVEWAY	100 SY		
0034	2905000000-N	859	CONVERT EXISTING DROP INLET TO JUNCTION BOX	1 EA		
0035	3030000000-E	862	STEEL BM GUARDRAIL	112.5 LF		
0036	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	25 LF		
0037	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0038	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	1 EA		

County : Caldwell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0039	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	3 EA		
0040	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0041	3503000000-E	866	WOVEN WIRE FENCE, 47" FABRIC	200 LF		
0042	3509000000-E	866	4" TIMBER FENCE POSTS, 7'-6" LONG	15 EA		
0043	3515000000-E	866	5" TIMBER FENCE POSTS, 8'-0" LONG	10 EA		
0044	3649000000-E	876	RIP RAP, CLASS B	20 TON		
0045	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	415 SY		
0046	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	160 SF		
0047	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	176 SF		
0048	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	20 SF		
0049	4430000000-N	1130	DRUMS	45 EA		
0050	4435000000-N	1135	CONES	21 EA		
0051	4445000000-E	1145	BARRICADES (TYPE III)	32 LF		
0052	4450000000-N	1150	FLAGGER	1,920 HR		
0053	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	2 EA		
0054	4480000000-N	1165	TMIA	1 EA		
0055	4485000000-E	1170	PORTABLE CONCRETE BARRIER	200 LF		
0056	4495000000-E	1170	PORTABLE CONCRETE BARRIER (DRAINAGE)	60 LF		
0057	4516000000-N	1180	SKINNY DRUM	32 EA		

County : Caldwell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0058	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	83 EA		
0059	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (IV)	480 LF		
0060	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	12,413 LF		
0061	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	80 LF		
0062	5325800000-E	1510	8" WATER LINE	255 LF		
0063	5546000000-E	1515	8" VALVE	1 EA		
0064	5691500000-E	1520	12" SANITARY GRAVITY SEWER	203 LF		
0065	5775000000-E	1525	4' DIA UTILITY MANHOLE	2 EA		
0066	5816000000-N	1530	ABANDON UTILITY MANHOLE	1 EA		
0067	5882000000-N	SP	GENERIC UTILITY ITEM VALVE POST INDICATOR	1 EA		
0068	6000000000-E	1605	TEMPORARY SILT FENCE	700 LF		
0069	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	150 TON		
0070	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	225 TON		
0071	6012000000-E	1610	SEDIMENT CONTROL STONE	200 TON		
0072	6015000000-E	1615	TEMPORARY MULCHING	1.5 ACR		
0073	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0074	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.25 TON		
0075	6024000000-E	1622	TEMPORARY SLOPE DRAINS	15 LF		
0076	6029000000-E	SP	SAFETY FENCE	225 LF		

County : Caldwell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0077	6030000000-E	1630	SILT EXCAVATION	555 CY		
0078	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,200 SY		
0079	6037000000-E	SP	COIR FIBER MAT	20 SY		
0080	6042000000-E	1632	1/4" HARDWARE CLOTH	80 LF		
0081	6070000000-N	SP	SPECIAL STILLING BASINS	4 EA		
0082	6071030000-E	SP	COIR FIBER BAFFLES	55 LF		
0083	6071050000-E	SP	*** SKIMMER (1-1/2")	2 EA		
0084	6084000000-E	1660	SEEDING & MULCHING	1.5 ACR		
0085	6087000000-E	1660	MOWING	1 ACR		
0086	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0087	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0088	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0089	6108000000-E	1665	FERTILIZER TOPDRESSING	1 TON		
0090	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
0091	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	16 EA		
0092	6123000000-E	1670	REFORESTATION	0.15 ACR		

***** BEGIN SCHEDULE AA *****
 ***** (3 ALTERNATES) *****

0093	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	16 LF		
AA1						
*** OR ***						
0094	0536000000-E	SP	**** HDPE PIPE CULVERTS (15")	16 LF		
AA2						
*** OR ***						

County : Caldwell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0095 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (15", 0.064")	16 LF		
***** END SCHEDULE AA *****						
STRUCTURE ITEMS						
0096	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (12+46.00-L-)	Lump Sum	L.S.	
0097	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (12+46.00-L-)	Lump Sum	L.S.	
0098	8105520000-E	SP	3'-0" DIA DRILLED PIERS IN SO IL	71.8 LF		
0099	8105620000-E	SP	3'-0" DIA DRILLED PIERS NOT IN SOIL	29 LF		
0100	8111200000-E	SP	PERMANENT STEEL CASING FOR 3'-0" DIA DRILLED PIER	29.8 LF		
0101	8113000000-N	SP	SID INSPECTION	2 EA		
0102	8115000000-N	SP	CROSSHOLE SONIC LOGGING	1 EA		
0103	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (12+46.00-L-)	Lump Sum	L.S.	
0104	8156000000-E	SP	CONCRETE WEARING SURFACE	2,900 SF		
0105	8161000000-E	420	GROOVING BRIDGE FLOORS	3,134 SF		
0106	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	55.4 CY		
0107	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (12+46.00-L-)	Lump Sum	L.S.	
0108	8217000000-E	425	REINFORCING STEEL (BRIDGE)	13,580 LB		

County : Caldwell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0109	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	1,839 LB		
0110	8364000000-E	450	HP12X53 STEEL PILES	330 LF		
0111	8391000000-N	450	STEEL PILE POINTS	6 EA		
0112	8468000000-E	460	ONE BAR METAL RAIL	219.48 LF		
0113	8517000000-E	460	1'-***X ***** CONCRETE PARAPET (1'-0" X 2'-0")	117.6 LF		
0114	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	170 TON		
0115	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	190 SY		
0116	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0117	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0118	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	1,056 LF		

1450/Jan03/Q46130.23/D526738820000/E117

Total Amount Of Bid For Entire Project :

Contract No: C201733

County: Caldwell

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General