



**FINAL PAVEMENT MARKING SCHEDULE**

SYMBOL	DESCRIPTION	PAY ITEM	QUANTITY BREAKDOWN	TOTAL QUANTITY
PAVEMENT MARKINGS LINES				
THERMOPLASTIC (24", 120 MILS)				
T2	WHITE STOPBAR		112 LF	
			TOTAL	112 LF
THERMOPLASTIC (4", 120 MILS)				
TD	2 FT. WHITE MINISKIP		132 LF	
TE	WHITE SOLD LANE LINE		320 LF	
TI	YELLOW DOUBLE CENTER		3596 LF	
			TOTAL	4048 LF
THERMOPLASTIC (4", 90 MILS)				
TA	WHITE EDGELINE		2620 LF	
			TOTAL	2620 LF
THERMOPLASTIC (8", 90 MILS)				
TT	YELLOW DIAGNOL		75 LF	
			TOTAL	75 LF
THERMOPLASTIC PAVEMENT MARKING SYMBOLS (90 MILS)				
UA	LEFT TURN ARROW		3 EA	
UB	RIGHT TURN ARROW		2 EA	
UC	STRAIGHT ARROW		2 EA	
			TOTAL	7 EA
PAVEMENT MARKERS				
SNOWPLOWABLE RAISED PAVEMENT MARKERS				
ME	YELLOW & YELLOW		52 EA	
MF	CRYSTAL & RED		20 EA	
			TOTAL	72 EA

**PLANS PREPARED BY:**  
**TGS ENGINEERS**  
 TGS ENGINEERS  
 SUITE 141  
 975 WALNUT STREET  
 CARY, NC 27511  
 PH (919) 319-8850

APPROVED: _____ DATE: _____	<b>PAVEMENT MARKING PLAN</b>	SCALE: NONE	REVISIONS
		DATE: JAN. 2007	
	DWG. BY: JLT		
	DESIGN BY: JLT		
REVIEWED BY: BCH			

SYSTEMS: JLT  
 CHECKED: JLT  
 DESIGNED: JLT  
 DRAWN: JLT  
 USER: JLT