

County : Chatham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (13+35.00)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0006	0195000000-E	265	SELECT GRANULAR MATERIAL	200 CY		
0007	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	200 SY		
0008	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	35 TON		
0009	0343000000-E	310	15" SIDE DRAIN PIPE	136 LF		
0010	0344000000-E	310	18" SIDE DRAIN PIPE	32 LF		
0011	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	148 LF		
0012	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	8 EA		
0013	0995000000-E	340	PIPE REMOVAL	98 LF		
0014	1220000000-E	545	INCIDENTAL STONE BASE	30 TON		
0015	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	480 TON		
0016	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	325 TON		
0017	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	380 TON		

County : Chatham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	61 TON		
001E	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	200 TON		
002C	2000000000-N	806	RIGHT OF WAY MARKERS	18 EA		
0021	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	4 EA		
0022	2355000000-N	840	FRAME WITH GRATE, STD 840.29	4 EA		
0023	2556000000-E	846	SHOULDER BERM GUTTER	550 LF		
0024	3030000000-E	862	STEEL BM GUARDRAIL	675 LF		
002E	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	50 LF		
002E	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0027	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		
002E	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
002E	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	3 EA		
003C	3649000000-E	876	RIP RAP, CLASS B	38 TON		
0031	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	859 SY		
0032	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	372 SF		
0033	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	131 SF		
0034	4445000000-E	1145	BARRICADES (TYPE III)	80 LF		
003E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	7,200 LF		

County : Chatham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	11	EA	
0037	6000000000-E	1605	TEMPORARY SILT FENCE	1,000	LF	
003E	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75	TON	
003E	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	145	TON	
004C	6012000000-E	1610	SEDIMENT CONTROL STONE	330	TON	
0041	6015000000-E	1615	TEMPORARY MULCHING	2.5	ACR	
0042	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100	LB	
0043	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.5	TON	
0044	6024000000-E	1622	TEMPORARY SLOPE DRAINS	140	LF	
004E	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	4	EA	
004E	6029000000-E	SP	SAFETY FENCE	360	LF	
0047	6030000000-E	1630	SILT EXCAVATION	735	CY	
004E	6036000000-E	1631	MATTING FOR EROSION CONTROL	570	SY	
004E	6037000000-E	SP	COIR FIBER MAT	25	SY	
005C	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	550	SY	
0051	6042000000-E	1632	1/4" HARDWARE CLOTH	80	LF	
0052	6070000000-N	SP	SPECIAL STILLING BASINS	12	EA	
0053	6071030000-E	SP	COIR FIBER BAFFLES	255	LF	

County : Chatham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	6071050000-E	SP	*** SKIMMER (1-1/2")	4 EA		
005E	6084000000-E	1660	SEEDING & MULCHING	2.5 ACR		
005E	6087000000-E	1660	MOWING	1.5 ACR		
0057	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
005E	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
005E	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
006C	6108000000-E	1665	FERTILIZER TOPDRESSING	2 TON		
0061	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
0062	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
STRUCTURE ITEMS						
006E	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (13+35.00 -L-)	Lump Sum	L.S.	
0064	8105540000-E	SP	3'-6" DIA DRILLED PIERS IN SOIL	192 LF		
006E	8105640000-E	SP	3'-6" DIA DRILLED PIERS NOT IN SOIL	18 LF		
006E	8113000000-N	SP	SID INSPECTION	6 EA		
0067	8114000000-N	SP	SPT TESTING	6 EA		
006E	8115000000-N	SP	CROSSHOLE SONIC LOGGING	2 EA		
006E	8119000000-E	412	UNCLASSIFIED STRUCTURE EXCAVA- TION (13+35.00 -L-)	3,443 CY		

County : Chatham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
007C	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	4,897 SF		
0071	8161000000-E	420	GROOVING BRIDGE FLOORS	4,846 SF		
0072	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	108.5 CY		
0073	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (13 + 35.00 -L-)	Lump Sum	L.S.	
0074	8217000000-E	425	REINFORCING STEEL (BRIDGE)	34,196 LB		
007E	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	5,848 LB		
007E	8262000000-E	430	45" PRESTRESSED CONCRETE GIR- DERS	552.67 LF		
0077	8364000000-E	450	HP12X53 STEEL PILES	595 LF		
007E	8475000000-E	460	TWO BAR METAL RAIL	266.65 LF		
007E	8517000000-E	460	1'-***X ***** CONCRETE PARA- PET (1'-0 x 2'-6")	283 LF		
008C	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	651 TON		
0081	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	724 SY		
0082	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0083	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	

0909/Dec05/Q73689.07/D402845360000/E83

Total Amount Of Bid For Entire Project :

Contract No: C201787

County: Chatham

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General