

County : Craven

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|----------------------|--------------|-------|--|-------------|-----------|--------|
| ROADWAY ITEMS | | | | | | |
| 0001 | 0000100000-N | 800 | MOBILIZATION | Lump Sum | L.S. | |
| 0002 | 0000400000-N | 801 | CONSTRUCTION SURVEYING | Lump Sum | L.S. | |
| 0003 | 0029000000-N | SP | REINFORCED BRIDGE APPROACH FILL, STATION ***** (12+42.500) | Lump Sum | L.S. | |
| 0004 | 0050000000-E | 226 | SUPPLEMENTARY CLEARING & GRUB- BING | 1 ACR | | |
| 0005 | 0057000000-E | 226 | UNDERCUT EXCAVATION | 200 CY | | |
| 0006 | 0063000000-N | SP | GRADING | Lump Sum | L.S. | |
| 0007 | 0106000000-E | 230 | BORROW EXCAVATION | 2,100 CY | | |
| 0008 | 0196000000-E | 270 | FABRIC FOR SOIL STABILIZATION | 1,500 SY | | |
| 0009 | 0234000000-E | SP | GENERIC GRADING ITEM SELECT GRANULAR MATERIAL | 1,500 CY | | |
| 0010 | 0318000000-E | 300 | FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS | 17 TON | | |
| 0011 | 0366000000-E | 310 | 15" RC PIPE CULVERTS, CLASS III | 96 LF | | |
| 0012 | 0546000000-E | 310 | *** CAA PIPE CULVERTS, ***** THICK (15", 0.060") | 64 LF | | |
| 0013 | 0564000000-E | 310 | *** CAA PIPE ELBOWS, ***** THICK (15", 0.060") | 4 EA | | |
| 0014 | 1220000000-E | 545 | INCIDENTAL STONE BASE | 100 TON | | |
| 0015 | 1330000000-E | 607 | INCIDENTAL MILLING | 300 SY | | |
| 0016 | 1489000000-E | 610 | ASPHALT CONC BASE COURSE, TYPE B25.0B | 185 TON | | |
| 0017 | 1498000000-E | 610 | ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B | 200 TON | | |

County : Craven

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|---|------------|-----------|--------|
| 0018 | 1519000000-E | 610 | ASPHALT CONC SURFACE COURSE, TYPE S9.5B | 465 TON | | |
| 0019 | 1560000000-E | 620 | ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22 | 46 TON | | |
| 0020 | 1693000000-E | 654 | ASPHALT PLANT MIX, PAVEMENT REPAIR | 100 TON | | |
| 0021 | 2022000000-E | 815 | SUBDRAIN EXCAVATION | 22.4 CY | | |
| 0022 | 2033000000-E | 815 | SUBDRAIN FINE AGGREGATE | 16.8 CY | | |
| 0023 | 2044000000-E | 815 | 6" PERFORATED SUBDRAIN PIPE | 100 LF | | |
| 0024 | 2055000000-E | 815 | 6" SUBDRAIN PIPE WYES, TEES, & ELBOWS | 3 EA | | |
| 0025 | 2066000000-N | 815 | CONCRETE PAD FOR SUBDRAIN PIPE OUTLET | 1 EA | | |
| 0026 | 2077000000-E | 815 | 6" OUTLET PIPE (SUBDRAINS) | 6 LF | | |
| 0027 | 2286000000-N | 840 | MASONRY DRAINAGE STRUCTURES | 5 EA | | |
| 0028 | 2367000000-N | 840 | FRAME WITH TWO GRATES, STD 840.29 | 5 EA | | |
| 0029 | 2556000000-E | 846 | SHOULDER BERM GUTTER | 775 LF | | |
| 0030 | 3030000000-E | 862 | STEEL BM GUARDRAIL | 800 LF | | |
| 0031 | 3150000000-N | 862 | ADDITIONAL GUARDRAIL POSTS | 5 EA | | |
| 0032 | 3270000000-N | SP | GUARDRAIL ANCHOR UNITS, TYPE 350 | 4 EA | | |
| 0033 | 3317000000-N | 862 | GUARDRAIL ANCHOR UNITS, TYPE B-77 | 4 EA | | |
| 0034 | 3649000000-E | 876 | RIP RAP, CLASS B | 4 TON | | |
| 0035 | 3656000000-E | 876 | FILTER FABRIC FOR DRAINAGE | 160 SY | | |

County : Craven

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|---|-------------|-----------|--------|
| 0036 | 4025000000-E | 901 | CONTRACTOR FURNISHED, TYPE *** SIGN (D) | 13.5 SF | | |
| 0037 | 4025000000-E | 901 | CONTRACTOR FURNISHED, TYPE *** SIGN (E) | 5.56 SF | | |
| 0038 | 4082000000-E | 903 | SUPPORTS, WOOD | 62 LF | | |
| 0039 | 4096000000-N | 904 | SIGN ERECTION, TYPE D | 2 EA | | |
| 0040 | 4102000000-N | 904 | SIGN ERECTION, TYPE E | 1 EA | | |
| 0041 | 4155000000-N | 907 | DISPOSAL OF SIGN SYSTEM, U- CHANNEL | 1 EA | | |
| 0042 | 4158000000-N | 907 | DISPOSAL OF SIGN SYSTEM, WOOD | 10 EA | | |
| 0043 | 4400000000-E | 1110 | WORK ZONE SIGNS (STATIONARY) | 353 SF | | |
| 0044 | 4410000000-E | 1110 | WORK ZONE SIGNS (BARRICADE MOUNTED) | 20 SF | | |
| 0045 | 4445000000-E | 1145 | BARRICADES (TYPE III) | 64 LF | | |
| 0046 | 4810000000-E | 1205 | PAINT PAVEMENT MARKING LINES (4") | 7,200 LF | | |
| 0047 | 4900000000-N | 1251 | PERMANENT RAISED PAVEMENT MARKERS | 12 EA | | |
| 0048 | 6000000000-E | 1605 | TEMPORARY SILT FENCE | 750 LF | | |
| 0049 | 6006000000-E | 1610 | STONE FOR EROSION CONTROL, CLASS A | 50 TON | | |
| 0050 | 6009000000-E | 1610 | STONE FOR EROSION CONTROL, CLASS B | 80 TON | | |
| 0051 | 6012000000-E | 1610 | SEDIMENT CONTROL STONE | 60 TON | | |
| 0052 | 6015000000-E | 1615 | TEMPORARY MULCHING | 1.5 ACR | | |
| 0053 | 6018000000-E | 1620 | SEED FOR TEMPORARY SEEDING | 50 LB | | |

County : Craven

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|---|-------------|-----------|--------|
| 0054 | 6021000000-E | 1620 | FERTILIZER FOR TEMPORARY SEED- ING | 0.25 TON | | |
| 0055 | 6024000000-E | 1622 | TEMPORARY SLOPE DRAINS | 120 LF | | |
| 0056 | 6027000000-N | 1622 | INLET PROTECTION AT TEMPORARY SLOPE DRAINS | 6 EA | | |
| 0057 | 6029000000-E | SP | SAFETY FENCE | 500 LF | | |
| 0058 | 6030000000-E | 1630 | SILT EXCAVATION | 175 CY | | |
| 0059 | 6036000000-E | 1631 | MATTING FOR EROSION CONTROL | 350 SY | | |
| 0060 | 6042000000-E | 1632 | 1/4" HARDWARE CLOTH | 160 LF | | |
| 0061 | 6048000000-E | SP | FLOATING TURBIDITY CURTAIN | 100 SY | | |
| 0062 | 6071030000-E | SP | COIR FIBER BAFFLES | 45 LF | | |
| 0063 | 6084000000-E | 1660 | SEEDING & MULCHING | 1.5 ACR | | |
| 0064 | 6087000000-E | 1660 | MOWING | 1 ACR | | |
| 0065 | 6090000000-E | 1661 | SEED FOR REPAIR SEEDING | 50 LB | | |
| 0066 | 6093000000-E | 1661 | FERTILIZER FOR REPAIR SEEDING | 0.25 TON | | |
| 0067 | 6096000000-E | 1662 | SEED FOR SUPPLEMENTAL SEEDING | 50 LB | | |
| 0068 | 6108000000-E | 1665 | FERTILIZER TOPDRESSING | 1 TON | | |
| 0069 | 6114000000-N | SP | SPECIALIZED HAND MOWING | 2 HR | | |
| 0070 | 6117000000-N | SP | RESPONSE FOR EROSION CONTROL | 8 EA | | |
| 0071 | 6123000000-E | 1670 | REFORESTATION | 0.1 ACR | | |

County : Craven

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--|--------------|-------|--|-------------|-----------|--------|
| STRUCTURE ITEMS | | | | | | |
| 0072 | 8035000000-N | 402 | REMOVAL OF EXISTING STRUCTURE AT STATION ***** (12+42.50-L-) | Lump Sum | L.S. | |
| 0073 | 8121000000-N | 412 | UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (12+42.50-L-) | Lump Sum | L.S. | |
| 0074 | 8156000000-E | SP | CONCRETE WEARING SURFACE | 3,672 SF | | |
| 0075 | 8161000000-E | 420 | GROOVING BRIDGE FLOORS | 4,742 SF | | |
| 0076 | 8182000000-E | 420 | CLASS A CONCRETE (BRIDGE) | 51.8 CY | | |
| 0077 | 8210000000-N | 422 | BRIDGE APPROACH SLABS, STATION ***** (12+42.50-L-) | Lump Sum | L.S. | |
| 0078 | 8217000000-E | 425 | REINFORCING STEEL (BRIDGE) | 8,182 LB | | |
| 0079 | 8364000000-E | 450 | HP12X53 STEEL PILES | 350 LF | | |
| 0080 | 8384000000-E | 450 | HP14X73 STEEL PILES | 500 LF | | |
| 0081 | 8391000000-N | 450 | STEEL PILE POINTS | 20 EA | | |
| 0082 | 8503000000-E | 460 | CONCRETE BARRIER RAIL | 225 LF | | |
| 0083 | 8608000000-E | 876 | RIP RAP CLASS II (2'-0" THICK) | 373 TON | | |
| 0084 | 8622000000-E | 876 | FILTER FABRIC FOR DRAINAGE | 415 SY | | |
| 0085 | 8657000000-N | 430 | ELASTOMERIC BEARINGS | Lump Sum | L.S. | |
| 0086 | 8692000000-N | SP | EVAZOTE JOINT SEALS | Lump Sum | L.S. | |
| 0087 | 8762000000-E | 430 | 3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS | 1,350 LF | | |
| <hr/> | | | | | | |
| 0831/Dec14/Q38984.66/D383389530000/E87 | | | Total Amount Of Bid For Entire Project : | | | |

Contract No: C201428

County: Craven

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General