

County : Davidson

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|----------------------|--------------|-------|---|-------------|-----------|--------|
| ROADWAY ITEMS | | | | | | |
| 0001 | 0000100000-N | 800 | MOBILIZATION | Lump Sum | L.S. | |
| 0002 | 0000400000-N | 801 | CONSTRUCTION SURVEYING | Lump Sum | L.S. | |
| 0003 | 0029000000-N | SP | REINFORCED BRIDGE APPROACH FILL, STATION ***** (24 + 38.00) | Lump Sum | L.S. | |
| 0004 | 0043000000-N | 226 | GRADING | Lump Sum | L.S. | |
| 0005 | 0050000000-E | 226 | SUPPLEMENTARY CLEARING & GRUB- BING | 1 ACR | | |
| 0006 | 0057000000-E | 226 | UNDERCUT EXCAVATION | 450 CY | | |
| 0007 | 0080000000-E | SP | CLASS IV SUBGRADE STABILIZA- TION | 500 TON | | |
| 0008 | 0134000000-E | 240 | DRAINAGE DITCH EXCAVATION | 470 CY | | |
| 0009 | 0195000000-E | 265 | SELECT GRANULAR MATERIAL | 5,000 CY | | |
| 0010 | 0196000000-E | 270 | FABRIC FOR SOIL STABILIZATION | 5,000 SY | | |
| 0011 | 0199000000-E | SP | TEMPORARY SHORING | 420 SF | | |
| 0012 | 0318000000-E | 300 | FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS | 20 TON | | |
| 0013 | 0344000000-E | 310 | 18" SIDE DRAIN PIPE | 20 LF | | |
| 0014 | 0366000000-E | 310 | 15" RC PIPE CULVERTS, CLASS III | 36 LF | | |
| 0015 | 0372000000-E | 310 | 18" RC PIPE CULVERTS, CLASS III | 56 LF | | |
| 0016 | 0708000000-E | 310 | 15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK | 24 LF | | |
| 0017 | 0995000000-E | 340 | PIPE REMOVAL | 196 LF | | |
| 0018 | 1077000000-E | SP | #57 STONE | 20 TON | | |

County : Davidson

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|---|--------------|-----------|--------|
| 0019 | 1121000000-E | 520 | AGGREGATE BASE COURSE | 1,250 TON | | |
| 002C | 1220000000-E | 545 | INCIDENTAL STONE BASE | 100 TON | | |
| 0021 | 1275000000-E | 600 | PRIME COAT | 925 GAL | | |
| 0022 | 1330000000-E | 607 | INCIDENTAL MILLING | 50 SY | | |
| 0023 | 1489000000-E | 610 | ASPHALT CONC BASE COURSE, TYPE B25.0B | 930 TON | | |
| 0024 | 1498000000-E | 610 | ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B | 830 TON | | |
| 002E | 1519000000-E | 610 | ASPHALT CONC SURFACE COURSE, TYPE S9.5B | 1,630 TON | | |
| 002E | 1560000000-E | 620 | ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22 | 180 TON | | |
| 0027 | 1693000000-E | 654 | ASPHALT PLANT MIX, PAVEMENT REPAIR | 10 TON | | |
| 002E | 2000000000-N | 806 | RIGHT OF WAY MARKERS | 16 EA | | |
| 002E | 2253000000-E | 840 | PIPE COLLARS | 0.9 CY | | |
| 003C | 2286000000-N | 840 | MASONRY DRAINAGE STRUCTURES | 2 EA | | |
| 0031 | 2355000000-N | 840 | FRAME WITH GRATE, STD 840.29 | 2 EA | | |
| 0032 | 2556000000-E | 846 | SHOULDER BERM GUTTER | 33 LF | | |
| 0033 | 3030000000-E | 862 | STEEL BM GUARDRAIL | 2,400 LF | | |
| 0034 | 3150000000-N | 862 | ADDITIONAL GUARDRAIL POSTS | 5 EA | | |
| 003E | 3270000000-N | SP | GUARDRAIL ANCHOR UNITS, TYPE 350 | 4 EA | | |
| 003E | 3317000000-N | 862 | GUARDRAIL ANCHOR UNITS, TYPE B-77 | 4 EA | | |

County : Davidson

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|---|----------|-----------|--------|
| 0037 | 3380000000-E | 862 | TEMPORARY STEEL BM GUARDRAIL | 1,350 | | LF |
| 003E | 3387000000-N | 862 | GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (B-77) | 4 | | EA |
| 003E | 3389100000-N | SP | GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY | 3 | | EA |
| 004C | 3559000000-E | 866 | ** STRAND BARBED WIRE FENCE WITH POSTS (6) | 1,040 | | LF |
| 0041 | 3649000000-E | 876 | RIP RAP, CLASS B | 40 | | TON |
| 0042 | 3651000000-E | SP | BOULDERS | 45 | | TON |
| 0043 | 3656000000-E | 876 | FILTER FABRIC FOR DRAINAGE | 425 | | SY |
| 0044 | 3659000000-N | SP | PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON | 1 | | EA |
| 004E | 4400000000-E | 1110 | WORK ZONE SIGNS (STATIONARY) | 349 | | SF |
| 004E | 4405000000-E | 1110 | WORK ZONE SIGNS (PORTABLE) | 112 | | SF |
| 0047 | 4410000000-E | 1110 | WORK ZONE SIGNS (BARRICADE MOUNTED) | 126 | | SF |
| 004E | 4430000000-N | 1130 | DRUMS | 30 | | EA |
| 004E | 4435000000-N | 1135 | CONES | 35 | | EA |
| 005C | 4445000000-E | 1145 | BARRICADES (TYPE III) | 80 | | LF |
| 0051 | 4450000000-N | 1150 | FLAGGER | 624 | | HR |
| 0052 | 4480000000-N | 1165 | TMIA | 1 | | EA |
| 0053 | 4650000000-N | 1251 | TEMPORARY RAISED PAVEMENT MARKERS | 112 | | EA |
| 0054 | 4810000000-E | 1205 | PAINT PAVEMENT MARKING LINES (4") | 25,136 | | LF |

County : Davidson

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|---|-------------|-----------|--------|
| 005E | 4847000000-E | 1205 | POLYUREA PAVEMENT MARKING LINES (4", *****) (STANDARD GLASS BEADS) | 7,200 LF | | |
| 005E | 4900000000-N | 1251 | PERMANENT RAISED PAVEMENT MARKERS | 23 EA | | |
| 0057 | 6000000000-E | 1605 | TEMPORARY SILT FENCE | 950 LF | | |
| 005E | 6006000000-E | 1610 | STONE FOR EROSION CONTROL, CLASS A | 160 TON | | |
| 005E | 6009000000-E | 1610 | STONE FOR EROSION CONTROL, CLASS B | 490 TON | | |
| 006C | 6012000000-E | 1610 | SEDIMENT CONTROL STONE | 355 TON | | |
| 0061 | 6015000000-E | 1615 | TEMPORARY MULCHING | 6.5 ACR | | |
| 0062 | 6018000000-E | 1620 | SEED FOR TEMPORARY SEEDING | 250 LB | | |
| 0063 | 6021000000-E | 1620 | FERTILIZER FOR TEMPORARY SEED- ING | 1 TON | | |
| 0064 | 6024000000-E | 1622 | TEMPORARY SLOPE DRAINS | 602 LF | | |
| 006E | 6027000000-N | 1622 | INLET PROTECTION AT TEMPORARY SLOPE DRAINS | 8 EA | | |
| 006E | 6029000000-E | SP | SAFETY FENCE | 510 LF | | |
| 0067 | 6030000000-E | 1630 | SILT EXCAVATION | 1,745 CY | | |
| 006E | 6036000000-E | 1631 | MATTING FOR EROSION CONTROL | 1,800 SY | | |
| 006E | 6037000000-E | SP | COIR FIBER MAT | 40 SY | | |
| 007C | 6038000000-E | SP | PERMANENT SOIL REINFORCEMENT MAT | 800 SY | | |
| 0071 | 6042000000-E | 1632 | 1/4" HARDWARE CLOTH | 580 LF | | |
| 0072 | 6071030000-E | SP | COIR FIBER BAFFLES | 225 LF | | |

County : Davidson

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|-------------------------------|-------------|-----------|--------|
| 0073 | 6071050000-E | SP | *** SKIMMER (1-1/2") | 2 EA | | |
| 0074 | 6071050000-E | SP | *** SKIMMER (2") | 2 EA | | |
| 0075 | 6084000000-E | 1660 | SEEDING & MULCHING | 8 ACR | | |
| 0076 | 6087000000-E | 1660 | MOWING | 4 ACR | | |
| 0077 | 6090000000-E | 1661 | SEED FOR REPAIR SEEDING | 100 LB | | |
| 0078 | 6093000000-E | 1661 | FERTILIZER FOR REPAIR SEEDING | 0.25 TON | | |
| 0079 | 6096000000-E | 1662 | SEED FOR SUPPLEMENTAL SEEDING | 150 LB | | |
| 0080 | 6108000000-E | 1665 | FERTILIZER TOPDRESSING | 5.75 TON | | |
| 0081 | 6114000000-N | SP | SPECIALIZED HAND MOWING | 5 HR | | |
| 0082 | 6117000000-N | SP | RESPONSE FOR EROSION CONTROL | 27 EA | | |
| 0083 | 6123000000-E | 1670 | REFORESTATION | 0.3 ACR | | |

STRUCTURE ITEMS

| | | | | | | |
|------|--------------|-----|--|-----------|------|--|
| 0084 | 8007000000-N | SP | CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP STRUCTURE AT STA ***** (24 + 38.00-L-) | Lump Sum | L.S. | |
| 0085 | 8017000000-N | SP | CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (24 + 38.00-L-) | Lump Sum | L.S. | |
| 0086 | 8035000000-N | 402 | REMOVAL OF EXISTING STRUCTURE AT STATION ***** (24 + 38.00-L-) | Lump Sum | L.S. | |
| 0087 | 8119000000-E | 412 | UNCLASSIFIED STRUCTURE EXCAVA- TION | 850 CY | | |

County : Davidson

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|--|---------------|-----------|--------|
| 008E | 8147000000-E | 420 | REINFORCED CONCRETE DECK SLAB | 6,055 SF | | |
| 008E | 8161000000-E | 420 | GROOVING BRIDGE FLOORS | 6,918 SF | | |
| 009C | 8182000000-E | 420 | CLASS A CONCRETE (BRIDGE) | 40.6 CY | | |
| 0091 | 8210000000-N | 422 | BRIDGE APPROACH SLABS, STATION ***** (24 + 38.00-L-) | Lump Sum | L.S. | |
| 0092 | 8217000000-E | 425 | REINFORCING STEEL (BRIDGE) | 8,256 LB | | |
| 009E | 8280000000-E | 440 | APPROX LBS STRUCTURAL STEEL | 192,200 LS | | |
| 0094 | 8364000000-E | 450 | HP12X53 STEEL PILES | 900 LF | | |
| 009E | 8503000000-E | 460 | CONCRETE BARRIER RAIL | 276.55 LF | | |
| 009E | 8608000000-E | 876 | RIP RAP CLASS II (2'-0" THICK) | 663 TON | | |
| 0097 | 8622000000-E | 876 | FILTER FABRIC FOR DRAINAGE | 737 SY | | |
| 009E | 8692000000-N | SP | EVAZOTE JOINT SEALS | Lump Sum | L.S. | |

1522/Nov29/Q283052.85/D412710730000/E98

Total Amount Of Bid For Entire Project :

Contract No: C201756

County: Davidson

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General