

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (22+07.50)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
000E	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
000E	0057000000-E	226	UNDERCUT EXCAVATION	1,000 CY		
0007	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	1,000 TON		
000E	0134000000-E	240	DRAINAGE DITCH EXCAVATION	30 CY		
000E	0195000000-E	265	SELECT GRANULAR MATERIAL	1,500 CY		
001C	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	2,000 SY		
0011	0199000000-E	SP	TEMPORARY SHORING	200 SF		
0012	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	20 TON		
001E	0343000000-E	310	15" SIDE DRAIN PIPE	20 LF		
0014	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	76 LF		
001E	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	64 LF		
001E	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	4 EA		
0017	0995000000-E	340	PIPE REMOVAL	96 LF		
001E	1121000000-E	520	AGGREGATE BASE COURSE	811 TON		

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1220000000-E	545	INCIDENTAL STONE BASE	20 TON		
0020	1275000000-E	600	PRIME COAT	630 GAL		
0021	1330000000-E	607	INCIDENTAL MILLING	50 SY		
0022	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	300 TON		
0023	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	230 TON		
0024	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	690 TON		
0025	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	70 TON		
0026	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	10 TON		
0027	2000000000-N	806	RIGHT OF WAY MARKERS	10 EA		
0028	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	1 EA		
0029	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1 EA		
0030	2556000000-E	846	SHOULDER BERM GUTTER	24 LF		
0031	2612000000-E	848	6" CONCRETE DRIVEWAY	10 SY		
0032	3030000000-E	862	STEEL BM GUARDRAIL	875 LF		
0033	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0034	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0035	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0036	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	575 LF		

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (B-77)	4 EA		
003E	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	4 EA		
0039	3574000000-E	867	GENERIC FENCING ITEM WOOD RAIL FENCE RESET	165 LF		
004C	3628000000-E	876	RIP RAP, CLASS I	10 TON		
0041	3635000000-E	876	RIP RAP, CLASS II	120 TON		
0042	3649000000-E	876	RIP RAP, CLASS B	5 TON		
0043	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	520 SY		
0044	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	160 SF		
0045	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	112 SF		
0046	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	52 SF		
0047	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	2 EA		
004E	4430000000-N	1130	DRUMS	30 EA		
0049	4435000000-N	1135	CONES	30 EA		
005C	4445000000-E	1145	BARRICADES (TYPE III)	48 LF		
0051	4450000000-N	1150	FLAGGER	512 HR		
0052	4480000000-N	1165	TMIA	1 EA		
0053	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	68 EA		
0054	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	14,616 LF		

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	4847000000-E	1205	POLYUREA PAVEMENT MARKING LINES (4", *****) (STANDARD GLASS BEADS)	3,800 LF		
005E	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	12 EA		
0057	5325800000-E	1510	8" WATER LINE	118 LF		
005E	5801000000-E	1530	ABANDON 8" UTILITY PIPE	146 LF		
005E	6000000000-E	1605	TEMPORARY SILT FENCE	2,000 LF		
006C	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	150 TON		
0061	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	210 TON		
0062	6012000000-E	1610	SEDIMENT CONTROL STONE	65 TON		
006E	6015000000-E	1615	TEMPORARY MULCHING	2.5 ACR		
0064	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
006E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.5 TON		
006E	6024000000-E	1622	TEMPORARY SLOPE DRAINS	100 LF		
0067	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	3 EA		
006E	6029000000-E	SP	SAFETY FENCE	300 LF		
006E	6030000000-E	1630	SILT EXCAVATION	540 CY		
007C	6036000000-E	1631	MATTING FOR EROSION CONTROL	900 SY		
0071	6037000000-E	SP	COIR FIBER MAT	40 SY		
0072	6042000000-E	1632	1/4" HARDWARE CLOTH	25 LF		

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0073	6071030000-E	SP	COIR FIBER BAFFLES	125 LF		
0074	6071050000-E	SP	*** SKIMMER (1-1/2")	5 EA		
0075	6084000000-E	1660	SEEDING & MULCHING	3 ACR		
0076	6087000000-E	1660	MOWING	1.5 ACR		
0077	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0078	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0079	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	75 LB		
0080	6108000000-E	1665	FERTILIZER TOPDRESSING	2.25 TON		
0081	6114000000-N	SP	SPECIALIZED HAND MOWING	4.5 HR		
0082	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		

**STRUCTURE ITEMS**

0083	8007000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP STRUCTURE AT STA ***** (22+07.50-L-)	Lump Sum	L.S.	
0084	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (22+07.50-L-)	Lump Sum	L.S.	
0085	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (22+07.50-L-)	Lump Sum	L.S.	
0086	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	46.2 CY		
0087	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (22+07.50-L-)	Lump Sum	L.S.	
0088	8217000000-E	425	REINFORCING STEEL (BRIDGE)	7,408 LB		

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
008E	8364000000-E	450	HP12X53 STEEL PILES	850 LF		
009C	8503000000-E	460	CONCRETE BARRIER RAIL	165.33 LF		
0091	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	191 TON		
0092	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	213 SY		
009E	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0094	8753100000-E	430	3'-0" X 2'-9" PRESTRESSED CONC BOX BEAMS	1,240 LF		
0945/Nov29/Q45703.03/D385847580000/E94			Total Amount Of Bid For Entire Project :			

**Contract No: C201757**

**County: Davidson**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General