

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	1220000000-E	545	INCIDENTAL STONE BASE	742 TON		
0003	1245000000-E	SP	SHOULDER RECONSTRUCTION	29.62 SMI		
0004	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	15,806 SY		
0005	1330000000-E	607	INCIDENTAL MILLING	70 SY		
0006	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	21,960 TON		
0007	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	1,318 TON		
0008	1704000000-E	SP	PATCHING EXISTING PAVEMENT	7,777 TON		
0009	2830000000-N	858	ADJUSTMENT OF MANHOLES	31 EA		
0010	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	18 EA		
0011	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	159,355 LF		
0012	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	107,250 LF		
0013	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	111 LF		
0014	4705000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (16", 120 MILS)	100 LF		
0015	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	482 LF		
0016	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	30 EA		
0017	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	70 EA		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	9,504	LF	
001E	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	1,103	EA	
002C	6084000000-E	1660	SEEDING & MULCHING	21.48	ACR	
0021	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	144	LF	
1321/Dec11/Q325923.1/D71717100000/E21			Total Amount Of Bid For Entire Project :			

Contract No: C201992

County: Wake

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General