TIP# R-2809A Date:08-07-07 Revised Date:

TRAFFIC CONTROL DEVICES REMAINING FROM PREVIOUS PROJECT

DESCRIPTION.

Accept ownership, monitor, maintain, replace, and remove the following traffic control devices, which are remaining from the previous project in accordance with the plans and specifications.

- 1-*Road Closed signs*
- 2-*End of road markers*
- 3-*Tubular markers*
- 4-*Temporary guardrail*

MATERIALS.

Replace any of the above mentioned devices which do not meet the material requirements of their respective specifications as directed by the Engineer.

CONSTRUCTION METHODS.

Accept ownership and maintenance responsibilities of the above mentioned devices and retain ownership at the completion of the project.

Section 1105-03 of the 2002 Standard Specifications applies to this special provision.

MAINTENANCE.

Maintain the above mentioned devices in accordance with Section 1105-4 of the 2002 Standard Specifications.

BASIS OF PAYMENT.

No separate payment will be made for the maintenance, replacement, and removal of the above mentioned devices. Such work will be considered as incidental to the other traffic control items listed in the contract.