

County : Warren

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (16+87.50)	Lump Sum	L.S.	
0003	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0004	0057000000-E	226	UNDERCUT EXCAVATION	250 CY		
0005	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0006	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	100 TON		
0007	0106000000-E	230	BORROW EXCAVATION	2,400 CY		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	98 CY		
0009	0195000000-E	265	SELECT GRANULAR MATERIAL	250 CY		
0010	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	250 SY		
0011	0306000000-E	300	SELECT MATERIAL, CLASS III	50 TON		
0012	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	10 TON		
0013	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	52 LF		
0014	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	32 LF		
0015	1220000000-E	545	INCIDENTAL STONE BASE	25 TON		
0016	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	520 TON		
0017	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	440 TON		
0018	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	53 TON		

County : Warren

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	25 TON		
0020	2000000000-N	806	RIGHT OF WAY MARKERS	10 EA		
0021	2022000000-E	815	SUBDRAIN EXCAVATION	25 CY		
0022	2033000000-E	815	SUBDRAIN FINE AGGREGATE	20 CY		
0023	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		
0024	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	3 EA		
0025	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0026	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0027	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3 EA		
0028	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	3 EA		
0029	2556000000-E	846	SHOULDER BERM GUTTER	67 LF		
0030	3030000000-E	862	STEEL BM GUARDRAIL	475 LF		
0031	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0032	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0033	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0034	3649000000-E	876	RIP RAP, CLASS B	110 TON		
0035	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	434 SY		
0036	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1 EA		
0037	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	429 SF		

County : Warren

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	132 SF		
0039	4445000000-E	1145	BARRICADES (TYPE III)	128 LF		
0040	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	10,400 LF		
0041	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	17 EA		
0042	6000000000-E	1605	TEMPORARY SILT FENCE	1,500 LF		
0043	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75 TON		
0044	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	165 TON		
0045	6012000000-E	1610	SEDIMENT CONTROL STONE	55 TON		
0046	6015000000-E	1615	TEMPORARY MULCHING	3 ACR		
0047	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0048	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.5 TON		
0049	6024000000-E	1622	TEMPORARY SLOPE DRAINS	15 LF		
0050	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	1 EA		
0051	6029000000-E	SP	SAFETY FENCE	250 LF		
0052	6030000000-E	1630	SILT EXCAVATION	415 CY		
0053	6036000000-E	1631	MATTING FOR EROSION CONTROL	580 SY		
0054	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	165 SY		
0055	6042000000-E	1632	1/4" HARDWARE CLOTH	60 LF		
0056	6071030000-E	SP	COIR FIBER BAFFLES	185 LF		

County : Warren

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	6084000000-E	1660	SEEDING & MULCHING	3 ACR		
0058	6087000000-E	1660	MOWING	1.5 ACR		
0059	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0060	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0061	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	75 LB		
0062	6108000000-E	1665	FERTILIZER TOPDRESSING	2 TON		
0063	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
0064	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
STRUCTURE ITEMS						
0065	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (16+87.50-L-)	Lump Sum	L.S.	
0066	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (16+87.50-L-)	Lump Sum	L.S.	
0067	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	38.2 CY		
0068	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (16+87.50-L-)	Lump Sum	L.S.	
0069	8217000000-E	425	REINFORCING STEEL (BRIDGE)	6,341 LB		
0070	8364000000-E	450	HP12X53 STEEL PILES	500 LF		
0071	8503000000-E	460	CONCRETE BARRIER RAIL	185.3 LF		
0072	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	185 TON		
0073	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	205 SY		

County : Warren

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	865700000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0075	875320000-E	430	3'-0" X 3'-3" PRESTRESSED CONC BOX BEAMS	1,019.33 LF		

1014/Dec07/Q29129.08/D309736330000/E75

Total Amount Of Bid For Entire Project :

Contract No: C201763

County: Warren

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General

Signature Sheet (Bid - Acceptance by Department)