



STATE OF NORTH CAROLINA  
DEPARTMENT OF TRANSPORTATION

MICHAEL F. EASLEY  
GOVERNOR

LYNDO TIPPETT  
SECRETARY

February 11, 2008

**Addendum No. 1**

RE: Contract ID: C201776

WBS# 37331.3.1

F.A. # IMS-73(12)

**Randolph County (K-3807)**

Rest Areas on I-73/74 and US-220

Bypass NB and SB South of Seagrove

**February 19, 2008 Letting**

To Whom It May Concern:

Reference is made to the plans and proposal form recently furnished to you on this project.

The following revisions have been made to the proposal form:

On Page No. 50 the Project Special Provisions entitled "Cooperation Between Contractors" and "Mountable Concrete Curb" have been added. Please void Page No. 50 in your proposal and staple the revised Page No. 50 thereto.

On Page No. 1 of the item sheets, by copy of this addendum, the quantity for Line Item "7-0106000000-E-230 Borrow Excavation" is hereby increased from 111,600 CY to 190,000 CY. The Contractor's bid must be based on this revised pay item quantity.

On Page No. 16 of the item sheets, by copy of this addendum, the following new Pay Item is hereby added: "252-2308000000-E-840 Masonry Drainage Structures (Quantity = 41 LF)". The Contractor's bid must include the new pay item.

The following revisions have been made to the Roadway plans:

Sheet No. 3 "Summary of Quantities" has been revised to reflect the above noted quantity changes. Please void Sheet No. 3 (first sheet) in your plans and staple the revised Sheet No. 3 thereto.

Sheet No. 3-E has been revised to show the total quantity of "Masonry Drainage Structure by linear foot". Please void Sheet No. 3-E in your plans and staple the revised Sheet No. 3-E thereto.

**MAILING ADDRESS:**  
NC DEPARTMENT OF TRANSPORTATION  
DESIGN SERVICES UNIT  
1591 MAIL SERVICE CENTER  
RALEIGH NC 27699-1591

TELEPHONE: 919-250-4128  
FAX: 919-250-4119

WEBSITE: [WWW.NCDOT.ORG/](http://WWW.NCDOT.ORG/)

**LOCATION:**  
CENTURY CENTER COMPLEX  
ENTRANCE B2  
1020 BIRCH RIDGE DRIVE  
RALEIGH NC

Page 2  
Contract ID: C201776  
Randolph County (K-3807)


Sheet No. 3-G "Summary of Earthwork" has been revised to reflect the above noted quantity changes. Please void Sheet No. 3-G in your plans and staple the revised Sheet No. 3-G thereto.

The following revision has been made to the Subsurface Plans:

Sheet No. 3 of 89 has been revised to reflect the above noted quantity change. Please void Sheet No. 3 of 89 in your subsurface plans and staple the revised Sheet No. 3 of 89 thereto.

The Expedite File has been updated to reflect these quantity revisions. Please download the Expedite Addendum File and follow the instructions for applying the addendum. Bid Express will not accept your bid unless the addendum has been applied.

Sincerely,



R. A. Garris, PE  
Contract Officer

RAG/jag/blr  
Attachments

cc: Mr. W. S. Varnedoe, PE  
Mr. E. C. Powell, PE  
Mr. Tim Johnson, PE  
Ms. D. M. Barbour, PE  
Mr. Art McMillan, PE  
Mr. J. V. Barbour, PE  
Mr. Don Lee (Attn: Mr. Paul Stankiewicz)  
Mr. Mark Staley (2)  
Mr. Robert Memory  
Mr. R. E. Davenport, Jr., PE  
Ms. Norma Smith  
Mr. Ronnie Higgins  
File (2)

**PERMANENT SEEDING AND MULCHING:**

(7-1-95)

SP16 R01

The Department desires that permanent seeding and mulching be established on this project as soon as practical after slopes or portions of slopes have been graded. As an incentive to obtain an early stand of vegetation on this project, the Contractor's attention is called to the following:

For all permanent seeding and mulching that is satisfactorily completed in accordance with the requirements of Section 1660, Seeding and Mulching, and within the following percentages of elapsed contract times, an additional payment will be made to the Contractor as an incentive additive. The incentive additive will be determined by multiplying the number of acres of seeding and mulching satisfactorily completed times the contract unit bid price per acre for Seeding and Mulching times the appropriate percentage additive.

Percentage of Elapsed Contract Time	Percentage Additive
0% - 30%	30%
30.01% - 50%	15%

Percentage of elapsed contract time is defined as the number of calendar days from the date of availability of the contract to the date the permanent seeding and mulching is acceptably completed divided by the total original contract time.

**COOPERATION BETWEEN CONTRACTORS:**

(7-1-95)

SP1 G133

The Contractor's attention is directed to Article 105-7 of the *2006 Standard Specifications*.

There will be a separate contract let by the Seagrove-Ulah Metropolitan Water District for the extension of water and sewer lines to serve the proposed vest area which will be under construction at the same time as this project.

The Contractor on this project shall cooperate with the Contractor working within or adjacent to the limits of this project to the extent that the work can be carried out to the best advantage of all concerned.

**MOUNTABLE CONCRETE CURB:**

At locations shown on the plans and labeled as "Reinforced Concrete Curbing" on Sheet LD-016 in the plans, the Contractor shall construct a transition from 2'-6" Concrete Curb and Gutter dimensions to the mountable curb expressway gutter section for driveway access, and ending flush with the driveway pavement.

No additional payment will be made for constructing the transition from the 2'-6" concrete curb and gutter section thru the mountable curb expressway gutter and ending flush at the driveway pavement, as the complete transition up to the point where the expressway gutter become flush with the driveway pavement will be included in the measurements made for "2'-6" Concrete Curb and Gutter". Payment will be made at the contract unit price per linear foot for "2'-6" Concrete Curb and Gutter".