

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	1220000000-E	545	INCIDENTAL STONE BASE	1,275 TON		
0003	1245000000-E	SP	SHOULDER RECONSTRUCTION	37.78 SMI		
0004	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	2,200 SY		
0005	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (1-1/2" TO 3")	121,088 SY		
0006	1330000000-E	607	INCIDENTAL MILLING	6,817 SY		
0007	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	2,180 TON		
0008	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	24,524 TON		
0009	1520000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE S9.5B (LEVELING COURSE)	200 TON		
0010	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	12,989 TON		
0011	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	1,577 TON		
0012	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	780 TON		
0013	1704000000-E	SP	PATCHING EXISTING PAVEMENT	3,690 TON		
0014	2830000000-N	858	ADJUSTMENT OF MANHOLES	130 EA		
0015	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	32 EA		
0016	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	205,344 LF		
0017	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	235,562 LF		

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	100 LF		
001E	4705000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (16", 120 MILS)	670 LF		
002C	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	2,846 LF		
0021	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	142 EA		
0022	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	299 EA		
002E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	52,480 LF		
0024	4830000000-E	1205	PAINT PAVEMENT MARKING LINES (16")	450 LF		
002E	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	1,130 LF		
002E	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	20 EA		
0027	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	3,341 EA		
002E	6084000000-E	1660	SEEDING & MULCHING	24.21 ACR		
002E	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	24,500 LF		
003C	7456000000-E	1726	LEAD-IN CABLE (*****) (18-4)	7,750 LF		

1502/Jan14/Q712178.99/D10109010000/E30

Total Amount Of Bid For Entire Project :

Contract No: C201997

County: Durham

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General