

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (21 + 95.000)	Lump Sum	L.S.	
0003	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0004	0057000000-E	226	UNDERCUT EXCAVATION	500 CY		
0005	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0006	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	100 TON		
0007	0106000000-E	230	BORROW EXCAVATION	5,500 CY		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	40 CY		
0009	0195000000-E	265	SELECT GRANULAR MATERIAL	400 CY		
001C	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	400 SY		
0011	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	20 TON		
0012	0344000000-E	310	18" SIDE DRAIN PIPE	72 LF		
0013	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	52 LF		
0014	0995000000-E	340	PIPE REMOVAL	61 LF		
001E	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0016	1330000000-E	607	INCIDENTAL MILLING	100 SY		
0017	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	600 TON		
001E	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	350 TON		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	450 TON		
002C	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	70 TON		
0021	2000000000-N	806	RIGHT OF WAY MARKERS	19 EA		
0022	2022000000-E	815	SUBDRAIN EXCAVATION	70 CY		
0023	2033000000-E	815	SUBDRAIN FINE AGGREGATE	55 CY		
0024	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	300 LF		
002E	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	9 EA		
002E	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0027	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
002E	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3 EA		
002E	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	1 EA		
003C	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0031	2556000000-E	846	SHOULDER BERM GUTTER	56 LF		
0032	3030000000-E	862	STEEL BM GUARDRAIL	450 LF		
0033	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0034	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
003E	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
003E	3628000000-E	876	RIP RAP, CLASS I	30 TON		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	3649000000-E	876	RIP RAP, CLASS B	75 TON		
003E	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	580 SY		
003E	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	5 SF		
004C	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	13 LF		
0041	4102000000-N	904	SIGN ERECTION, TYPE E	1 EA		
0042	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	11 EA		
004E	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	48 SF		
0044	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96 SF		
004E	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	52 SF		
004E	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	2 EA		
0047	4430000000-N	1130	DRUMS	50 EA		
004E	4435000000-N	1135	CONES	50 EA		
004E	4445000000-E	1145	BARRICADES (TYPE III)	32 LF		
005C	4450000000-N	1150	FLAGGER	640 HR		
0051	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	2 EA		
0052	4480000000-N	1165	TMIA	2 EA		
005E	4485000000-E	1170	PORTABLE CONCRETE BARRIER	650 LF		
0054	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	103 EA		
005E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	23,420 LF		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	13 EA		
0057	6000000000-E	1605	TEMPORARY SILT FENCE	1,000 LF		
005E	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75 TON		
005E	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	310 TON		
006C	6012000000-E	1610	SEDIMENT CONTROL STONE	190 TON		
0061	6015000000-E	1615	TEMPORARY MULCHING	2.5 ACR		
0062	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0063	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.5 TON		
0064	6024000000-E	1622	TEMPORARY SLOPE DRAINS	35 LF		
006E	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	1 EA		
006E	6029000000-E	SP	SAFETY FENCE	250 LF		
0067	6030000000-E	1630	SILT EXCAVATION	1,025 CY		
006E	6036000000-E	1631	MATTING FOR EROSION CONTROL	885 SY		
006E	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	210 SY		
007C	6042000000-E	1632	1/4" HARDWARE CLOTH	60 LF		
0071	6070000000-N	SP	SPECIAL STILLING BASINS	4 EA		
0072	6071030000-E	SP	COIR FIBER BAFFLES	300 LF		
0073	6084000000-E	1660	SEEDING & MULCHING	2.5 ACR		
0074	6087000000-E	1660	MOWING	1.5 ACR		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
007E	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
007E	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0077	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
007E	6108000000-E	1665	FERTILIZER TOPDRESSING	2 TON		
007E	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
008C	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
0081	6123000000-E	1670	REFORESTATION	0.5 ACR		

***** BEGIN SCHEDULE AA *****
***** (3 ALTERNATES) *****

0082 AA1	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	44 LF		
-------------	--------------	-----	---------------------------------	----------	--	--

*** OR ***

0083 AA2	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	28 LF		
-------------	--------------	-----	---------------------------------	----------	--	--

0084 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (15")	16 LF		
-------------	--------------	----	-------------------------------	----------	--	--

*** OR ***

0085 AA3	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	28 LF		
-------------	--------------	-----	---------------------------------	----------	--	--

0086 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (15", 0.064")	16 LF		
-------------	--------------	----	--	----------	--	--

***** END SCHEDULE AA *****

STRUCTURE ITEMS

0087	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (21 +95.00-L-)	Lump Sum	L.S.	
008E	8096000000-E	SP	PILE EXCAVATION IN SOIL	75 LF		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0089	8097000000-E	SP	PILE EXCAVATION NOT IN SOIL	15 LF		
009C	8105540000-E	SP	3'-6" DIA DRILLED PIERS IN SOIL	25 LF		
0091	8105640000-E	SP	3'-6" DIA DRILLED PIERS NOT IN SOIL	11 LF		
0092	8113000000-N	SP	SID INSPECTION	1 EA		
0093	8115000000-N	SP	CROSSHOLE SONIC LOGGING	1 EA		
0094	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	6,600 SF		
009E	8161000000-E	420	GROOVING BRIDGE FLOORS	6,017 SF		
009E	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	59.2 CY		
0097	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (21 +95.00-L-)	Lump Sum	L.S.	
009E	8217000000-E	425	REINFORCING STEEL (BRIDGE)	11,531 LB		
009E	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	1,119 LB		
010C	8280000000-E	440	APPROX LBS STRUCTURAL STEEL	205,700 LS		
0101	8364000000-E	450	HP12X53 STEEL PILES	210 LF		
0102	8503000000-E	460	CONCRETE BARRIER RAIL	400 LF		
0103	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	368 TON		
0104	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	409 SY		
010E	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	

Contract No: C201769

County: Guilford

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General