

FINAL PAVEMENT MARKING SCHEDULE

SYMBOL	DESCRIPTION	PAY ITEM	PAY ITEM QUANTITY BREAKDOWN	TOTAL QUANTITY
	<u>PAVEMENT MARKINGS</u>			
		COLD APPLIED PLASTIC (4") Type 3-Permanent Std		
CA	WHITE EDGELINE		200 LF	
CF	10 FT. YELLOW SKIP		25 LF	
			TOTAL	225 LF
		PAINT(4")		
PA	WHITE EDGELINE (2X)		73708 LF	
PD	2 FT. WHITE MINISKIP (2X)		53 LF	
PE	WHITE SOLID LANE LINE (2X)		600 LF	
PF	10 FT. YELLOW SKIP (2X)		2304 LF	
PI	YELLOW DOUBLE CENTER (2X)		69648 LF	
			TOTAL	146313 LF
		PAINT(8")		
PX	WHITE CROSSWALK LINE (2X)		480 LF	
			TOTAL	480 LF
		PAINT(16")		
P3	WHITE LINE, RR X (2X)		160 LF	
			TOTAL	160 LF
		PAINT(24")		
P4	WHITE STOPBAR (2X)		360 LF	
			TOTAL	360 LF
		THERMOPLASTIC(4", 90 MILS)		
TA	WHITE EDGELINE		1400 LF	
			TOTAL	1400 LF
		THERMOPLASTIC(4", 120 MILS)		
TF	10 FT. YELLOW SKIP		175 LF	
			TOTAL	175 LF
		PAINT MARKING SYMBOLS		
QA	LEFT TURN ARROW (2X)		8 EA	
QE	COMBO.STRAIGHT/RIGHT (2X)		8 EA	
			TOTAL	16 EA
		PAINT MARKING CHARACTERS		
QI	ALPHANUMERIC CHAR. (2X)		8 EA	
			TOTAL	8 EA
		MARKERS		
		PERMANENT RAISED PAVEMENT MARKERS		
MA	YELLOW & YELLOW		288 EA	
			TOTAL	288 EA

NOTE: FOR EACH PAINT PAVEMENT MARKING ITEM, 1X IMPLIES A SINGLE APPLICATION, 2X IMPLIES TWO APPLICATIONS, AND 3X IMPLIES THREE APPLICATIONS.

SEPI ENGINEERING GROUP
 1025 Wade Avenue
 Raleigh, NC 27605
 Tel: 919-789-9977 Fax: 919-789-9991

APPROVED: DATE: 11/5/03

SEAL

SEAL
022568
ENGINEER
STEVEN L. SCOTT

FINAL PAVEMENT MARKING SCHEDULE

SCALE: NONE	REVISIONS
DATE: 10-26	
DWG. BY: RLW	
DESIGN BY: RLW	
REVIEWED BY: SLS	