

County : Randolph

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0003	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUBBING	3 ACR		
0004	0022000000-E	225	UNCLASSIFIED EXCAVATION	181,200 CY		
0005	0036000000-E	225	UNDERCUT EXCAVATION	17,635 CY		
0006	0080000000-E	SP	CLASS IV SUBGRADE STABILIZATION	8,400 TON		
0007	0106000000-E	230	BORROW EXCAVATION	190,000 CY		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	10,910 CY		
0009	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	2,970 SY		
0010	0192000000-N	260	PROOF ROLLING	18 HR		
0011	0195000000-E	265	SELECT GRANULAR MATERIAL	5,650 CY		
0012	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	5,650 SY		
0013	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	1,000 TON		
0014	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	1,432 LF		
0015	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	192 LF		
0016	0396000000-E	310	42" RC PIPE CULVERTS, CLASS III	148 LF		
0017	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	548 LF		
0018	0720000000-E	310	24" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	452 LF		

County : Randolph

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0726000000-E	310	30" BIT COAT CS PIPE CULVERTS, TYPE B 0.079" THICK	132 LF		
0020	0732000000-E	310	36" BIT COAT CS PIPE CULVERTS, TYPE B 0.079" THICK	84 LF		
0021	0804000000-E	310	*** BIT COAT CS PIPE ELBOWS, TYPE B ***** THICK (36", 0.079")	2 EA		
0022	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	14 EA		
0023	0808000000-E	310	24" BIT COAT CS PIPE ELBOWS, T YPE B 0.064" THICK	8 EA		
0024	0809000000-E	310	30" BIT COAT CS PIPE ELBOWS, T YPE B 0.079" THICK	4 EA		
0025	0986000000-E	SP	GENERIC PIPE ITEM 6" HDPE PIPE	48 LF		
0026	0986000000-E	SP	GENERIC PIPE ITEM 6" PERF. HDPE	105 LF		
0027	0992000000-E	SP	GENERIC PIPE ITEM 6" HDPE CAPS, TEES, Y'S & ELBOWS	17 EA		
0028	0995000000-E	340	PIPE REMOVAL	181 LF		
0029	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
0030	1044000000-E	501	LIME TREATED SOIL (SLURRY METHOD)	49,078 SY		
0031	1066000000-E	501	LIME FOR LIME TREATED SOIL	345 TON		
0032	1077000000-E	SP	#57 STONE	100 TON		
0033	1110000000-E	510	STABILIZER AGGREGATE	1,000 TON		
0034	1121000000-E	520	AGGREGATE BASE COURSE	18,000 TON		
0035	1176000000-E	542	SOIL CEMENT BASE	49,078 SY		

County : Randolph

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	1187000000-E	542	PORTLAND CEMENT FOR SOIL CEMENT BASE	405 TON		
0037	1209000000-E	543	ASPHALT CURING SEAL	7,363 GAL		
0038	1220000000-E	545	INCIDENTAL STONE BASE	50 TON		
0039	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	2,700 TON		
0040	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	12,960 TON		
0041	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	10,030 TON		
0042	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	730 TON		
0043	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	605 TON		
0044	2022000000-E	815	SUBDRAIN EXCAVATION	224 CY		
0045	2033000000-E	815	SUBDRAIN FINE AGGREGATE	168 CY		
0046	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	1,000 LF		
0047	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	30 EA		
0048	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	2 EA		
0049	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	12 LF		
0050	2143000000-E	818	BLOTTING SAND	20 TON		
0051	2209000000-E	838	ENDWALLS	7.9 CY		
0052	2253000000-E	840	PIPE COLLARS	1.06 CY		
0053	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	100 EA		
0054	2352000000-N	840	FRAME WITH GRATE, STD 840.**** (840.20)	3 EA		

County : Randolph

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0055	2354000000-N	840	FRAME WITH GRATE, STD 840.22	17 EA		
0056	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	7 EA		
0057	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	40 EA		
0058	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	27 EA		
0059	2396000000-N	840	FRAME WITH COVER, STD 840.54	5 EA		
0060	2462000000-E	SP	*** SLUICE GATE (24")	2 EA		
0061	2462000000-E	SP	*** SLUICE GATE (6")	2 EA		
0062	2473000000-N	SP	GENERIC DRAINAGE ITEM RETICULINE FRAME & GRATE	1 EA		
0063	2473000000-N	SP	GENERIC DRAINAGE ITEM TRASH RACK	2 EA		
0064	2489000000-E	SP	GENERIC DRAINAGE ITEM 10MM IMPERVIOUS PLASTIC	1,197 SY		
0065	2495000000-E	SP	GENERIC DRAINAGE ITEM 4" CONCRETE PAD FOR TRASH RACK	1 CY		
0066	2495000000-E	SP	GENERIC DRAINAGE ITEM WASHED CONCRETE SAND	112 CY		
0067	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	18,600 LF		
0068	2591000000-E	848	4" CONCRETE SIDEWALK	5,075 SY		
0069	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	20 EA		
0070	2612000000-E	848	6" CONCRETE DRIVEWAY	500 SY		
0071	3030000000-E	862	STEEL BM GUARDRAIL	2,450 LF		

County : Randolph

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
0073	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	4 EA		
0074	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	2 EA		
0075	3360000000-E	863	REMOVE EXISTING GUARDRAIL	1,780 LF		
0076	3503000000-E	866	WOVEN WIRE FENCE, 47" FABRIC	13,420 LF		
0077	3509000000-E	866	4" TIMBER FENCE POSTS, 7'-6" LONG	875 EA		
0078	3515000000-E	866	5" TIMBER FENCE POSTS, 8'-0" LONG	171 EA		
0079	3524000000-E	SP	VINYL COATED CHAIN LINK FENCE, *** FABRIC (72")	550 LF		
0080	3536000000-E	866	CHAIN LINK FENCE, 48" FABRIC	460 LF		
0081	3539000000-E	866	METAL LINE POSTS FOR *** CHAIN LINK FENCE (72")	54 EA		
0082	3542000000-E	866	METAL LINE POSTS FOR 48" CHAIN LINK FENCE	40 EA		
0083	3545000000-E	866	METAL TERMINAL POSTS FOR *** CHAIN LINK FENCE (72")	2 EA		
0084	3548000000-E	866	METAL TERMINAL POSTS FOR 48" CHAIN LINK FENCE	5 EA		
0085	3575000000-E	SP	GENERIC FENCING ITEM 6' WOOD FENCE	40 LF		
0086	3575000000-E	SP	GENERIC FENCING ITEM WOOD SPLIT RAIL FENCE	1,009 LF		
0087	3628000000-E	876	RIP RAP, CLASS I	788 TON		
0088	3649000000-E	876	RIP RAP, CLASS B	117 TON		

County : Randolph

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0089	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	615		SY
0090	4048000000-E	902	REINFORCED CONCRETE SIGN FOUNDATIONS	6		CY
0091	4060000000-E	903	SUPPORTS, BREAKAWAY STEEL BEAM	719		LB
0092	4066000000-E	903	SUPPORTS, SIMPLE STEEL BEAM	3,839		LB
0093	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	939		LF
0094	4078000000-E	903	SUPPORTS, 2-LB STEEL U-CHANNEL	2		EA
0095	4096000000-N	904	SIGN ERECTION, TYPE D	6		EA
0096	4102000000-N	904	SIGN ERECTION, TYPE E	36		EA
0097	4110000000-N	904	SIGN ERECTION, TYPE *** (GROUND MOUNTED) (A)	7		EA
0098	4110000000-N	904	SIGN ERECTION, TYPE *** (GROUND MOUNTED) (B)	1		EA
0099	4114000000-N	904	SIGN ERECTION, MILEMARKERS	2		EA
0100	4138000000-N	907	DISPOSAL OF SUPPORT, STEEL BEAM	2		EA
0101	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	4		EA
0102	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	352		SF
0103	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	192		SF
0104	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	40		SF
0105	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	2		EA
0106	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	2		EA
0107	4430000000-N	1130	DRUMS	88		EA

County : Randolph

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0108	4445000000-E	1145	BARRICADES (TYPE III)	48 LF		
0109	4480000000-N	1165	TMIA	2 EA		
0110	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	7,200 LF		
0111	4688000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 90 MILS)	7,600 LF		
0112	4690000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 120 MILS)	593 LF		
0113	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	2,900 LF		
0114	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	49 EA		
0115	4775000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (6") (IV)	6,400 LF		
0116	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	167 EA		
0117	4935000000-N	1267	FLEXIBLE DELINEATORS (CRYSTAL)	73 EA		
0118	4940000000-N	1267	FLEXIBLE DELINEATORS (YELLOW)	48 EA		
0119	5070000000-N	1405	STANDARD FOUNDATION ***** (TYPE R1)	76 EA		
0120	5155000000-E	1409	ELECTRICAL DUCT, TYPE BD, SIZE ***** (3")	803 LF		
0121	5155000000-E	1409	ELECTRICAL DUCT, TYPE BD, SIZE ***** (4")	50 LF		
0122	5180000000-E	1410	** #4 W/G FEEDER CIRCUIT (2)	196 LF		
0123	5185000000-E	1410	** #2 W/G FEEDER CIRCUIT (2)	535 LF		
0124	5205000000-E	1410	** #8 W/G FEEDER CIRCUIT IN ***** CONDUIT (2, 1-1/2")	5,523 LF		

County : Randolph

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0125	5210000000-E	1410	** #6 W/G FEEDER CIRCUIT IN ***** CONDUIT (2, 1-1/2")	385	LF	
0126	5215000000-E	1410	** #4 W/G FEEDER CIRCUIT IN ***** CONDUIT (2, 1-1/2")	8,166	LF	
0127	5220000000-E	1410	** #2 W/G FEEDER CIRCUIT IN ***** CONDUIT (2, 1-1/2")	4,501	LF	
0128	5240000000-N	1411	ELECTRICAL JUNCTION BOXES ***** (TYPE PC18)	14	EA	
0129	5240000000-N	1411	ELECTRICAL JUNCTION BOXES ***** (TYPE PG30)	6	EA	
0130	5240000000-N	1411	ELECTRICAL JUNCTION BOXES ***** (TYPE PG36)	2	EA	
0131	5265000000-E	SP	GENERIC LIGHTING ITEM 2-#2 W/ NEUTRAL FEEDER CIRCUIT	48	LF	
0132	5265000000-E	SP	GENERIC LIGHTING ITEM 2-#2 W/ NEUTRAL FEEDER CIRCUIT IN 2" CONDUIT	687	LF	
0133	5270000000-N	SP	GENERIC LIGHTING ITEM BOLLARD LGT STD	20	EA	
0134	5270000000-N	SP	GENERIC LIGHTING ITEM DAVIT STYLE LGT STD, MH 25', SA 6'	2	EA	
0135	5270000000-N	SP	GENERIC LIGHTING ITEM DAVIT STYLE LGT STD, MH 35', SA 6'	74	EA	
0136	5270000000-N	SP	GENERIC LIGHTING ITEM LIGHT CONTROL EQUIPMENT, TYPE RA, 120/208V	2	EA	
0137	5270000000-N	SP	GENERIC LIGHTING ITEM POST TOP LGT STD	56	EA	
0138	5270000000-N	SP	GENERIC LIGHTING ITEM POST TOP LUMINAIRE, 100W, MH, TYPE 5, CUTOFF	56	EA	



County : Randolph

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0139	5270000000-N	SP	GENERIC LIGHTING ITEM STD FOUNDATION, TYPE B1	20 EA		
0140	5270000000-N	SP	GENERIC LIGHTING ITEM STD FOUNDATION, TYPE R1S	56 EA		
0141	6000000000-E	1605	TEMPORARY SILT FENCE	2,280 LF		
0142	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	580 TON		
0143	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	2,150 TON		
0144	6012000000-E	1610	SEDIMENT CONTROL STONE	1,700 TON		
0145	6015000000-E	1615	TEMPORARY MULCHING	49 ACR		
0146	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	1,750 LB		
0147	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	7 TON		
0148	6024000000-E	1622	TEMPORARY SLOPE DRAINS	1,050 LF		
0149	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	13 EA		
0150	6029000000-E	SP	SAFETY FENCE	2,350 LF		
0151	6030000000-E	1630	SILT EXCAVATION	18,630 CY		
0152	6036000000-E	1631	MATTING FOR EROSION CONTROL	17,375 SY		
0153	6037000000-E	SP	COIR FIBER MAT	50 SY		
0154	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	6,125 SY		
0155	6042000000-E	1632	1/4" HARDWARE CLOTH	1,500 LF		
0156	6071030000-E	SP	COIR FIBER BAFFLES	2,700 LF		
0157	6071050000-E	SP	*** SKIMMER (1-1/2")	4 EA		

County: Randolph

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0158	6071050000-E	SP	*** SKIMMER (2")	1 EA		
0159	6071050000-E	SP	*** SKIMMER (2-1/2")	1 EA		
0160	6071050000-E	SP	*** SKIMMER (4")	1 EA		
0161	6071050000-E	SP	*** SKIMMER (6")	1 EA		
0162	6084000000-E	1660	SEEDING & MULCHING	62 ACR		
0163	6087000000-E	1660	MOWING	29 ACR		
0164	6090000000-E	1661	SEED FOR REPAIR SEEDING	450 LB		
0165	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	1 TON		
0166	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	1,150 LB		
0167	6102000000-E	1664	SODDING	3,650 SY		
0168	6108000000-E	1665	FERTILIZER TOPDRESSING	46.5 TON		
0169	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
0170	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	27 EA		
0171	6123000000-E	1670	REFORESTATION	7.05 ACR		
0172	6245000000-N	1670	CERCIS CANADENSIS, REDBUD, (6'-8', B&B)	28 EA		
0173	6260000000-N	1670	CORNUS FLORIDA, FLOWERING DOG- WOOD, (6'-8', B&B)	31 EA		
0174	6410000000-N	1670	JUNIPERUS VIRGINIANA, EASTERN RED CEDAR, (6'-8', B&B)	38 EA		
0175	6560000000-N	1670	QUERCUS COCCINEA, SCARLET OAK, (10'-12', B&B)	3 EA		

County : Randolph

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0176	6575000000-N	1670	QUERCUS PHELLOS, WILLOW OAK, (10'-12', B&B)	8 EA		
0177	6580000000-N	1670	QUERCUS RUBRA, NORTHERN RED OAK, (10'-12', B&B)	2 EA		
0178	6640000000-N	1670	GENERIC PLANTING ITEM ACER SACCHARUM 'LEGACY', LEGACY SUGAR MAPLE, 10'-12', B&B	13 EA		
0179	6640000000-N	1670	GENERIC PLANTING ITEM AMELANCHER 'AUTUMN BRILLIANCE' AUTUMN BRILLIANCE SERVICEBERRY, 6'-8',B&B	50 EA		
0180	6640000000-N	1670	GENERIC PLANTING ITEM CELPHALOTAXUS HARRINGTONIA PROTRATA PROSTRATE JAPANESE YEW, #7 CONT	126 EA		
0181	6640000000-N	1670	GENERIC PLANTING ITEM ECHINACEA PURPUREA, PURPLE CONEFLOWER, 4" POT	59 EA		
0182	6640000000-N	1670	GENERIC PLANTING ITEM ERAGROSTIS CURVULA ,LOVE GRASS 2-1/2" PLUG	6,955 EA		
0183	6640000000-N	1670	GENERIC PLANTING ITEM ILEX 'LIBERTY', LIBERTY HOLLY, 6', B&B	44 EA		
0184	6640000000-N	1670	GENERIC PLANTING ITEM ILEX VOMITORIA 'NANA, DWARF YAUPON HOLLY , # 7 CONT	76 EA		
0185	6640000000-N	1670	GENERIC PLANTING ITEM JUNCUS EFFUSUS, SOFT RUSH # 1 CONT	59 EA		
0186	6640000000-N	1670	GENERIC PLANTING ITEM LAGERSTROEMIA 'NATCHEZ', NATCHEZ CRAPE MYRTLE, 10'- 12', B&B	7 EA		
0187	6640000000-N	1670	GENERIC PLANTING ITEM MAGNOLIA GRANDIFLORA 'BRACKEN' S BROWN BEAUTY, SOUTHERN MAGNOLIA ,10' -12', B&B	11 EA		

County : Randolph

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0188	6640000000-N	1670	GENERIC PLANTING ITEM MUHLENBERGIA CAPILLARIS, PINK MUHLY GRASS , # 1 CONT	157 EA		
0189	6640000000-N	1670	GENERIC PLANTING ITEM PINUS TAEDA, LOBLOLLY PINE, 8'-10', B&B	87 EA		
0190	6640000000-N	1670	GENERIC PLANTING ITEM QUERCUS FALCATA, SOUTHERN RED OAK, 10'-12', B&B	2 EA		
0191	6640000000-N	1670	GENERIC PLANTING ITEM QUERCUS LYRATA, OVERCUP OAK, 10'-12', B&B	11 EA		
0192	6640000000-N	1670	GENERIC PLANTING ITEM QUERCUS SHUMARDII, SHUMARD OAK, 10'-12', B&B	15 EA		
0193	6640000000-N	1670	GENERIC PLANTING ITEM RUDBECKIA FULGIDA 'GOLDSTRUM' ORANGE CONEFLOWER , 4" POT	67 EA		
0194	6640000000-N	1670	GENERIC PLANTING ITEM ULMUS AMERICANA 'PRINCETON' PRINCETON ELM , 10'-12', B&B	12 EA		
0195	6650000000-E	1670	MULCH FOR PLANTING	1,600 CY		
0196	6655000000-E	1670	WATER FOR PLANTING	10 M/G		
0197	6665000000-E	1670	POSTEMERGENT HERBICIDAL TREAT- MENT FOR PLANT BEDS	100 SY		
0198	6670000000-E	1670	PREEMERGENT HERBICIDAL TREAT- MENT FOR PLANT BEDS	100 SY		
0199	6674000000-N	SP	GENERIC PLANTING ITEM (LS) LANDSCAPE GRADING	Lump Sum	L.S.	
0200	6690000000-E	SP	GENERIC PLANTING ITEM STEEL LANDSCAPE EDGING	365 LF		
0201	6885000000-E	SP	6" CONCRETE REINFORCED PAD	133 SY		
0202	6890000000-E	SP	CONCRETE STEPS	90 CY		
0203	6895000000-E	SP	HANDRAIL ON STEPS	191 LF		

County : Randolph

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0204	6900000000-E	SP	TOPSOIL	300 CY		
0205	6905000000-N	SP	PICNIC TABLE, TERRAZZO & STEEL	8 EA		
0206	6910000000-N	SP	PICNIC SHELTER, SINGLE PICNIC TABLE	11 EA		
0207	6915000000-N	SP	OUTDOOR PARK STOVE	6 EA		
0208	6945000000-E	SP	3/4" POST TYPE YARD HYDRANT	9 EA		
0209	6970000000-N	SP	GENERIC REST AREA ITEM 1" GATE VALVE AND BOX	7 EA		
0210	6970000000-N	SP	GENERIC REST AREA ITEM 3/4" GATE VALVE AND BOX	11 EA		
0211	6970000000-N	SP	GENERIC REST AREA ITEM BENCH WITH STONE BASE	13 EA		
0212	6970000000-N	SP	GENERIC REST AREA ITEM BOULDER PLACEMENT	20 EA		
0213	6970000000-N	SP	GENERIC REST AREA ITEM CONCRETE PATIO TABLE	4 EA		
0214	6970000000-N	SP	GENERIC REST AREA ITEM FLAGPOLE, ALUMINUM	4 EA		
0215	6970000000-N	SP	GENERIC REST AREA ITEM SPECIAL REST AREA SIGNAGE (NBL)	1 EA		
0216	6970000000-N	SP	GENERIC REST AREA ITEM SPECIAL REST AREA SIGNAGE (SBL)	1 EA		
0217	6970000000-N	SP	GENERIC REST AREA ITEM STONE ENTRANCE SIGN BASE	2 EA		
0218	6970000000-N	SP	GENERIC REST AREA ITEM STORAGE BUILDING CONSTRUCTION	2 EA		
0219	6970000000-N	SP	GENERIC REST AREA ITEM WASTE CONTAINER	26 EA		
0220	6975000000-N	SP	GENERIC REST AREA ITEM CONSTRUCTION OF REST AREA BUILDING (NLB)	Lump Sum	L.S.	

County : Randolph

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0221	6975000000-N	SP	GENERIC REST AREA ITEM CONSTRUCTION OF REST AREA BUILDING (SBL)	Lump Sum	L.S.	
0222	6975000000-N	SP	GENERIC REST AREA ITEM CONSTRUCTION OF VENDING MACHINE BUILDING (NBL)	Lump Sum	L.S.	
0223	6975000000-N	SP	GENERIC REST AREA ITEM CONSTRUCTION OF VENDING MACHINE BUILDING (SBL)	Lump Sum	L.S.	
0224	6975000000-N	SP	GENERIC REST AREA ITEM CONSTRUCTION OF VISITOR CENTER BUILDING (NBL)	Lump Sum	L.S.	
0225	6975000000-N	SP	GENERIC REST AREA ITEM CONSTRUCTION OF VISITOR CENTER BUILDING (SBL)	Lump Sum	L.S.	
0226	6975000000-N	SP	GENERIC REST AREA ITEM IRRIGATION SYSTEM (NBL)	Lump Sum	L.S.	
0227	6975000000-N	SP	GENERIC REST AREA ITEM IRRIGATION SYSTEM (SBL)	Lump Sum	L.S.	
0228	6975000000-N	SP	GENERIC REST AREA ITEM LANDSCAPE LIGHTING (NBL)	Lump Sum	L.S.	
0229	6975000000-N	SP	GENERIC REST AREA ITEM LANDSCAPE LIGHTING (SBL)	Lump Sum	L.S.	
0230	6975000000-N	SP	GENERIC REST AREA ITEM PATIO HANDRAIL (NBL)	Lump Sum	L.S.	
0231	6975000000-N	SP	GENERIC REST AREA ITEM WATER FEATURE (NBL)	Lump Sum	L.S.	
0232	6980000000-E	SP	GENERIC REST AREA ITEM 1" PVC WATER PIPE, SCH 80	2,170 LF		
0233	6980000000-E	SP	GENERIC REST AREA ITEM 3" PVC ENCASEMENT PIPE	534 LF		
0234	6980000000-E	SP	GENERIC REST AREA ITEM 3/4" PVC WATER PIPE, SCH 80	135 LF		
0235	6980000000-E	SP	GENERIC REST AREA ITEM STONE WALL	302 LF		

County : Randolph

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0236	6980000000-E	SP	GENERIC REST AREA ITEM TREE PROTECTION FENCE	225 LF		
0237	6982000000-E	SP	GENERIC REST AREA ITEM COBBLESTONE PAVERS	4,153 SF		
0238	6985000000-E	SP	GENERIC REST AREA ITEM PLACEMENT OF FIELD STONE	15 CY		
***** BEGIN SCHEDULE AA ***** ***** ( 3 ALTERNATES ) *****						
0239 AA1	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	4,240 LF		
0240 AA1	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	1,724 LF		
0241 AA1	0390000000-E	310	36" RC PIPE CULVERTS, CLASS III	816 LF		
*** OR ***						
0242 AA2	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	3,640 LF		
0243 AA2	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	1,172 LF		
0244 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (15")	600 LF		
0245 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (24")	552 LF		
0246 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (36")	816 LF		
*** OR ***						
0247 AA3	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	3,640 LF		
0248 AA3	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	1,172 LF		
0249 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (15",0.064")	600 LF		

County : Randolph

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0250 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (24",0.064")	552 LF		
0251 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (36",0.064")	816 LF		
***** END SCHEDULE AA *****						
0252	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	41 LF		
1612/Feb07/Q784000.51/D1055048380000/E252			Total Amount Of Bid For Entire Project :			



**Contract No: C201776**

**County: Randolph**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General