

County : Stokes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (18+20.37)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	350 CY		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	21 CY		
0008	0141000000-E	240	BERM DITCH CONSTRUCTION	100 LF		
0009	0195000000-E	265	SELECT GRANULAR MATERIAL	500 CY		
0010	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
0011	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	29 TON		
0012	0343000000-E	310	15" SIDE DRAIN PIPE	68 LF		
0013	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	200 LF		
0014	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	10 EA		
0015	1220000000-E	545	INCIDENTAL STONE BASE	30 TON		
0016	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	240 TON		
0017	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	155 TON		
0018	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	225 TON		

County : Stokes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	33 TON		
0020	2000000000-N	806	RIGHT OF WAY MARKERS	8 EA		
0021	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	5 EA		
0022	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	1 EA		
0023	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	4 EA		
0024	2556000000-E	846	SHOULDER BERM GUTTER	105 LF		
0025	3030000000-E	862	STEEL BM GUARDRAIL	375 LF		
0026	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0027	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0028	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0029	3649000000-E	876	RIP RAP, CLASS B	160 TON		
0030	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,210 SY		
0031	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	2 EA		
0032	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (D)	9 SF		
0033	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	12.5 SF		
0034	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	62 LF		
0035	4096000000-N	904	SIGN ERECTION, TYPE D	1 EA		
0036	4102000000-N	904	SIGN ERECTION, TYPE E	2 EA		

County : Stokes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	7 EA		
0038	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	375 SF		
0039	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	151 SF		
0040	4445000000-E	1145	BARRICADES (TYPE III)	64 LF		
0041	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	16 EA		
0042	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	1,000 LF		
0043	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	1,000 LF		
0044	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (III)	660 LF		
0045	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	200 LF		
0046	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	5 EA		
0047	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	12 EA		
0048	6000000000-E	1605	TEMPORARY SILT FENCE	475 LF		
0049	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	90 TON		
0050	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	90 TON		
0051	6012000000-E	1610	SEDIMENT CONTROL STONE	350 TON		
0052	6015000000-E	1615	TEMPORARY MULCHING	1 ACR		
0053	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0054	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.25 TON		

County : Stokes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0055	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0056	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	4 EA		
0057	6029000000-E	SP	SAFETY FENCE	275 LF		
0058	6030000000-E	1630	SILT EXCAVATION	450 CY		
0059	6036000000-E	1631	MATTING FOR EROSION CONTROL	375 SY		
0060	6037000000-E	SP	COIR FIBER MAT	25 SY		
0061	6042000000-E	1632	1/4" HARDWARE CLOTH	150 LF		
0062	6070000000-N	SP	SPECIAL STILLING BASINS	12 EA		
0063	6071030000-E	SP	COIR FIBER BAFFLES	130 LF		
0064	6071050000-E	SP	*** SKIMMER (1-1/2")	4 EA		
0065	6084000000-E	1660	SEEDING & MULCHING	1 ACR		
0066	6087000000-E	1660	MOWING	0.5 ACR		
0067	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0068	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0069	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0070	6108000000-E	1665	FERTILIZER TOPDRESSING	0.5 TON		
0071	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
0072	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
0073	6123000000-E	1670	REFORESTATION	0.1 ACR		

County : Stokes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
STRUCTURE ITEMS						
0074	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (18+20.37-L-)	Lump Sum	L.S.	
0075	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (18+20.37-L-)	Lump Sum	L.S.	
0076	8105560000-E	SP	4'-0" DIA DRILLED PIERS IN SO IL	162.25 LF		
0077	8105660000-E	SP	4'-0" DIA DRILLED PIERS NOT IN SOIL	37 LF		
0078	8111600000-E	SP	PERMANENT STEEL CASING FOR 4'-0" DIA DRILLED PIER	44.87 LF		
0079	8113000000-N	SP	SID INSPECTION	6 EA		
0080	8114000000-N	SP	SPT TESTING	6 EA		
0081	8115000000-N	SP	CROSSHOLE SONIC LOGGING	2 EA		
0082	8119000000-E	412	UNCLASSIFIED STRUCTURE EXCAVA- TION	1,760 CY		
0083	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	112.8 CY		
0084	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (18+20.37-L-)	Lump Sum	L.S.	
0085	8217000000-E	425	REINFORCING STEEL (BRIDGE)	35,328 LB		
0086	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	6,573 LB		
0087	8364000000-E	450	HP12X53 STEEL PILES	603 LF		
0088	8503000000-E	460	CONCRETE BARRIER RAIL	324.21 LF		
0089	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	950 TON		
0090	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	1,060 SY		
0091	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	

County : Stokes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0092	8753200000-E	430	3'-0" X 3'-3" PRESTRESSED CONC BOX BEAMS	1,945.25 LF		

1330/Jan09/Q59641.48/D431414600000/E92

Total Amount Of Bid For Entire Project :

Contract No: C201774

County: Stokes

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General