

County : Burke, Catawba, Iredell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0036000000-E	225	UNDERCUT EXCAVATION	6,861 CY		
0003	0170000000-E	SP	REMOVAL OF EXISTING CONCRETE PAVEMENT SLABS	20,580 SY		
0004	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	20,580 SY		
0005	1121000000-E	520	AGGREGATE BASE COURSE	13,892 TON		
0006	1231000000-E	560	SHOULDER BORROW	22,660 CY		
0007	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (3")	2,000 SY		
0008	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 2")	20,360 SY		
0009	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	9,327 TON		
0010	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	109,807 TON		
0011	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	2,305 TON		
0012	1524200000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5D	138,955 TON		
0013	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	5,562 TON		
0014	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	139 TON		
0015	1567000000-E	SP	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-28	962 TON		
0016	1570000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 76-22	7,643 TON		
0017	1704000000-E	SP	PATCHING EXISTING PAVEMENT	250 TON		

County : Burke, Catawba, Iredell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	1737000000-E	SP	PATCHING CONCRETE PAVEMENT SPALLS	3,000 SF		
0019	1839110000-E	661	ULTRATHIN HOT MIX ASPHALT, TYPE B	18,506 TON		
0020	1839200000-E	661	APPLICATION OF ULTRATHIN HOT MIX ASPHALT	508,920 SY		
0021	1840000000-E	665	MILLED RUMBLE STRIPS (ASPHALT CEMENT CONCRETE)	560,100 LF		
0022	3030000000-E	862	STEEL BM GUARDRAIL	6,000 LF		
0023	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	15 EA		
0024	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	13 EA		
0025	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	73 EA		
0026	3285000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE M-350	9 EA		
0027	3345000000-E	864	REMOVE & RESET EXISTING GUARDRAIL	40,200 LF		
0028	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	704 SF		
0029	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	170 SF		
0030	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	48 SF		
0031	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	4 EA		
0032	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	4 EA		
0033	4430000000-N	1130	DRUMS	300 EA		
0034	4445000000-E	1145	BARRICADES (TYPE III)	48 LF		
0035	4480000000-N	1165	TMIA	4 EA		
0036	4510000000-N	SP	POLICE	60 HR		

County : Burke, Catawba, Iredell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	4688000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 90 MILS)	574,772 LF		
0038	4690000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 120 MILS)	69,347 LF		
0039	4700000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (12", 90 MILS)	42,000 LF		
0040	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	12 EA		
0041	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	1,270,086 LF		
0042	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	42,000 LF		
0043	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	24 EA		
0044	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	275 EA		
0045	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	6,100 EA		
0046	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	
0047	6084000000-E	1660	SEEDING & MULCHING	70 ACR		
0048	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		

0822/Feb11/Q3524761.0/D146365610000/E48

Total Amount Of Bid For Entire Project :

Contract No **C201820**

County (ies): **Burke, Catawba & Iredell**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General