

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0036000000-E	225	UNDERCUT EXCAVATION	1,000 CY		
0003	1121000000-E	520	AGGREGATE BASE COURSE	1,958 TON		
0004	1245000000-E	SP	SHOULDER RECONSTRUCTION	9.6 SMI		
0005	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (3")	53,286 SY		
0006	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (6")	4,463 SY		
0007	1508000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0D	10,644 TON		
0008	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	4,896 TON		
0009	1524200000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5D	8,360 TON		
0010	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	297 TON		
0011	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	501 TON		
0012	1570000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 76-22	763 TON		
0013	1663000000-E	650	OPEN-GRADED ASPHALT FRICTION COURSE, TYPE FC-2 MODIFIED	5,014 TON		
0014	1840000000-E	665	MILLED RUMBLE STRIPS (ASPHALT CEMENT CONCRETE)	63,944 LF		
0015	2619000000-E	850	4" CONCRETE PAVED DITCH	7 SY		
0016	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	1,028 SF		
0017	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	2 EA		
0018	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	2 EA		

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	4430000000-N	1130	DRUMS	400 EA		
0020	4480000000-N	1165	TMIA	2 EA		
0021	4510000000-N	SP	POLICE	2,000 HR		
0022	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	224,940 LF		
0023	4847000000-E	1205	POLYUREA PAVEMENT MARKING LINES (4", *****) (STANDARD GLASS BEADS)	12,640 LF		
0024	4847100000-E	1205	POLYUREA PAVEMENT MARKING LINES (6", *****) (STANDARD GLASS BEADS)	72,174 LF		
0025	4847120000-E	1205	POLYUREA PAVEMENT MARKING LINES (12", *****) (STANDARD GLASS BEADS)	1,800 LF		
0026	4847220000-N	1205	POLYUREA PAVEMENT MARKING SYMBOL (*****) (STANDARD GLASS BEADS)	9 EA		
0027	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	490 EA		
0028	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	490 EA		
0029	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	

1104/Feb11/Q471121.6/D86282740000/E29

Total Amount Of Bid For Entire Project :

Contract No **C202002**

County (ies): **Henderson**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General