

County : Iredell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (22+79.50)	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	600 CY		
0006	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0007	0106000000-E	230	BORROW EXCAVATION	8,820 CY		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	495 CY		
0009	0195000000-E	265	SELECT GRANULAR MATERIAL	750 CY		
0010	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	250 SY		
0011	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	60 TON		
0012	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	136 LF		
0013	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	148 LF		
0014	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	52 LF		
0015	0714000000-E	310	18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	164 LF		
0016	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	2 EA		
0017	0807000000-E	310	18" BIT COAT CS PIPE ELBOWS, T YPE B 0.064" THICK	6 EA		
0018	0995000000-E	340	PIPE REMOVAL	128 LF		

County : Iredell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1220000000-E	545	INCIDENTAL STONE BASE	100	TON	
0020	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	890	TON	
0021	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	530	TON	
0022	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	73	TON	
0023	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	3	TON	
0024	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	8	EA	
0025	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	1.6	LF	
0026	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	2	EA	
0027	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	6	EA	
0028	2556000000-E	846	SHOULDER BERM GUTTER	740	LF	
0029	3030000000-E	862	STEEL BM GUARDRAIL	1,175	LF	
0030	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	75	LF	
0031	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10	EA	
0032	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	2	EA	
0033	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	6	EA	
0034	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4	EA	
0035	3559000000-E	866	** STRAND BARBED WIRE FENCE WITH POSTS (5)	850	LF	
0036	3649000000-E	876	RIP RAP, CLASS B	115	TON	

County : Iredell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	565 SY		
0038	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	3 EA		
0039	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	388 SF		
0040	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	94 SF		
0041	4445000000-E	1145	BARRICADES (TYPE III)	48 LF		
0042	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	10,600 LF		
0043	6000000000-E	1605	TEMPORARY SILT FENCE	300 LF		
0044	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75 TON		
0045	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	220 TON		
0046	6012000000-E	1610	SEDIMENT CONTROL STONE	230 TON		
0047	6015000000-E	1615	TEMPORARY MULCHING	3 ACR		
0048	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	150 LB		
0049	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.5 TON		
0050	6024000000-E	1622	TEMPORARY SLOPE DRAINS	80 LF		
0051	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	1 EA		
0052	6029000000-E	SP	SAFETY FENCE	360 LF		
0053	6030000000-E	1630	SILT EXCAVATION	960 CY		
0054	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,250 SY		
0055	6037000000-E	SP	COIR FIBER MAT	30 SY		

County : Iredell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	180 SY		
0057	6042000000-E	1632	1/4" HARDWARE CLOTH	575 LF		
0058	6071030000-E	SP	COIR FIBER BAFFLES	140 LF		
0059	6071050000-E	SP	*** SKIMMER (1-1/2")	3 EA		
0060	6071050000-E	SP	*** SKIMMER (2")	1 EA		
0061	6084000000-E	1660	SEEDING & MULCHING	3.5 ACR		
0062	6087000000-E	1660	MOWING	2 ACR		
0063	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0064	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	2.75 TON		
0065	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	75 LB		
0066	6108000000-E	1665	FERTILIZER TOPDRESSING	0.25 TON		
0067	6114000000-N	SP	SPECIALIZED HAND MOWING	3 HR		
0068	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		

STRUCTURE ITEMS

0069	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (22+79.50-L-)	Lump Sum	L.S.	
0070	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (22+79.50-L-)	Lump Sum	L.S.	
0071	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (22+79.50-L-)	Lump Sum	L.S.	

County : Iredell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	6,345 SF		
0073	8161000000-E	420	GROOVING BRIDGE FLOORS	5,930 SF		
0074	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	101.2 CY		
0075	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (22+79.50-L-)	Lump Sum	L.S.	
0076	8217000000-E	425	REINFORCING STEEL (BRIDGE)	14,578 LB		
0077	8265000000-E	430	54" PRESTRESSED CONCRETE GIR- DERS	715.96 LF		
0078	8364000000-E	450	HP12X53 STEEL PILES	700 LF		
0079	8384200000-E	450	HP14X73 GALVANIZED STEEL PILES	800 LF		
0080	8503000000-E	460	CONCRETE BARRIER RAIL	365.19 LF		
0081	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	310 TON		
0082	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	345 SY		
0083	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0084	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	

1445/Feb08/Q62807.95/D367412830000/E84

Total Amount Of Bid For Entire Project :

Contract No **C201782**

County (ies): **Iredell**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General