

County : McDowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0022000000-E	225	UNCLASSIFIED EXCAVATION	13,700 CY		
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (15+47.00)	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	50 CY		
0006	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0007	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	400 TON		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	140 CY		
0009	0195000000-E	265	SELECT GRANULAR MATERIAL	400 CY		
0010	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	400 SY		
0011	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	40 TON		
0012	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	28 LF		
0013	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	88 LF		
0014	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	116 LF		
0015	0714000000-E	310	18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	48 LF		
0016	0738000000-E	310	42" BIT COAT CS PIPE CULVERTS, TYPE B 0.109" THICK	20 LF		
0017	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	1 EA		
0018	0995000000-E	340	PIPE REMOVAL	90 LF		

County : McDowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1121000000-E	520	AGGREGATE BASE COURSE	1,113 TON		
0020	1220000000-E	545	INCIDENTAL STONE BASE	25 TON		
0021	1275000000-E	600	PRIME COAT	820 GAL		
0022	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	452 TON		
0023	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	320 TON		
0024	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	1,020 TON		
0025	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	100 TON		
0026	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	25 TON		
0027	2000000000-N	806	RIGHT OF WAY MARKERS	4 EA		
0028	2022000000-E	815	SUBDRAIN EXCAVATION	45 CY		
0029	2033000000-E	815	SUBDRAIN FINE AGGREGATE	35 CY		
0030	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	200 LF		
0031	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	6 EA		
0032	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0033	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0034	2209000000-E	838	ENDWALLS	7.6 CY		
0035	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3 EA		
0036	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	0.3 LF		
0037	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		

County : Mcdowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	2556000000-E	846	SHOULDER BERM GUTTER	52 LF		
0039	3030000000-E	862	STEEL BM GUARDRAIL	1,350 LF		
0040	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	20 EA		
0041	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0042	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0043	3360000000-E	863	REMOVE EXISTING GUARDRAIL	1,281 LF		
0044	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	950 LF		
0045	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (III)	4 EA		
0046	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	4 EA		
0047	3628000000-E	876	RIP RAP, CLASS I	20 TON		
0048	3649000000-E	876	RIP RAP, CLASS B	360 TON		
0049	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,210 SY		
0050	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1 EA		
0051	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	6.25 SF		
0052	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	14 LF		
0053	4102000000-N	904	SIGN ERECTION, TYPE E	1 EA		
0054	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	5 EA		
0055	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	88 SF		

County : Mcdowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96 SF		
0057	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	36 SF		
0058	4430000000-N	1130	DRUMS	37 EA		
0059	4445000000-E	1145	BARRICADES (TYPE III)	32 LF		
0060	4455000000-N	1150	FLAGGER	240 MD		
0061	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	80 EA		
0062	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	12,773 LF		
0063	4847000000-E	1205	POLYUREA PAVEMENT MARKING LINES (4", *****) (STANDARD GLASS BEADS)	6,401 LF		
0064	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	2,100 LF		
0065	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	20 EA		
0066	6000000000-E	1605	TEMPORARY SILT FENCE	2,370 LF		
0067	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	105 TON		
0068	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	650 TON		
0069	6012000000-E	1610	SEDIMENT CONTROL STONE	205 TON		
0070	6015000000-E	1615	TEMPORARY MULCHING	6.5 ACR		
0071	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	250 LB		
0072	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	1 TON		
0073	6024000000-E	1622	TEMPORARY SLOPE DRAINS	420 LF		

County : McDowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	7 EA		
0075	6029000000-E	SP	SAFETY FENCE	300 LF		
0076	6030000000-E	1630	SILT EXCAVATION	2,100 CY		
0077	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,100 SY		
0078	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	320 SY		
0079	6042000000-E	1632	1/4" HARDWARE CLOTH	40 LF		
0080	6071030000-E	SP	COIR FIBER BAFFLES	550 LF		
0081	6084000000-E	1660	SEEDING & MULCHING	7.5 ACR		
0082	6087000000-E	1660	MOWING	4 ACR		
0083	6090000000-E	1661	SEED FOR REPAIR SEEDING	100 LB		
0084	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0085	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	175 LB		
0086	6108000000-E	1665	FERTILIZER TOPDRESSING	5.5 TON		
0087	6114000000-N	SP	SPECIALIZED HAND MOWING	6 HR		
0088	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	27 EA		
0089	6123000000-E	1670	REFORESTATION	0.75 ACR		
STRUCTURE ITEMS						
0090	8007000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP STRUCTURE AT STA ***** (15+47.00-L-)	Lump Sum	L.S.	

County : Mcdowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0091	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (15+47.00-L-)	Lump Sum	L.S.	
0092	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (15+47.00-L-)	Lump Sum	L.S.	
0093	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	3,990 SF		
0094	8161000000-E	420	GROOVING BRIDGE FLOORS	3,953 SF		
0095	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	32.4 CY		
0096	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (15+47.00-L-)	Lump Sum	L.S.	
0097	8217000000-E	425	REINFORCING STEEL (BRIDGE)	6,332 LB		
0098	8280000000-E	440	APPROX LBS STRUCTURAL STEEL	117,500 LS		
0099	8364000000-E	450	HP12X53 STEEL PILES	720 LF		
0100	8503000000-E	460	CONCRETE BARRIER RAIL	236.67 LF		
0101	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	336 TON		
0102	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	373 SY		
0103	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0951/Jan28/Q189127.72/D412508230000/E103			Total Amount Of Bid For Entire Project :			

Contract No **C201805**

County (ies): **McDowell**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General