

County : Northampton

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|----------------------|--------------|-------|--|---------------|-----------|--------|
| ROADWAY ITEMS | | | | | | |
| 0001 | 0000100000-N | 800 | MOBILIZATION | Lump Sum | L.S. | |
| 0002 | 0029000000-N | SP | REINFORCED BRIDGE APPROACH FILL, STATION ***** (26+25.000) | Lump Sum | L.S. | |
| 0003 | 0050000000-E | 226 | SUPPLEMENTARY CLEARING & GRUB- BING | 1 ACR | | |
| 0004 | 0057000000-E | 226 | UNDERCUT EXCAVATION | 250 CY | | |
| 0005 | 0063000000-N | SP | GRADING | Lump Sum | L.S. | |
| 0006 | 0106000000-E | 230 | BORROW EXCAVATION | 3,300 CY | | |
| 0007 | 0195000000-E | 265 | SELECT GRANULAR MATERIAL | 1,900 CY | | |
| 0008 | 0196000000-E | 270 | FABRIC FOR SOIL STABILIZATION | 1,900 SY | | |
| 0009 | 0318000000-E | 300 | FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS | 5 TON | | |
| 0010 | 0366000000-E | 310 | 15" RC PIPE CULVERTS, CLASS III | 12 LF | | |
| 0011 | 0708000000-E | 310 | 15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK | 28 LF | | |
| 0012 | 0806000000-E | 310 | 15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK | 2 EA | | |
| 0013 | 1220000000-E | 545 | INCIDENTAL STONE BASE | 300 TON | | |
| 0014 | 1245000000-E | SP | SHOULDER RECONSTRUCTION | 16.6 SMI | | |
| 0015 | 1489000000-E | 610 | ASPHALT CONC BASE COURSE, TYPE B25.0B | 5,085 TON | | |
| 0016 | 1519000000-E | 610 | ASPHALT CONC SURFACE COURSE, TYPE S9.5B | 348 TON | | |
| 0017 | 1525000000-E | 610 | ASPHALT CONC SURFACE COURSE, TYPE SF9.5A | 10,000 TON | | |
| 0018 | 1560000000-E | 620 | ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22 | 890 TON | | |

County : Northampton

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|---|-----------|-----------|--------|
| 0019 | 2022000000-E | 815 | SUBDRAIN EXCAVATION | 23 CY | | |
| 0020 | 2033000000-E | 815 | SUBDRAIN FINE AGGREGATE | 17 CY | | |
| 0021 | 2044000000-E | 815 | 6" PERFORATED SUBDRAIN PIPE | 100 LF | | |
| 0022 | 2055000000-E | 815 | 6" SUBDRAIN PIPE WYES, TEES, & ELBOWS | 3 EA | | |
| 0023 | 2066000000-N | 815 | CONCRETE PAD FOR SUBDRAIN PIPE OUTLET | 1 EA | | |
| 0024 | 2077000000-E | 815 | 6" OUTLET PIPE (SUBDRAINS) | 6 LF | | |
| 0025 | 2286000000-N | 840 | MASONRY DRAINAGE STRUCTURES | 2 EA | | |
| 0026 | 2367000000-N | 840 | FRAME WITH TWO GRATES, STD 840.29 | 2 EA | | |
| 0027 | 2531000000-E | SP | GENERIC GRADING ITEM (SY) ROCK PLATING | 273 SY | | |
| 0028 | 2556000000-E | 846 | SHOULDER BERM GUTTER | 204 LF | | |
| 0029 | 3030000000-E | 862 | STEEL BM GUARDRAIL | 600 LF | | |
| 0030 | 3150000000-N | 862 | ADDITIONAL GUARDRAIL POSTS | 5 EA | | |
| 0031 | 3270000000-N | SP | GUARDRAIL ANCHOR UNITS, TYPE 350 | 4 EA | | |
| 0032 | 3317000000-N | 862 | GUARDRAIL ANCHOR UNITS, TYPE B-77 | 4 EA | | |
| 0033 | 3360000000-E | 863 | REMOVE EXISTING GUARDRAIL | 343 LF | | |
| 0034 | 3642000000-E | 876 | RIP RAP, CLASS A | 25 TON | | |
| 0035 | 3656000000-E | 876 | FILTER FABRIC FOR DRAINAGE | 150 SY | | |
| 0036 | 3659000000-N | SP | PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON | 2 EA | | |
| 0037 | 4400000000-E | 1110 | WORK ZONE SIGNS (STATIONARY) | 276 SF | | |

County : Northampton

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|---|--------------|-----------|--------|
| 0038 | 4405000000-E | 1110 | WORK ZONE SIGNS (PORTABLE) | 112 SF | | |
| 0039 | 4410000000-E | 1110 | WORK ZONE SIGNS (BARRICADE MOUNTED) | 51 SF | | |
| 0040 | 4420000000-N | 1120 | CHANGEABLE MESSAGE SIGN | 2 EA | | |
| 0041 | 4435000000-N | 1135 | CONES | 75 EA | | |
| 0042 | 4445000000-E | 1145 | BARRICADES (TYPE III) | 96 LF | | |
| 0043 | 4450000000-N | 1150 | FLAGGER | 1,200 HR | | |
| 0044 | 4510000000-N | SP | POLICE | 40 HR | | |
| 0045 | 4685000000-E | 1205 | THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS) | 87,614 LF | | |
| 0046 | 4686000000-E | 1205 | THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS) | 87,614 LF | | |
| 0047 | 4900000000-N | 1251 | PERMANENT RAISED PAVEMENT MARKERS | 548 EA | | |
| 0048 | 5325800000-E | 1510 | 8" WATER LINE | 911 LF | | |
| 0049 | 5709000000-E | 1520 | *** FORCE MAIN SEWER (3") | 750 LF | | |
| 0050 | 5871200000-E | 1550 | TRENCHLESS INSTALLATION OF 3" IN SOIL | 340 LF | | |
| 0051 | 5871210000-E | 1550 | TRENCHLESS INSTALLATION OF 3" NOT IN SOIL | 340 LF | | |
| 0052 | 5871500000-E | 1550 | TRENCHLESS INSTALLATION OF 8" IN SOIL | 375 LF | | |
| 0053 | 5871510000-E | 1550 | TRENCHLESS INSTALLATION OF 8" NOT IN SOIL | 375 LF | | |
| 0054 | 6000000000-E | 1605 | TEMPORARY SILT FENCE | 550 LF | | |
| 0055 | 6006000000-E | 1610 | STONE FOR EROSION CONTROL, CLASS A | 75 TON | | |

County : Northampton

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|---|-------------|-----------|--------|
| 0056 | 6009000000-E | 1610 | STONE FOR EROSION CONTROL, CLASS B | 55 TON | | |
| 0057 | 6012000000-E | 1610 | SEDIMENT CONTROL STONE | 55 TON | | |
| 0058 | 6015000000-E | 1615 | TEMPORARY MULCHING | 1.5 ACR | | |
| 0059 | 6018000000-E | 1620 | SEED FOR TEMPORARY SEEDING | 50 LB | | |
| 0060 | 6021000000-E | 1620 | FERTILIZER FOR TEMPORARY SEED- ING | 0.25 TON | | |
| 0061 | 6024000000-E | 1622 | TEMPORARY SLOPE DRAINS | 150 LF | | |
| 0062 | 6027000000-N | 1622 | INLET PROTECTION AT TEMPORARY SLOPE DRAINS | 3 EA | | |
| 0063 | 6029000000-E | SP | SAFETY FENCE | 225 LF | | |
| 0064 | 6030000000-E | 1630 | SILT EXCAVATION | 60 CY | | |
| 0065 | 6036000000-E | 1631 | MATTING FOR EROSION CONTROL | 200 SY | | |
| 0066 | 6042000000-E | 1632 | 1/4" HARDWARE CLOTH | 200 LF | | |
| 0067 | 6084000000-E | 1660 | SEEDING & MULCHING | 6.5 ACR | | |
| 0068 | 6087000000-E | 1660 | MOWING | 1 ACR | | |
| 0069 | 6090000000-E | 1661 | SEED FOR REPAIR SEEDING | 50 LB | | |
| 0070 | 6093000000-E | 1661 | FERTILIZER FOR REPAIR SEEDING | 0.25 TON | | |
| 0071 | 6096000000-E | 1662 | SEED FOR SUPPLEMENTAL SEEDING | 50 LB | | |
| 0072 | 6108000000-E | 1665 | FERTILIZER TOPDRESSING | 1 TON | | |
| 0073 | 6114000000-N | SP | SPECIALIZED HAND MOWING | 2 HR | | |
| 0074 | 6117000000-N | SP | RESPONSE FOR EROSION CONTROL | 12 EA | | |

County : Northampton

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|------------------------|--------------|-------|--|--------------|-----------|--------|
| STRUCTURE ITEMS | | | | | | |
| 0075 | 8021000000-N | SP | REMOVAL OF EXISTING STRUCTURE AT STATION ***** (26+25.00-L-) | Lump Sum | L.S. | |
| 0076 | 8112730000-N | SP | PDA TESTING | 1 EA | | |
| 0077 | 8112740000-N | SP | PDA ASSISTANCE | 1 EA | | |
| 0078 | 8119000000-E | 412 | UNCLASSIFIED STRUCTURE EXCAVATION | 3,450 CY | | |
| 0079 | 8147000000-E | 420 | REINFORCED CONCRETE DECK SLAB | 8,913 SF | | |
| 0080 | 8161000000-E | 420 | GROOVING BRIDGE FLOORS | 8,359 SF | | |
| 0081 | 8182000000-E | 420 | CLASS A CONCRETE (BRIDGE) | 157.5 CY | | |
| 0082 | 8210000000-N | 422 | BRIDGE APPROACH SLABS, STATION ***** (26+25.00-L-) | Lump Sum | L.S. | |
| 0083 | 8217000000-E | 425 | REINFORCING STEEL (BRIDGE) | 34,755 LB | | |
| 0084 | 8262000000-E | 430 | 45° PRESTRESSED CONCRETE GIRDERS | 884.1 LF | | |
| 0085 | 8364000000-E | 450 | HP12X53 STEEL PILES | 1,730 LF | | |
| 0086 | 8365000000-E | 450 | HP12X53 GALVANIZED STEEL PILES | 2,640 LF | | |
| 0087 | 8393000000-N | 450 | PILE REDRIVES | 20 EA | | |
| 0088 | 8503000000-E | 460 | CONCRETE BARRIER RAIL | 454.35 LF | | |
| 0089 | 8608000000-E | 876 | RIP RAP CLASS II (2'-0" THICK) | 205 TON | | |
| 0090 | 8622000000-E | 876 | FILTER FABRIC FOR DRAINAGE | 229 SY | | |
| 0091 | 8657000000-N | 430 | ELASTOMERIC BEARINGS | Lump Sum | L.S. | |
| 0092 | 8692000000-N | SP | EVAZOTE JOINT SEALS | Lump Sum | L.S. | |

Contract No **C201807**

County (ies): **Northampton**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General