

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (16+50.00)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	100 CY		
0006	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	500 TON		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	200 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	500 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
0010	0199000000-E	SP	TEMPORARY SHORING	825 SF		
0011	0241000000-E	SP	GENERIC GRADING ITEM ROCK PLATING	80 SY		
0012	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	50 TON		
0013	0342000000-E	310	*** SIDE DRAIN PIPE (30")	36 LF		
0014	0343000000-E	310	15" SIDE DRAIN PIPE	68 LF		
0015	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	32 LF		
0016	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	36 LF		
0017	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	220 LF		
0018	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	6 EA		

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1121000000-E	520	AGGREGATE BASE COURSE	276 TON		
0020	1220000000-E	545	INCIDENTAL STONE BASE	25 TON		
0021	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	810 TON		
0022	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	540 TON		
0023	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	370 TON		
0024	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	85 TON		
0025	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	25 TON		
0026	2000000000-N	806	RIGHT OF WAY MARKERS	26 EA		
0027	2022000000-E	815	SUBDRAIN EXCAVATION	224 CY		
0028	2033000000-E	815	SUBDRAIN FINE AGGREGATE	168 CY		
0029	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	1,000 LF		
0030	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	30 EA		
0031	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	2 EA		
0032	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	12 LF		
0033	2253000000-E	840	PIPE COLLARS	1 CY		
0034	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3 EA		
0035	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	3 EA		
0036	2556000000-E	846	SHOULDER BERM GUTTER	507 LF		
0037	3030000000-E	862	STEEL BM GUARDRAIL	787.5 LF		

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0039	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0040	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0041	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	37.5 LF		
0042	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	2 EA		
0043	3649000000-E	876	RIP RAP, CLASS B	25 TON		
0044	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	270 SY		
0045	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1 EA		
0046	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	378 SF		
0047	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96 SF		
0048	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	114 SF		
0049	4430000000-N	1130	DRUMS	75 EA		
0050	4435000000-N	1135	CONES	10 EA		
0051	4445000000-E	1145	BARRICADES (TYPE III)	128 LF		
0052	4450000000-N	1150	FLAGGER	64 HR		
0053	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	26,400 LF		
0054	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	500 LF		
0055	6000000000-E	1605	TEMPORARY SILT FENCE	1,400 LF		
0056	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	120 TON		

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	485 TON		
0058	6012000000-E	1610	SEDIMENT CONTROL STONE	150 TON		
0059	6015000000-E	1615	TEMPORARY MULCHING	3 ACR		
0060	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0061	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.5 TON		
0062	6024000000-E	1622	TEMPORARY SLOPE DRAINS	100 LF		
0063	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	3 EA		
0064	6029000000-E	SP	SAFETY FENCE	400 LF		
0065	6030000000-E	1630	SILT EXCAVATION	1,600 CY		
0066	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,250 SY		
0067	6037000000-E	SP	COIR FIBER MAT	20 SY		
0068	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	1,950 SY		
0069	6042000000-E	1632	1/4" HARDWARE CLOTH	60 LF		
0070	6071030000-E	SP	COIR FIBER BAFFLES	350 LF		
0071	6071050000-E	SP	*** SKIMMER (1-1/2")	3 EA		
0072	6084000000-E	1660	SEEDING & MULCHING	4.8 ACR		
0073	6087000000-E	1660	MOWING	1.5 ACR		
0074	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0075	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0076	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	75 LB		

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0077	6108000000-E	1665	FERTILIZER TOPDRESSING	2.25	TON	
0078	6114000000-N	SP	SPECIALIZED HAND MOWING	2	HR	
0079	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12	EA	
0080	6123000000-E	1670	REFORESTATION	0.25	ACR	
<b>WALL ITEMS</b>						
0081	8802012000-E	SP	PILE PANEL RETAINING WALLS	896	SF	
0082	8847000000-E	SP	GENERIC RETAINING WALL ITEM FABRIC WALL	1,248	SF	
0083	8847000000-E	SP	GENERIC RETAINING WALL ITEM GABION & RENO MATTRESS RETAIN- ING WALL	815	SF	
<b>STRUCTURE ITEMS</b>						
0084	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (16+50.00-L-)	Lump Sum	L.S.	
0085	8097000000-E	SP	PILE EXCAVATION NOT IN SOIL	80	LF	
0086	8119000000-E	412	UNCLASSIFIED STRUCTURE EXCAVA- TION	650	CY	
0087	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	4,208	SF	
0088	8161000000-E	420	GROOVING BRIDGE FLOORS	4,493	SF	
0089	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	124.7	CY	
0090	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (16+50.00-L-)	Lump Sum	L.S.	
0091	8217000000-E	425	REINFORCING STEEL (BRIDGE)	14,653	LB	

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0092	8280000000-E	440	APPROX ..... LBS STRUCTURAL STEEL	103,700 LS		
0093	8364000000-E	450	HP12X53 STEEL PILES	240 LF		
0094	8384200000-E	450	HP14X73 GALVANIZED STEEL PILES	400 LF		
0095	8503000000-E	460	CONCRETE BARRIER RAIL	194.59 LF		
0096	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	215 TON		
0097	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	260 SY		
0098	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0099	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0100	8881000000-E	SP	GENERIC STRUCTURE ITEM CHIPPED TIRE MATERIAL	83 CY		

1146/Apr02/Q176571.84/D435530492000/E100

Total Amount Of Bid For Entire Project :

**Contract No: C201786**

**County: Burke**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General