

County : Chatham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0022000000-E	225	UNCLASSIFIED EXCAVATION	5,900 CY		
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (22 + 85.00)	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	250 CY		
0006	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	400 CY		
0008	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	82 TON		
0009	0343000000-E	310	15" SIDE DRAIN PIPE	128 LF		
0010	0390000000-E	310	36" RC PIPE CULVERTS, CLASS III	140 LF		
0011	0426000000-E	310	72" RC PIPE CULVERTS, CLASS III	100 LF		
0012	0995000000-E	340	PIPE REMOVAL	72 LF		
0013	1121000000-E	520	AGGREGATE BASE COURSE	175 TON		
0014	1220000000-E	545	INCIDENTAL STONE BASE	50 TON		
0015	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	970 TON		
0016	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE 119.0B	740 TON		
0017	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	850 TON		

County : Chatham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	132 TON		
001E	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	12 TON		
002C	2000000000-N	806	RIGHT OF WAY MARKERS	34 EA		
0021	2220000000-E	838	REINFORCED ENDWALLS	7.1 CY		
0022	2253000000-E	840	PIPE COLLARS	0.6 CY		
002E	2264000000-E	840	PIPE PLUGS	1 CY		
0024	2275000000-E	SP	FLOWABLE FILL	39 CY		
002E	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	5 EA		
002E	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	5.8 LF		
0027	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	5 EA		
002E	2556000000-E	846	SHOULDER BERM GUTTER	207 LF		
002E	2577000000-E	846	CONCRETE EXPRESSWAY GUTTER	374 LF		
003C	3030000000-E	862	STEEL BM GUARDRAIL	987.5 LF		
0031	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	68.75 LF		
0032	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
003E	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		
0034	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	5 EA		
003E	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		

County : Chatham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	3574000000-E	867	GENERIC FENCING ITEM 4 STRAND BARBED WIRE FENCE WITH POSTS (& 1 STRAND ELECTRI C)(TEMP)	160 LF		
0037	3574000000-E	867	GENERIC FENCING ITEM TEMP 4 STRAND BARBED WIRE FENCE WITH POSTS (& 1 STRAND ELECTRIC)	70 LF		
003E	3628000000-E	876	RIP RAP, CLASS I	110 TON		
003E	3642000000-E	876	RIP RAP, CLASS A	40 TON		
004C	3649000000-E	876	RIP RAP, CLASS B	200 TON		
0041	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,260 SY		
0042	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	47.25 SF		
0043	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (F)	6 SF		
0044	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	147 LF		
004E	4102000000-N	904	SIGN ERECTION, TYPE E	7 EA		
004E	4108000000-N	904	SIGN ERECTION, TYPE F	1 EA		
0047	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	15 EA		
004E	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	550 SF		
004E	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	100 SF		
005C	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	130 SF		
0051	4430000000-N	1130	DRUMS	100 EA		
0052	4435000000-N	1135	CONES	100 EA		

County : Chatham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0053	4445000000-E	1145	BARRICADES (TYPE III)	120 LF		
0054	4455000000-N	1150	FLAGGER	200 MD		
0055	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	30 EA		
0056	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	4,000 LF		
0057	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	4,000 LF		
005E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	20,000 LF		
0059	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	180 LF		
006C	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	30 EA		
0061	5325200000-E	1510	2" WATER LINE	874 LF		
0062	5536000000-E	1515	2" VALVE	1 EA		
0063	5871100000-E	1550	TRENCHLESS INSTALLATION OF 2" IN SOIL	35 LF		
0064	6000000000-E	1605	TEMPORARY SILT FENCE	1,250 LF		
006E	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	165 TON		
0066	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	565 TON		
0067	6012000000-E	1610	SEDIMENT CONTROL STONE	205 TON		
006E	6015000000-E	1615	TEMPORARY MULCHING	5 ACR		
0069	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	200 LB		
007C	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.75 TON		

County : Chatham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0071	6024000000-E	1622	TEMPORARY SLOPE DRAINS	60 LF		
0072	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	2 EA		
0073	6029000000-E	SP	SAFETY FENCE	730 LF		
0074	6030000000-E	1630	SILT EXCAVATION	2,350 CY		
0075	6036000000-E	1631	MATTING FOR EROSION CONTROL	2,150 SY		
0076	6037000000-E	SP	COIR FIBER MAT	70 SY		
0077	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	150 SY		
0078	6042000000-E	1632	1/4" HARDWARE CLOTH	170 LF		
0079	6071030000-E	SP	COIR FIBER BAFFLES	720 LF		
0080	6071050000-E	SP	*** SKIMMER (1-1/2")	10 EA		
0081	6071050000-E	SP	*** SKIMMER (2")	1 EA		
0082	6084000000-E	1660	SEEDING & MULCHING	5 ACR		
0083	6087000000-E	1660	MOWING	3 ACR		
0084	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0085	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0086	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	125 LB		
0087	6108000000-E	1665	FERTILIZER TOPDRESSING	3.75 TON		
0088	6114000000-N	SP	SPECIALIZED HAND MOWING	3 HR		
0089	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		

County : Chatham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
009C	6123000000-E	1670	REFORESTATION	0.15	ACR	
***** BEGIN SCHEDULE AA ***** ***** (3 ALTERNATES) *****						
0091 AA1	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	232	LF	
0092 AA1	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	164	LF	
*** OR ***						
0093 AA2	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	120	LF	
0094 AA2	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	140	LF	
0095 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (15")	112	LF	
0096 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (24")	24	LF	
*** OR ***						
0097 AA3	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	120	LF	
009E AA3	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	140	LF	
009E AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (15", 0.064")	112	LF	
010C AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (24", 0.064")	24	LF	
***** END SCHEDULE AA *****						

County : Chatham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
STRUCTURE ITEMS						
0101	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (22 + 85.00-L-)	Lump Sum	L.S.	
0102	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (22 + 85.00-L-)	Lump Sum	L.S.	
0103	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	2,935 SF		
0104	8161000000-E	420	GROOVING BRIDGE FLOORS	3,112 SF		
0105	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	31.2 CY		
0106	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (22 + 85.00-L-)	Lump Sum	L.S.	
0107	8217000000-E	425	REINFORCING STEEL (BRIDGE)	4,578 LB		
0108	8280000000-E	440	APPROX LBS STRUCTURAL STEEL	78,100 LS		
0109	8364000000-E	450	HP12X53 STEEL PILES	280 LF		
0110	8503000000-E	460	CONCRETE BARRIER RAIL	176.55 LF		
0111	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	262 TON		
0112	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	290 SY		
0113	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	

1333/Feb28/Q144230.65/D453419530000/E113

Total Amount Of Bid For Entire Project :

Contract No: C201813

County: Chatham

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General