

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (17+82.50)	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	400 CY		
0006	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0007	0106000000-E	230	BORROW EXCAVATION	4,500 CY		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	1,260 CY		
0009	0141000000-E	240	BERM DITCH CONSTRUCTION	50 LF		
0010	0195000000-E	265	SELECT GRANULAR MATERIAL	1,000 CY		
0011	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	1,000 SY		
0012	0199000000-E	SP	TEMPORARY SHORING	350 SF		
0013	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	30 TON		
0014	0343000000-E	310	15" SIDE DRAIN PIPE	56 LF		
0015	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	92 LF		
0016	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	52 LF		
0017	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	4 EA		
0018	0995000000-E	340	PIPE REMOVAL	232 LF		
0019	1220000000-E	545	INCIDENTAL STONE BASE	200 TON		

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0020	1330000000-E	607	INCIDENTAL MILLING	125		SY
0021	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	610		TON
0022	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	400		TON
0023	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	55		TON
0024	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	10		TON
0025	2000000000-N	806	RIGHT OF WAY MARKERS	13		EA
0026	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	5		EA
0027	2352000000-N	840	FRAME WITH GRATE, STD 840.**** (840.16)	2		EA
0028	2365000000-N	840	FRAME WITH TWO GRATES, STD 840.22	1		EA
0029	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2		EA
0030	2619000000-E	850	4" CONCRETE PAVED DITCH	11		SY
0031	3030000000-E	862	STEEL BM GUARDRAIL	437.5		LF
0032	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	12.5		LF
0033	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5		EA
0034	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1		EA
0035	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	3		EA
0036	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4		EA
0037	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	425		LF

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (B-77)	4 EA		
0039	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	4 EA		
0040	3628000000-E	876	RIP RAP, CLASS I	2 TON		
0041	3649000000-E	876	RIP RAP, CLASS B	331 TON		
0042	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,531 SY		
0043	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	14.75 SF		
0044	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	29 LF		
0045	4102000000-N	904	SIGN ERECTION, TYPE E	3 EA		
0046	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	10 EA		
0047	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	198 SF		
0048	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	144 SF		
0049	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	20 SF		
0050	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	2 EA		
0051	4430000000-N	1130	DRUMS	55 EA		
0052	4435000000-N	1135	CONES	52 EA		
0053	4445000000-E	1145	BARRICADES (TYPE III)	48 LF		
0054	4450000000-N	1150	FLAGGER	1,050 HR		
0055	4480000000-N	1165	TMIA	2 EA		
0056	4516000000-N	1180	SKINNY DRUM	104 EA		

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	220 EA		
0058	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	2,070 LF		
0059	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	1,827 LF		
0060	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	10 LF		
0061	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (I)	828 LF		
0062	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (IV)	828 LF		
0063	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	14,391 LF		
0064	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	82 LF		
0065	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	1,200 LF		
0066	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	10 LF		
0067	5325800000-E	1510	8" WATER LINE	812 LF		
0068	5546000000-E	1515	8" VALVE	1 EA		
0069	5648000000-N	1515	RELOCATE WATER METER	1 EA		
0070	5801000000-E	1530	ABANDON 8" UTILITY PIPE	764 LF		
0071	6000000000-E	1605	TEMPORARY SILT FENCE	1,175 LF		
0072	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	290 TON		
0073	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	265 TON		

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	6012000000-E	1610	SEDIMENT CONTROL STONE	430 TON		
0075	6015000000-E	1615	TEMPORARY MULCHING	2.5 ACR		
0076	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0077	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.5 TON		
0078	6029000000-E	SP	SAFETY FENCE	250 LF		
0079	6030000000-E	1630	SILT EXCAVATION	1,360 CY		
0080	6036000000-E	1631	MATTING FOR EROSION CONTROL	705 SY		
0081	6042000000-E	1632	1/4" HARDWARE CLOTH	40 LF		
0082	6070000000-N	SP	SPECIAL STILLING BASINS	8 EA		
0083	6071030000-E	SP	COIR FIBER BAFFLES	330 LF		
0084	6084000000-E	1660	SEEDING & MULCHING	2.5 ACR		
0085	6087000000-E	1660	MOWING	1.5 ACR		
0086	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0087	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0088	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0089	6108000000-E	1665	FERTILIZER TOPDRESSING	1.75 TON		
0090	6114000000-N	SP	SPECIALIZED HAND MOWING	3 HR		
0091	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	18 EA		
0092	7060000000-E	1705	SIGNAL CABLE	1,425 LF		
0093	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	6 EA		

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0094	7264000000-E	1710	MESSENGER CABLE (3/8")	1,190 LF		
0095	7360000000-N	1720	WOOD POLE	6 EA		
0096	7372000000-N	1721	GUY ASSEMBLY	7 EA		
0097	7408000000-E	1722	1" RISER WITH WEATHERHEAD	1 EA		
0098	7420000000-E	1722	2" RISER WITH WEATHERHEAD	4 EA		
0099	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	420 LF		
0100	7456000000-E	1726	LEAD-IN CABLE (***** (14-2)	1,600 LF		
0101	7636000000-N	1745	SIGN FOR SIGNALS	4 EA		
0102	7768000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, POLE MOUNTED)	1 EA		
0103	7780000000-N	1751	DETECTOR CARD (TYPE 2070L)	3 EA		
***** BEGIN SCHEDULE AA ***** ***** (3 ALTERNATES) *****						
0104	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	84 LF		
AA1						
*** OR ***						
0105	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	28 LF		
AA2						
0106	0536000000-E	SP	**** HDPE PIPE CULVERTS (15")	56 LF		
AA2						
*** OR ***						
0107	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	28 LF		
AA3						
0108	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (15", 0.064")	56 LF		
AA3						
***** END SCHEDULE AA *****						

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
STRUCTURE ITEMS						
0109	8007000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP STRUCTURE AT STA ***** (17+82.50-L-)	Lump Sum	L.S.	
0110	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (17+82.50-L-)	Lump Sum	L.S.	
0111	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (17+82.50-L-)	Lump Sum	L.S.	
0112	8105540000-E	SP	3'-6" DIA DRILLED PIERS IN SOIL	44.9 LF		
0113	8105640000-E	SP	3'-6" DIA DRILLED PIERS NOT IN SOIL	19 LF		
0114	8111400000-E	SP	PERMANENT STEEL CASING FOR 3'-6" DIA DRILLED PIER	44.4 LF		
0115	8113000000-N	SP	SID INSPECTION	2 EA		
0116	8115000000-N	SP	CROSSHOLE SONIC LOGGING	2 EA		
0117	8119000000-E	412	UNCLASSIFIED STRUCTURE EXCAVA- TION	1,095 CY		
0118	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	8,050 SF		
0119	8161000000-E	420	GROOVING BRIDGE FLOORS	7,629 SF		
0120	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	91.7 CY		
0121	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (17+82.50-L-)	Lump Sum	L.S.	
0122	8217000000-E	425	REINFORCING STEEL (BRIDGE)	18,656 LB		
0123	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	1,548 LB		
0124	8262000000-E	430	45" PRESTRESSED CONCRETE GIR- DERS	1,015 LF		
0125	8364000000-E	450	HP12X53 STEEL PILES	160 LF		

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0126	8503000000-E	460	CONCRETE BARRIER RAIL	410.17 LF		
0127	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	555 TON		
0128	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	615 SY		
0129	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0130	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
1458/Feb15/Q87945.92/D598304010000/E130			Total Amount Of Bid For Entire Project :			

Contract No: C201713

County: Davidson

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General