

County : Duplin, Sampson

| Line #               | Item Number  | Sec # | Description                                                       | Quantity      | Unit Cost | Amount |
|----------------------|--------------|-------|-------------------------------------------------------------------|---------------|-----------|--------|
| <b>ROADWAY ITEMS</b> |              |       |                                                                   |               |           |        |
| 0001                 | 0000100000-N | 800   | MOBILIZATION                                                      | Lump Sum      | L.S.      |        |
| 0002                 | 0106000000-E | 230   | BORROW EXCAVATION                                                 | 11,334<br>CY  |           |        |
| 0003                 | 1220000000-E | 545   | INCIDENTAL STONE BASE                                             | 2,187<br>TON  |           |        |
| 0004                 | 1245000000-E | SP    | SHOULDER RECONSTRUCTION                                           | 66.46<br>SMI  |           |        |
| 0005                 | 1297000000-E | 607   | MILLING ASPHALT PAVEMENT, ****<br>DEPTH<br>(2-1/2")               | 83,646<br>SY  |           |        |
| 0006                 | 1330000000-E | 607   | INCIDENTAL MILLING                                                | 3,533<br>SY   |           |        |
| 0007                 | 1503000000-E | 610   | ASPHALT CONC INTERMEDIATE<br>COURSE, TYPE 119.0C                  | 13,322<br>TON |           |        |
| 0008                 | 1523000000-E | 610   | ASPHALT CONC SURFACE COURSE,<br>TYPE S9.5C                        | 65,812<br>TON |           |        |
| 0009                 | 1560000000-E | 620   | ASPHALT BINDER FOR PLANT MIX,<br>GRADE PG 64-22                   | 624<br>TON    |           |        |
| 0010                 | 1565000000-E | 620   | ASPHALT BINDER FOR PLANT MIX,<br>GRADE PG 70-22                   | 3,950<br>TON  |           |        |
| 0011                 | 1840000000-E | 665   | MILLED RUMBLE STRIPS (ASPHALT<br>CEMENT CONCRETE)                 | 115,843<br>LF |           |        |
| 0012                 | 1880000000-E | SP    | GENERIC PAVING ITEM<br>PATCHING EXISTING PAVEMENT<br>(FULL DEPTH) | 50<br>TON     |           |        |
| 0013                 | 1880000000-E | SP    | GENERIC PAVING ITEM<br>PATCHING EXISTING PAVEMENT<br>(MILL)       | 100<br>TON    |           |        |
| 0014                 | 2845000000-N | 858   | ADJUSTMENT OF METER BOXES OR<br>VALVE BOXES                       | 2<br>EA       |           |        |
| 0015                 | 4520000000-N | 1266  | TUBULAR MARKERS (FIXED)                                           | 25<br>EA      |           |        |
| 0016                 | 4685000000-E | 1205  | THERMOPLASTIC PAVEMENT MARKING<br>LINES (4", 90 MILS)             | 356,475<br>LF |           |        |
| 0017                 | 4686000000-E | 1205  | THERMOPLASTIC PAVEMENT MARKING<br>LINES (4", 120 MILS)            | 211,130<br>LF |           |        |

County : Duplin, Sampson

| Line # | Item Number  | Sec # | Description                                          | Quantity | Unit Cost | Amount |
|--------|--------------|-------|------------------------------------------------------|----------|-----------|--------|
| 0018   | 4695000000-E | 1205  | THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)   | 2,850    | LF        |        |
| 0019   | 4710000000-E | 1205  | THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS) | 650      | LF        |        |
| 0020   | 4721000000-E | 1205  | THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)  | 20       | EA        |        |
| 0021   | 4725000000-E | 1205  | THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)      | 368      | EA        |        |
| 0022   | 4810000000-E | 1205  | PAINT PAVEMENT MARKING LINES (4")                    | 71,397   | LF        |        |
| 0023   | 4835000000-E | 1205  | PAINT PAVEMENT MARKING LINES (24")                   | 120      | LF        |        |
| 0024   | 4845000000-N | 1205  | PAINT PAVEMENT MARKING SYMBOL                        | 66       | EA        |        |
| 0025   | 4905000000-N | 1253  | SNOWPLOWABLE PAVEMENT MARKERS                        | 2,450    | EA        |        |
| 0026   | 6000000000-E | 1605  | TEMPORARY SILT FENCE                                 | 3,186    | LF        |        |
| 0027   | 6009000000-E | 1610  | STONE FOR EROSION CONTROL, CLASS B                   | 754.25   | TON       |        |
| 0028   | 6012000000-E | 1610  | SEDIMENT CONTROL STONE                               | 802.25   | TON       |        |
| 0029   | 6015000000-E | 1615  | TEMPORARY MULCHING                                   | 30       | ACR       |        |
| 0030   | 6018000000-E | 1620  | SEED FOR TEMPORARY SEEDING                           | 1,566    | LB        |        |
| 0031   | 6021000000-E | 1620  | FERTILIZER FOR TEMPORARY SEEDING                     | 15       | TON       |        |
| 0032   | 6042000000-E | 1632  | 1/4" HARDWARE CLOTH                                  | 1,566.5  | LF        |        |
| 0033   | 6084000000-E | 1660  | SEEDING & MULCHING                                   | 35.42    | ACR       |        |
| 0034   | 7444000000-E | 1725  | INDUCTIVE LOOP SAWCUT                                | 1,726    | LF        |        |

County : Duplin, Sampson

| Line # | Item Number  | Sec # | Description                    | Quantity  | Unit Cost | Amount |
|--------|--------------|-------|--------------------------------|-----------|-----------|--------|
| 0035   | 7456000000-E | 1726  | LEAD-IN CABLE (*****<br>(18-4) | 400<br>LF |           |        |

0819/Mar13/Q956102.88/D135032100000/E35

Total Amount Of Bid For Entire Project :

**Contract No**     **C202058**

**County (ies):**   **Duplin, Sampson**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General