

County : Onslow

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0106000000-E	230	BORROW EXCAVATION	3,498 CY		
0003	1220000000-E	545	INCIDENTAL STONE BASE	459 TON		
0004	1245000000-E	SP	SHOULDER RECONSTRUCTION	12.62 SMI		
0005	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	27,132 SY		
0006	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (2-1/2")	7,696 SY		
0007	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (3")	37,967 SY		
0008	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (3-1/4")	20,990 SY		
0009	1330000000-E	607	INCIDENTAL MILLING	2,350 SY		
0010	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	136 TON		
0011	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	60 TON		
0012	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	18,858 TON		
0013	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	9,111 TON		
0014	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	1,139 TON		
0015	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	547 TON		
0016	1880000000-E	SP	GENERIC PAVING ITEM PATCHING EXISTING PAVEMENT (FULL DEPTH)	325 TON		

County : Onslow

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0017	1880000000-E	SP	GENERIC PAVING ITEM PATCHING EXISTING PAVEMENT (MILL)	1,500 TON		
0018	1880000000-E	SP	GENERIC PAVING ITEM WEDGING EXISTING PAVEMENT	169 TON		
0019	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	27 EA		
0020	2738000000-E	SP	GENERIC PAVING ITEM INCIDENTAL CONCRETE	250 SY		
0021	2752000000-E	SP	GENERIC PAVING ITEM 2' 6" CURB & GUTTER, REMOVE AND REPLACE	250 LF		
0022	2800000000-N	858	ADJUSTMENT OF CATCH BASINS	2 EA		
0023	2830000000-N	858	ADJUSTMENT OF MANHOLES	31 EA		
0024	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	40 EA		
0025	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	67,649 LF		
0026	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	90,854 LF		
0027	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	709 LF		
0028	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	1,100 LF		
0029	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	8 EA		
0030	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	213 EA		
0031	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	90,854 LF		
0032	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	180 LF		
0033	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	1,100 LF		

County : Onslow

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0034	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	8 EA		
0035	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	213 EA		
0036	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	1,504 EA		
0037	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	
0038	6000000000-E	1605	TEMPORARY SILT FENCE	616 LF		
0039	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	155 TON		
0040	6012000000-E	1610	SEDIMENT CONTROL STONE	154.5 TON		
0041	6015000000-E	1615	TEMPORARY MULCHING	6.66 ACR		
0042	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	308 LB		
0043	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	1.17 TON		
0044	6042000000-E	1632	1/4" HARDWARE CLOTH	308 LF		
0045	6084000000-E	1660	SEEDING & MULCHING	6.72 ACR		
0046	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	15,000 LF		
0047	7456000000-E	1726	LEAD-IN CABLE (***** (18-4)	1,500 LF		

1346/Mar12/Q404999.67/D166093100000/E47

Total Amount Of Bid For Entire Project :

**Contract No**     **C202054**

**County (ies):**   **Onslow**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General