

County : Wayne

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (17+23.00)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0006	0134000000-E	240	DRAINAGE DITCH EXCAVATION	21 CY		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	100 CY		
0008	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	100 SY		
0009	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	35 TON		
0010	0343000000-E	310	15" SIDE DRAIN PIPE	80 LF		
0011	0345000000-E	310	24" SIDE DRAIN PIPE	72 LF		
0012	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	24 LF		
0013	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	42 LF		
0014	0714000000-E	310	18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	108 LF		
0015	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	2 EA		
0016	0995000000-E	340	PIPE REMOVAL	163 LF		
0017	1220000000-E	545	INCIDENTAL STONE BASE	150 TON		
0018	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	838 TON		

County : Wayne

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	515 TON		
0020	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	601 TON		
0021	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	97 TON		
0022	2000000000-N	806	RIGHT OF WAY MARKERS	22 EA		
0023	2022000000-E	815	SUBDRAIN EXCAVATION	23 CY		
0024	2033000000-E	815	SUBDRAIN FINE AGGREGATE	17 CY		
0025	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		
0026	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	3 EA		
0027	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0028	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0029	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
0030	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0031	2556000000-E	846	SHOULDER BERM GUTTER	200 LF		
0032	3030000000-E	862	STEEL BM GUARDRAIL	250 LF		
0033	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0034	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0035	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0036	3649000000-E	876	RIP RAP, CLASS B	72 TON		
0037	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	623 SY		

County : Wayne

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	2 EA		
0039	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	8.5 SF		
0040	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	16 LF		
0041	4102000000-N	904	SIGN ERECTION, TYPE E	2 EA		
0042	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	11 EA		
0043	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	359 SF		
0044	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	94 SF		
0045	4445000000-E	1145	BARRICADES (TYPE III)	80 LF		
0046	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	2,400 LF		
0047	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	2,400 LF		
0048	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	20 EA		
0049	6000000000-E	1605	TEMPORARY SILT FENCE	1,540 LF		
0050	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75 TON		
0051	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	535 TON		
0052	6012000000-E	1610	SEDIMENT CONTROL STONE	220 TON		
0053	6015000000-E	1615	TEMPORARY MULCHING	2.5 ACR		
0054	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0055	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.5 TON		

County : Wayne

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	6024000000-E	1622	TEMPORARY SLOPE DRAINS	100 LF		
0057	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	2 EA		
0058	6029000000-E	SP	SAFETY FENCE	300 LF		
0059	6030000000-E	1630	SILT EXCAVATION	1,230 CY		
0060	6036000000-E	1631	MATTING FOR EROSION CONTROL	740 SY		
0061	6037000000-E	SP	COIR FIBER MAT	20 SY		
0062	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	643 SY		
0063	6042000000-E	1632	1/4" HARDWARE CLOTH	40 LF		
0064	6070000000-N	SP	SPECIAL STILLING BASINS	4 EA		
0065	6071030000-E	SP	COIR FIBER BAFFLES	340 LF		
0066	6071050000-E	SP	*** SKIMMER (1-1/2")	3 EA		
0067	6084000000-E	1660	SEEDING & MULCHING	2.5 ACR		
0068	6087000000-E	1660	MOWING	1.5 ACR		
0069	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0070	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0071	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	75 LB		
0072	6108000000-E	1665	FERTILIZER TOPDRESSING	1.75 TON		
0073	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
0074	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		

County : Wayne

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0075	6123000000-E	1670	REFORESTATION	0.1 ACR		
<b>STRUCTURE ITEMS</b>						
0076	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (17+23.00-L-)	Lump Sum	L.S.	
0077	8105540000-E	SP	3'-6" DIA DRILLED PIERS IN SOIL	20 LF		
0078	8105640000-E	SP	3'-6" DIA DRILLED PIERS NOT IN SOIL	10 LF		
0079	8111400000-E	SP	PERMANENT STEEL CASING FOR 3'-6" DIA DRILLED PIER	10 LF		
0080	8113000000-N	SP	SID INSPECTION	2 EA		
0081	8115000000-N	SP	CROSSHOLE SONIC LOGGING	2 EA		
0082	8119000000-E	412	UNCLASSIFIED STRUCTURE EXCAVA- TION	2,970 CY		
0083	8156000000-E	SP	CONCRETE WEARING SURFACE	4,164 SF		
0084	8161000000-E	420	GROOVING BRIDGE FLOORS	5,188 SF		
0085	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	62.3 CY		
0086	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (17+23.00-L-)	Lump Sum	L.S.	
0087	8217000000-E	425	REINFORCING STEEL (BRIDGE)	14,502 LB		
0088	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	1,024 LB		
0089	8364000000-E	450	HP12X53 STEEL PILES	270 LF		
0090	8503000000-E	460	CONCRETE BARRIER RAIL	255.5 LF		

County : Wayne

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0091	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	509 TON		
0092	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	566 SY		
0093	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0094	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0095	8753100000-E	430	3'-0" X 2'-9" PRESTRESSED CONC BOX BEAMS	1,531.5 LF		
0938/Mar11/Q47008.9/D431237860000/E95			Total Amount Of Bid For Entire Project :			

**Contract No: C201621**

**County: Wayne**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General