

County : Wilkes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (12+94.40)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	100 CY		
0006	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	50 TON		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	50 CY		
0008	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	50 SY		
0009	0199000000-E	SP	TEMPORARY SHORING	345 SF		
0010	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	30 TON		
0011	0343000000-E	310	15" SIDE DRAIN PIPE	64 LF		
0012	0345000000-E	310	24" SIDE DRAIN PIPE	52 LF		
0013	0714000000-E	310	18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	16 LF		
0014	0807000000-E	310	18" BIT COAT CS PIPE ELBOWS, T YPE B 0.064" THICK	1 EA		
0015	0995000000-E	340	PIPE REMOVAL	42 LF		
0016	1220000000-E	545	INCIDENTAL STONE BASE	50 TON		
0017	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	220 TON		
0018	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	220 TON		

County : Wilkes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	24 TON		
0020	2000000000-N	806	RIGHT OF WAY MARKERS	15 EA		
0021	2022000000-E	815	SUBDRAIN EXCAVATION	224 CY		
0022	2033000000-E	815	SUBDRAIN FINE AGGREGATE	168 CY		
0023	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	1,000 LF		
0024	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	30 EA		
0025	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	2 EA		
0026	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	12 LF		
0027	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	4 EA		
0028	2354200000-N	840	FRAME WITH GRATE, STD 840.24	2 EA		
0029	2355000000-N	840	FRAME WITH GRATE, STD 840.29	2 EA		
0030	2556000000-E	846	SHOULDER BERM GUTTER	85 LF		
0031	2619000000-E	850	4" CONCRETE PAVED DITCH	11 SY		
0032	3030000000-E	862	STEEL BM GUARDRAIL	50 LF		
0033	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	225 LF		
0034	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0035	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	2 EA		
0036	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0037	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	2 EA		

County : Wilkes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (RETROFIT)	1	EA	
0039	3628000000-E	876	RIP RAP, CLASS I	8	TON	
0040	3649000000-E	876	RIP RAP, CLASS B	7	TON	
0041	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	203	SY	
0042	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	36.5	SF	
0043	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	78	LF	
0044	4102000000-N	904	SIGN ERECTION, TYPE E	10	EA	
0045	4158000000-N	907	DISPOSAL OF SIGN SYSTEM, WOOD	9	EA	
0046	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	80	SF	
0047	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96	SF	
0048	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	36	SF	
0049	4430000000-N	1130	DRUMS	15	EA	
0050	4445000000-E	1145	BARRICADES (TYPE III)	32	LF	
0051	4455000000-N	1150	FLAGGER	540	MD	
0052	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	2	EA	
0053	4470000000-N	1160	RESET TEMPORARY CRASH CUSHIONS	2	EA	
0054	4485000000-E	1170	PORTABLE CONCRETE BARRIER	90	LF	
0055	4490000000-E	1170	PORTABLE CONCRETE BARRIER (ANCHORED)	100	LF	
0056	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	5,018	LF	

County : Wilkes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	856 LF		
0058	6000000000-E	1605	TEMPORARY SILT FENCE	590 LF		
0059	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	110 TON		
0060	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	170 TON		
0061	6012000000-E	1610	SEDIMENT CONTROL STONE	80 TON		
0062	6015000000-E	1615	TEMPORARY MULCHING	1 ACR		
0063	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0064	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.25 TON		
0065	6029000000-E	SP	SAFETY FENCE	250 LF		
0066	6030000000-E	1630	SILT EXCAVATION	480 CY		
0067	6036000000-E	1631	MATTING FOR EROSION CONTROL	430 SY		
0068	6037000000-E	SP	COIR FIBER MAT	10 SY		
0069	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	290 SY		
0070	6042000000-E	1632	1/4" HARDWARE CLOTH	100 LF		
0071	6045000000-E	SP	*** TEMPORARY PIPE (15")	45 LF		
0072	6071030000-E	SP	COIR FIBER BAFFLES	130 LF		
0073	6071050000-E	SP	*** SKIMMER (1-1/2")	1 EA		
0074	6084000000-E	1660	SEEDING & MULCHING	1 ACR		
0075	6087000000-E	1660	MOWING	0.5 ACR		

County : Wilkes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0076	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0077	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0078	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0079	6108000000-E	1665	FERTILIZER TOPDRESSING	0.5 TON		
0080	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
0081	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		

***** BEGIN SCHEDULE AA *****
***** (3 ALTERNATES) *****

0082	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	36 LF		
------	--------------	-----	---------------------------------	----------	--	--

0083	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	96 LF		
------	--------------	-----	---------------------------------	----------	--	--

*** OR ***

0084	0536000000-E	SP	**** HDPE PIPE CULVERTS (15")	36 LF		
------	--------------	----	-------------------------------	----------	--	--

0085	0536000000-E	SP	**** HDPE PIPE CULVERTS (24")	96 LF		
------	--------------	----	-------------------------------	----------	--	--

*** OR ***

0086	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (15", 0.064")	36 LF		
------	--------------	----	--	----------	--	--

0087	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (24", 0.064")	96 LF		
------	--------------	----	--	----------	--	--

***** END SCHEDULE AA *****

STRUCTURE ITEMS

0088	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (12+94.40-L-)	Lump Sum	L.S.	
------	--------------	----	--	----------	------	--

County : Wilkes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0089	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (12+94.40-L-)	Lump Sum	L.S.	
0090	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	3,402 SF		
0091	8161000000-E	420	GROOVING BRIDGE FLOORS	3,592 SF		
0092	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	48.5 CY		
0093	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (12+94.40-L-)	Lump Sum	L.S.	
0094	8217000000-E	425	REINFORCING STEEL (BRIDGE)	6,124 LB		
0095	8280000000-E	440	APPROX LBS STRUCTURAL STEEL	109,500 LS		
0096	8364000000-E	450	HP12X53 STEEL PILES	950 LF		
0097	8475000000-E	460	TWO BAR METAL RAIL	166.92 LF		
0098	8517000000-E	460	1'-***X ***** CONCRETE PARAPET (1'-2"X2'-6")	182.55 LF		
0099	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	435 TON		
0100	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	484 SY		
0101	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
1027/Feb27/Q138518.97/D405111380000/E101			Total Amount Of Bid For Entire Project :			

Contract No: C201817

County: Wilkes

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General