

County : Ashe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (15+72.00)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	300 CY		
0006	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	600 TON		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	150 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	500 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
001C	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	70 TON		
0011	0344000000-E	310	18" SIDE DRAIN PIPE	120 LF		
0012	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	96 LF		
0013	0726000000-E	310	30" BIT COAT CS PIPE CULVERTS, TYPE B 0.079" THICK	8 LF		
0014	0995000000-E	340	PIPE REMOVAL	132 LF		
0015	1121000000-E	520	AGGREGATE BASE COURSE	125 TON		
0016	1220000000-E	545	INCIDENTAL STONE BASE	150 TON		
0017	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	490 TON		
001E	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	180 TON		

County : Ashe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	380 TON		
0020	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	55 TON		
0021	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	40 TON		
0022	2000000000-N	806	RIGHT OF WAY MARKERS	13 EA		
0023	2022000000-E	815	SUBDRAIN EXCAVATION	68 CY		
0024	2033000000-E	815	SUBDRAIN FINE AGGREGATE	51 CY		
0025	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	300 LF		
0026	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	9 EA		
0027	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0028	2132000000-N	816	CONCRETE PAD FOR SHOULDER DRAIN PIPE OUTLET	1 EA		
0029	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	10 EA		
0030	2354200000-N	840	FRAME WITH GRATE, STD 840.24	2 EA		
0031	2355000000-N	840	FRAME WITH GRATE, STD 840.29	8 EA		
0032	2556000000-E	846	SHOULDER BERM GUTTER	16 LF		
0033	2577000000-E	846	CONCRETE EXPRESSWAY GUTTER	350 LF		
0034	3030000000-E	862	STEEL BM GUARDRAIL	125 LF		
0035	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	37.5 LF		
0036	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		

County : Ashe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	2 EA		
003E	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
003E	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	2 EA		
004C	3559000000-E	866	** STRAND BARBED WIRE FENCE WITH POSTS (4")	500 LF		
0041	3578000000-N	SP	GENERIC FENCING ITEM REMOVE & RESET EXISTING METAL GATE	1 EA		
0042	3649000000-E	876	RIP RAP, CLASS B	100 TON		
0043	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	665 SY		
0044	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	417 SF		
004E	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	94 SF		
004E	4430000000-N	1130	DRUMS	10 EA		
0047	4435000000-N	1135	CONES	10 EA		
004E	4445000000-E	1145	BARRICADES (TYPE III)	80 LF		
004E	4847000000-E	1205	POLYUREA PAVEMENT MARKING LINES (4", *****) (STANDARD GLASS BEADS)	5,840 LF		
005C	6000000000-E	1605	TEMPORARY SILT FENCE	1,200 LF		
0051	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	90 TON		
0052	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	300 TON		
0053	6012000000-E	1610	SEDIMENT CONTROL STONE	320 TON		

County : Ashe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	6015000000-E	1615	TEMPORARY MULCHING	1.5	ACR	
0055	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50	LB	
0056	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.25	TON	
0057	6024000000-E	1622	TEMPORARY SLOPE DRAINS	15	LF	
0058	6029000000-E	SP	SAFETY FENCE	440	LF	
0059	6030000000-E	1630	SILT EXCAVATION	660	CY	
0060	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,350	SY	
0061	6037000000-E	SP	COIR FIBER MAT	20	SY	
0062	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	250	SY	
0063	6042000000-E	1632	1/4" HARDWARE CLOTH	200	LF	
0064	6070000000-N	SP	SPECIAL STILLING BASINS	8	EA	
0065	6071030000-E	SP	COIR FIBER BAFFLES	90	LF	
0066	6071050000-E	SP	*** SKIMMER (1-1/2")	2	EA	
0067	6084000000-E	1660	SEEDING & MULCHING	1.5	ACR	
0068	6087000000-E	1660	MOWING	1	ACR	
0069	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	
0070	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
0071	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50	LB	
0072	6108000000-E	1665	FERTILIZER TOPDRESSING	1.25	TON	
0073	6114000000-N	SP	SPECIALIZED HAND MOWING	2	HR	

County : Ashe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12	EA	
0075	6123000000-E	1670	REFORESTATION	0.15	ACR	
***** BEGIN SCHEDULE AA ***** ***** (3 ALTERNATES) *****						
0076 AA1	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	336	LF	
0077 AA1	0396000000-E	310	42" RC PIPE CULVERTS, CLASS III	44	LF	
*** OR ***						
0078 AA2	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	220	LF	
0079 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (18")	116	LF	
0080 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (42")	44	LF	
*** OR ***						
0081 AA3	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	220	LF	
0082 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (18", 0.064")	116	LF	
0083 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (42", 0.079")	44	LF	
***** END SCHEDULE AA *****						
STRUCTURE ITEMS						
0084	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (15+72.00-L)	Lump Sum	L.S.	

County : Ashe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
008E	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (15 + 72.00-L-)	Lump Sum	L.S.	
008E	8105540000-E	SP	3'-6" DIA DRILLED PIERS IN SOIL	26 LF		
0087	8105640000-E	SP	3'-6" DIA DRILLED PIERS NOT IN SOIL	34 LF		
008E	8111400000-E	SP	PERMANENT STEEL CASING FOR 3'-6" DIA DRILLED PIER	25.7 LF		
008E	8113000000-N	SP	SID INSPECTION	2 EA		
009C	8115000000-N	SP	CROSSHOLE SONIC LOGGING	1 EA		
0091	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	99.9 CY		
0092	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (15 + 72.00-L-)	Lump Sum	L.S.	
0093	8217000000-E	425	REINFORCING STEEL (BRIDGE)	20,063 LB		
0094	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	1,747 LB		
009E	8364000000-E	450	HP12X53 STEEL PILES	240 LF		
009E	8468000000-E	460	ONE BAR METAL RAIL	382.13 LF		
0097	8517000000-E	460	1'-***X ***** CONCRETE PARA- PET (1'-0" x 1'-10 1/2")	397.63 LF		
009E	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	234 TON		
009E	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	260 SY		
010C	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	

County : Ashe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0101	8753100000-E	430	3'-0" X 2'-9" PRESTRESSED CONC BOX BEAMS	2,184.19 LF		

1308/Mar28/Q44581.95/D411006060000/E101

Total Amount Of Bid For Entire Project :

Contract No **C201838**

County (ies): **Ashe**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General