

County : Carteret

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (17+44.00)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	20 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	200 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	100 SY		
0010	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	33 TON		
0011	0344000000-E	310	18" SIDE DRAIN PIPE	100 LF		
0012	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	204 LF		
0013	0995000000-E	340	PIPE REMOVAL	59.1 LF		
0014	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0015	1330000000-E	607	INCIDENTAL MILLING	255 SY		
0016	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	675 TON		
0017	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	492 TON		
0018	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	59 TON		
0019	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3 EA		

County : Carteret

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0020	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0021	2396000000-N	840	FRAME WITH COVER, STD 840.54	1 EA		
0022	2556000000-E	846	SHOULDER BERM GUTTER	190 LF		
0023	3030000000-E	862	STEEL BM GUARDRAIL	600 LF		
0024	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0025	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0026	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0027	3649000000-E	876	RIP RAP, CLASS B	10 TON		
0028	3856000000-E	876	FILTER FABRIC FOR DRAINAGE	213 SY		
0029	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	16.25 SF		
0030	4082000000-E	903	SUPPORTS, WOOD	40 LF		
0031	4102000000-N	904	SIGN ERECTION, TYPE E	3 EA		
0032	4158000000-N	907	DISPOSAL OF SIGN SYSTEM, WOOD	9 EA		
0033	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	316 SF		
0034	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	210 SF		
0035	4430000000-N	1130	DRUMS	16 EA		
0036	4445000000-E	1145	BARRICADES (TYPE III)	168 LF		
0037	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	1,940 LF		
0038	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	1,940 LF		

County : Carteret

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0039	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	13 EA		
0040	6000000000-E	1605	TEMPORARY SILT FENCE	625 LF		
0041	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	50 TON		
0042	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	85 TON		
0043	6012000000-E	1610	SEDIMENT CONTROL STONE	45 TON		
0044	6015000000-E	1615	TEMPORARY MULCHING	1 ACR		
0045	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0046	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.25 TON		
0047	6024000000-E	1622	TEMPORARY SLOPE DRAINS	190 LF		
0048	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	6 EA		
0049	6029000000-E	SP	SAFETY FENCE	250 LF		
0050	6030000000-E	1630	SILT EXCAVATION	225 CY		
0051	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,300 SY		
0052	6037000000-E	SP	COIR FIBER MAT	20 SY		
0053	6042000000-E	1632	1/4" HARDWARE CLOTH	100 LF		
0054	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	150 SY		
0055	6071030000-E	SP	COIR FIBER BAFFLES	100 LF		
0056	6071050000-E	SP	*** SKIMMER (1-1/2")	3 EA		
0057	6084000000-E	1660	SEEDING & MULCHING	1.5 ACR		

County : Carteret

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0058	6087000000-E	1660	MOWING	1	ACR	
0059	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	
0060	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
0061	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50	LB	
0062	6108000000-E	1665	FERTILIZER TOPDRESSING	1	TON	
0063	6114000000-N	SP	SPECIALIZED HAND MOWING	2	HR	
0064	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12	EA	
<b>STRUCTURE ITEMS</b>						
0065	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (17+44.00-L-)	Lump Sum	L.S.	
0066	8112730000-N	SP	PDA TESTING	1	EA	
0067	8112740000-N	SP	PDA ASSISTANCE	1	EA	
0068	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (17+44.00-L-)	Lump Sum	L.S.	
0069	8175000000-E	420	CLASS AA CONCRETE (BRIDGE)	59.1	CY	
0070	8224000000-E	425	EPOXY COATED REINFORCING STEEL (BRIDGE)	9,672	LB	
0071	8336000000-E	450	20" PRESTRESSED CONC PILES	360	LF	
0072	8365000000-E	450	HP12X53 GALVANIZED STEEL PILES	1,440	LF	
0073	8393000000-N	450	PILE REDRIVES	15	EA	
0074	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	230	TON	
0075	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	250	SY	

County : Carteret

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0076	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0077	8860000000-N	SP	GENERIC STRUCTURE ITEM POST-TENSIONING AND GROUTING	Lump Sum	L.S.	
0078	8860000000-N	SP	GENERIC STRUCTURE ITEM PRECAST CONCRETE APPROACH SLAB	Lump Sum	L.S.	
0079	8867000000-E	SP	GENERIC STRUCTURE ITEM (3'-0" X 1'-10") PRESTRESSED CONCRETE CORED SLAB	1,404.38 LF		
0080	8867000000-E	SP	GENERIC STRUCTURE ITEM PRECAST CONCRETE BARRIER RAIL	186.75 LF		
0081	8892000000-E	SP	GENERIC STRUCTURE ITEM BRIDGE DECK GRINDING	5,906 SF		
0701/Apr08/Q31053.58/D383224050000/E81			Total Amount Of Bid For Entire Project :			

1-18-08

Z-13

**Contract No**     **C202081**

**County (ies):**   **Carteret**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General