

County : Catawba

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	100 CY		
0006	0134000000-E	240	DRAINAGE DITCH EXCAVATION	700 CY		
0007	0141000000-E	240	BERM DITCH CONSTRUCTION	600 LF		
0008	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	80 TON		
0009	0343000000-E	310	15" SIDE DRAIN PIPE	284 LF		
0010	0344000000-E	310	18" SIDE DRAIN PIPE	212 LF		
0011	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	76 LF		
0012	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	176 LF		
0013	0995000000-E	340	PIPE REMOVAL	20 LF		
0014	1220000000-E	545	INCIDENTAL STONE BASE	300 TON		
0015	1330000000-E	607	INCIDENTAL MILLING	100 SY		
0016	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	5,830 TON		
0017	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	4,810 TON		
0018	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	2,690 TON		

County : Catawba

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	480 TON		
0020	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	165 TON		
0021	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	20 TON		
0022	1704000000-E	SP	PATCHING EXISTING PAVEMENT	100 TON		
0023	2154000000-N	820	METAL FUNNELS	4 EA		
0024	2165000000-E	820	12" FUNNEL DRAIN PIPE	200 LF		
0025	2176000000-E	820	12" FUNNEL DRAIN PIPE ELBOWS	4 EA		
0026	2253000000-E	840	PIPE COLLARS	3 CY		
0027	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	4 EA		
0028	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	2 EA		
0029	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	1 EA		
0030	2556000000-E	846	SHOULDER BERM GUTTER	640 LF		
0031	2612000000-E	848	6" CONCRETE DRIVEWAY	115 SY		
0032	3030000000-E	862	STEEL BM GUARDRAIL	600 LF		
0033	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0034	3180000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** (BP-III)	4 EA		
0035	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0036	3503000000-E	866	WOVEN WIRE FENCE, 47" FABRIC	2,000 LF		

County : Catawba

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	3509000000-E	866	4" TIMBER FENCE POSTS, 7'-6" LONG	100	EA	
0038	3515000000-E	866	5" TIMBER FENCE POSTS, 8'-0" LONG	90	EA	
0039	3557000000-E	866	ADDITIONAL BARBED WIRE	2,100	LF	
0040	3563000000-E	SP	TEMP *** WOVEN WIRE FENCE, COMPLETE W/POSTS (47")	2,100	LF	
0041	3649000000-E	876	RIP RAP, CLASS B	1,530	TON	
0042	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	2,405	SY	
0043	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	675	SF	
0044	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96	SF	
0045	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	94	SF	
0046	4430000000-N	1130	DRUMS	150	EA	
0047	4445000000-E	1145	BARRICADES (TYPE III)	48	LF	
0048	4455000000-N	1150	FLAGGER	30	MD	
0049	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	30	EA	
0050	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	16,200	LF	
0051	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	19,101	LF	
0052	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	235	LF	
0053	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	189	LF	

County : Catawba

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	31	EA	
005E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	21,480	LF	
005E	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	322	EA	
0057	6000000000-E	1605	TEMPORARY SILT FENCE	4,440	LF	
005E	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	385	TON	
005E	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	1,250	TON	
006C	6012000000-E	1610	SEDIMENT CONTROL STONE	430	TON	
0061	6015000000-E	1615	TEMPORARY MULCHING	9.5	ACR	
0062	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	350	LB	
0063	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	2.5	TON	
0064	6024000000-E	1622	TEMPORARY SLOPE DRAINS	260	LF	
006E	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	4	EA	
006E	6029000000-E	SP	SAFETY FENCE	340	LF	
0067	6030000000-E	1630	SILT EXCAVATION	3,200	CY	
006E	6036000000-E	1631	MATTING FOR EROSION CONTROL	10,790	SY	
006E	6037000000-E	SP	COIR FIBER MAT	25	SY	
007C	6042000000-E	1632	1/4" HARDWARE CLOTH	100	LF	
0071	6071030000-E	SP	COIR FIBER BAFFLES	470	LF	

County : Catawba

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	6071050000-E	SP	*** SKIMMER (1-1/2")	2	EA	
0073	6071050000-E	SP	*** SKIMMER (2")	2	EA	
0074	6084000000-E	1660	SEEDING & MULCHING	10	ACR	
0075	6087000000-E	1660	MOWING	6	ACR	
0076	6090000000-E	1661	SEED FOR REPAIR SEEDING	100	LB	
0077	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
0078	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	250	LB	
0079	6108000000-E	1665	FERTILIZER TOPDRESSING	7	TON	
0080	6114000000-N	SP	SPECIALIZED HAND MOWING	2	HR	
0081	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	27	EA	

1545/Apr08/Q109801.25/D290993630000/E81

Total Amount Of Bid For Entire Project :

**Contract No**     **C202016**

**County (ies):**   **Catawba**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General