

County : Cherokee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (14+66.00)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	100 CY		
0006	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	500 TON		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	7 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	500 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
0010	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	10 TON		
0011	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	30 LF		
0012	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	2 EA		
0013	1121000000-E	520	AGGREGATE BASE COURSE	76 TON		
0014	1220000000-E	545	INCIDENTAL STONE BASE	300 TON		
0015	1275000000-E	600	PRIME COAT	50 GAL		
0016	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	192 TON		
0017	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	125 TON		
0018	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	20 TON		

County : Cherokee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2022000000-E	815	SUBDRAIN EXCAVATION	224 CY		
0020	2033000000-E	815	SUBDRAIN FINE AGGREGATE	168 CY		
0021	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	1,000 LF		
0022	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	30 EA		
0023	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	2 EA		
0024	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	12 LF		
0025	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	1 EA		
0026	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1 EA		
0027	2556000000-E	846	SHOULDER BERM GUTTER	28 LF		
0028	3030000000-E	862	STEEL BM GUARDRAIL	100 LF		
0029	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	112.5 LF		
0030	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0031	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	1 EA		
0032	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	3 EA		
0033	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0034	3578000000-N	SP	GENERIC FENCING ITEM RESET EXISTING GATE	1 EA		
0035	3649000000-E	876	RIP RAP, CLASS B	20 TON		
0036	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	230 SY		
0037	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	104 SF		

County : Cherokee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	192	SF	
0039	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	20	SF	
0040	4430000000-N	1130	DRUMS	44	EA	
0041	4435000000-N	1135	CONES	25	EA	
0042	4445000000-E	1145	BARRICADES (TYPE III)	48	LF	
0043	4455000000-N	1150	FLAGGER	40	MD	
0044	4480000000-N	1165	TMIA	1	EA	
0045	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	7,419	LF	
0046	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	300	LF	
0047	6000000000-E	1605	TEMPORARY SILT FENCE	650	LF	
0048	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	90	TON	
0049	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	170	TON	
0050	6012000000-E	1610	SEDIMENT CONTROL STONE	50	TON	
0051	6015000000-E	1615	TEMPORARY MULCHING	1.5	ACR	
0052	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50	LB	
0053	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.25	TON	
0054	6029000000-E	SP	SAFETY FENCE	325	LF	
0055	6030000000-E	1630	SILT EXCAVATION	420	CY	
0056	6036000000-E	1631	MATTING FOR EROSION CONTROL	750	SY	

County : Cherokee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	6037000000-E	SP	COIR FIBER MAT	25 SY		
0058	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	105 SY		
0059	6042000000-E	1632	1/4" HARDWARE CLOTH	20 LF		
0060	6071030000-E	SP	COIR FIBER BAFFLES	100 LF		
0061	6071050000-E	SP	*** SKIMMER (1-1/2")	4 EA		
0062	6084000000-E	1660	SEEDING & MULCHING	1.5 ACR		
0063	6087000000-E	1660	MOWING	1 ACR		
0064	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0065	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0066	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0067	6108000000-E	1665	FERTILIZER TOPDRESSING	1.25 TON		
0068	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
0069	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
0070	6144000000-E	SP	GENERIC EROSION CONTROL ITEM POLYACRYLAMIDE (PAM)	27 LB		
0071	6147000000-E	SP	GENERIC EROSION CONTROL ITEM WATTLE	75 LF		

**STRUCTURE ITEMS**

0072	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (14+66.00-L-)	Lump Sum	L.S.	
0073	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (14+66.00-L-)	Lump Sum	L.S.	

County : Cherokee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	3,216 SF		
0075	8161000000-E	420	GROOVING BRIDGE FLOORS	2,940 SF		
0076	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	34 CY		
0077	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (14+66.00-L-)	Lump Sum	L.S.	
0078	8217000000-E	425	REINFORCING STEEL (BRIDGE)	6,376 LB		
0079	8280000000-E	440	APPROX ..... LBS STRUCTURAL STEEL	115,600 LS		
0080	8384000000-E	450	HP14X73 STEEL PILES	175 LF		
0081	8391000000-N	450	STEEL PILE POINTS	14 EA		
0082	8503000000-E	460	CONCRETE BARRIER RAIL	232.67 LF		
0083	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	174 TON		
0084	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	194 SY		
0085	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	

1016/Apr02/Q144491.92/D373391180000/E85

Total Amount Of Bid For Entire Project :

**Contract No**     **C201835**

**County (ies):**   **Cherokee**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General