

PROJECT: B-4172  
COUNTY: Lenoir

PROJECT SPECIAL PROVISIONS  
Utilities

UTILITY CONFLICTS:

General:

The following utility companies have facilities located within the construction limits of this project:

- A. City of Kinston (power)
- B. Progress Energy
- C. Embarq
- D. Suddenlink Communications

The conflicting facilities of these concerns will be adjusted prior to the date of availability, unless otherwise noted and are therefore listed in these special provisions for the benefit of the Contractor. All utility work listed herein will be done by the utility owners. All utilities are shown on the plans from the best available information.

The Contractor's attention is directed to Article 105.8 of the Standard Specifications.

Utilities Requiring Adjustment:

A. City of Kinston

- 1. Conflicts will be adjusted in the field as necessary. The City requires two weeks notice to begin work and two weeks to complete the work.

B. Progress Energy

- 1. Conflicts will be adjusted in the field as necessary. Progress Energy requires two weeks notice to begin work and two weeks to complete the work.

C. Embarq

- 1. Conflicts will be adjusted in the field as necessary. Embarq requires two weeks notice to begin work and two weeks to complete the work.
- 2. Notify Embarq two weeks prior to installing the guardrail. An Embarq representative will be on-site for guardrail installation to locate the telephone cable and move the cable if required.

PROJECT: B-4172  
COUNTY: Lenoir

D. Suddenlink Communications

1. Conflicts will be adjusted in the field as necessary. Suddenlink Communications requires two weeks notice to begin work and two weeks to complete the work.