

County : Stanly

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0003	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUBBING	2 ACR		
0004	0022000000-E	225	UNCLASSIFIED EXCAVATION	272,500 CY		
0005	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (77+74.92)	Lump Sum	L.S.	
0006	0036000000-E	225	UNDERCUT EXCAVATION	2,250 CY		
0007	0080000000-E	SP	CLASS IV SUBGRADE STABILIZATION	500 TON		
0008	0106000000-E	230	BORROW EXCAVATION	57,500 CY		
0009	0134000000-E	240	DRAINAGE DITCH EXCAVATION	4,350 CY		
0010	0141000000-E	240	BERM DITCH CONSTRUCTION	1,880 LF		
0011	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	10,600 SY		
0012	0177000000-E	250	BREAKING OF EXISTING ASPHALT PAVEMENT	4,275 SY		
0013	0192000000-N	260	PROOF ROLLING	20 HR		
0014	0195000000-E	265	SELECT GRANULAR MATERIAL	500 CY		
0015	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	1,500 SY		
0016	0255000000-E	SP	GENERIC GRADING ITEM EXCAVATION, HAULING & DISPOSAL OF CONTAMINATED SOIL	10 TON		
0017	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	1,420 TON		
0018	0343000000-E	310	15" SIDE DRAIN PIPE	328 LF		

County : Stanly

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	1,004 LF		
0020	0390000000-E	310	36" RC PIPE CULVERTS, CLASS III	112 LF		
0021	0396000000-E	310	42" RC PIPE CULVERTS, CLASS III	366 LF		
0022	0448000000-E	310	***** RC PIPE CULVERTS, CLASS IV (60")	312 LF		
0023	0570000000-E	310	6" CS PIPE CULVERTS, 0.064" THICK (SPRING BOX)	8 LF		
0024	0706000000-E	310	12" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	24 LF		
0025	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	540 LF		
0026	0714000000-E	310	18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	12 LF		
0027	0720000000-E	310	24" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	48 LF		
0028	0805000000-E	310	12" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	2 EA		
0029	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	24 EA		
0030	0808000000-E	310	24" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	2 EA		
0031	0995000000-E	340	PIPE REMOVAL	1,167 LF		
0032	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
0033	1044000000-E	501	LIME TREATED SOIL (SLURRY METHOD)	25,770 SY		
0034	1066000000-E	501	LIME FOR LIME TREATED SOIL	260 TON		
0035	1077000000-E	SP	#57 STONE	26 TON		

County : Stanly

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	1110000000-E	510	STABILIZER AGGREGATE	850 TON		
0037	1121000000-E	520	AGGREGATE BASE COURSE	42,000 TON		
0038	1176000000-E	542	SOIL CEMENT BASE	38,660 SY		
0039	1187000000-E	542	PORTLAND CEMENT FOR SOIL CE- MENT BASE	1,064 TON		
0040	1198000000-E	SP	AGGREGATE FOR SOIL CEMENT BASE	250 TON		
0041	1209000000-E	543	ASPHALT CURING SEAL	9,670 GAL		
0042	1220000000-E	545	INCIDENTAL STONE BASE	5,000 TON		
0043	1275000000-E	600	PRIME COAT	5,720 GAL		
0044	1330000000-E	607	INCIDENTAL MILLING	1,475 SY		
0045	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	700 TON		
0046	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	9,500 TON		
0047	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	1,300 TON		
0048	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	20,000 TON		
0049	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	4,300 TON		
0050	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	15,900 TON		
0051	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	1,710 TON		
0052	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	960 TON		
0053	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	123.6 TON		

County : Stanly

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	2022000000-E	815	SUBDRAIN EXCAVATION	20 CY		
0055	2033000000-E	815	SUBDRAIN FINE AGGREGATE	10 CY		
0056	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	50 LF		
0057	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	2 EA		
0058	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0059	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0060	2099000000-E	816	SHOULDER DRAIN	4,800 LF		
0061	2110000000-E	816	4" SHOULDER DRAIN PIPE	4,800 LF		
0062	2121000000-E	816	4" OUTLET PIPE FOR SHOULDER DRAINS	120 LF		
0063	2132000000-N	816	CONCRETE PAD FOR SHOULDER DRAIN PIPE OUTLET	4 EA		
0064	2143000000-E	818	BLOTTING SAND	15 TON		
0065	2209000000-E	838	ENDWALLS	21.4 CY		
0066	2220000000-E	838	REINFORCED ENDWALLS	5.9 CY		
0067	2253000000-E	840	PIPE COLLARS	0.45 CY		
0068	2264000000-E	840	PIPE PLUGS	0.364 CY		
0069	2275000000-E	SP	FLOWABLE FILL	10 CY		
0070	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	85 EA		
0071	2297000000-E	840	MASONRY DRAINAGE STRUCTURES	3 CY		
0072	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	0.9 LF		
0073	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	16 EA		

County : Stanly

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	2365000000-N	840	FRAME WITH TWO GRATES, STD 840.22	16 EA		
0075	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	11 EA		
0076	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	3 EA		
0077	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	21 EA		
0078	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	17 EA		
0079	2484000000-E	SP	GENERIC DRAINAGE ITEM POLYMER DRAIN LINE	7 LF		
0080	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	7,770 LF		
0081	2556000000-E	846	SHOULDER BERM GUTTER	2,570 LF		
0082	2570000000-N	SP	MODIFIED CONCRETE FLUME	1 EA		
0083	2591000000-E	848	4" CONCRETE SIDEWALK	13,870 SY		
0084	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	24 EA		
0085	2612000000-E	848	6" CONCRETE DRIVEWAY	1,140 SY		
0086	2619000000-E	850	4" CONCRETE PAVED DITCH	35 SY		
0087	2830000000-N	858	ADJUSTMENT OF MANHOLES	17 EA		
0088	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	33 EA		
0089	3030000000-E	862	STEEL BM GUARDRAIL	8,050 LF		
0090	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	150 LF		
0091	3105000000-N	862	STEEL BM GUARDRAIL TERMINAL SECTIONS	8 EA		

County : Stanly

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0092	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
0093	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	2 EA		
0094	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	28 EA		
0095	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0096	3503000000-E	866	WOVEN WIRE FENCE, 47" FABRIC	22,300 LF		
0097	3509000000-E	866	4" TIMBER FENCE POSTS, 7'-6" LONG	1,375 EA		
0098	3515000000-E	866	5" TIMBER FENCE POSTS, 8'-0" LONG	430 EA		
0099	3557000000-E	866	ADDITIONAL BARBED WIRE	500 LF		
0100	3628000000-E	876	RIP RAP, CLASS I	240 TON		
0101	3642000000-E	876	RIP RAP, CLASS A	20 TON		
0102	3649000000-E	876	RIP RAP, CLASS B	1,850 TON		
0103	3651000000-E	SP	BOULDERS	35 TON		
0104	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	9,825 SY		
0105	4048000000-E	902	REINFORCED CONCRETE SIGN FOUNDATIONS	1 CY		
0106	4054000000-E	902	PLAIN CONCRETE SIGN FOUNDATIONS	2 CY		
0107	4060000000-E	903	SUPPORTS, BREAKAWAY STEEL BEAM	1,021 LB		
0108	4066000000-E	903	SUPPORTS, SIMPLE STEEL BEAM	643 LB		
0109	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	2,523 LF		
0110	4096000000-N	904	SIGN ERECTION, TYPE D	7 EA		

County : Stanly

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0111	4102000000-N	904	SIGN ERECTION, TYPE E	77 EA		
0112	4108000000-N	904	SIGN ERECTION, TYPE F	51 EA		
0113	4110000000-N	904	SIGN ERECTION, TYPE *** (GROUND MOUNTED) (A)	3 EA		
0114	4110000000-N	904	SIGN ERECTION, TYPE *** (GROUND MOUNTED) (B)	2 EA		
0115	4152000000-N	907	DISPOSAL OF SIGN SYSTEM, STEEL BEAM	3 EA		
0116	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	55 EA		
0117	4158000000-N	907	DISPOSAL OF SIGN SYSTEM, WOOD	2 EA		
0118	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	1,206 SF		
0119	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	543 SF		
0120	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	282 SF		
0121	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	2 EA		
0122	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	3 EA		
0123	4430000000-N	1130	DRUMS	240 EA		
0124	4435000000-N	1135	CONES	100 EA		
0125	4445000000-E	1145	BARRICADES (TYPE III)	608 LF		
0126	4450000000-N	1150	FLAGGER	6,120 HR		
0127	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	2 EA		
0128	4470000000-N	1160	RESET TEMPORARY CRASH CUSHIONS	1 EA		
0129	4480000000-N	1165	TMIA	2 EA		

County : Stanly

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0130	4485000000-E	1170	PORTABLE CONCRETE BARRIER	1,330	LF	
0131	4495000000-E	1170	PORTABLE CONCRETE BARRIER (DRAINAGE)	450	LF	
0132	4500000000-E	1170	RESET PORTABLE CONCRETE BAR- RIER	100	LF	
0133	4506000000-E	1170	RESET PORTABLE CONCRETE BAR- RIER (DRAINAGE)	50	LF	
0134	4510000000-N	SP	POLICE	50	HR	
0135	4516000000-N	1180	SKINNY DRUM	150	EA	
0136	4520000000-N	1266	TUBULAR MARKERS (FIXED)	31	EA	
0137	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	1,001	EA	
0138	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (4)	632	LF	
0139	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	272,474	LF	
0140	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	2,554	LF	
0141	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	1,810	LF	
0142	4840000000-N	1205	PAINT PAVEMENT MARKING CHARAC- TER	16	EA	
0143	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	242	EA	
0144	4847000000-E	1205	POLYUREA PAVEMENT MARKING LINES (4", *****) (STANDARD GLASS BEADS)	99,805	LF	
0145	4847110000-E	1205	POLYUREA PAVEMENT MARKING LINES (8", *****) (STANDARD GLASS BEADS)	1,277	LF	
0146	4847140000-E	1205	POLYUREA PAVEMENT MARKING LINES (24", *****) (STANDARD GLASS BEADS)	738	LF	



County : Stanly

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0147	4847200000-N	1205	POLYUREA PAVEMENT MARKING CHARACTER (*****) (STANDARD GLASS BEADS)	8 EA		
0148	4847220000-N	1205	POLYUREA PAVEMENT MARKING SYMBOL (*****) (STANDARD GLASS BEADS)	120 EA		
0149	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	17,729 LF		
0150	4860000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (8")	100 LF		
0151	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	57 LF		
0152	4875000000-N	1205	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS	20 EA		
0153	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	793 EA		
0154	4915000000-E	1264	7' U-CHANNEL POSTS	12 EA		
0155	4955000000-N	1264	OBJECT MARKERS (END OF ROAD)	12 EA		
0156	5325600000-E	1510	6" WATER LINE	646.3 LF		
0157	5326200000-E	1510	12" WATER LINE	371.9 LF		
0158	5326600000-E	1510	16" WATER LINE	3,264 LF		
0159	5540000000-E	1515	6" VALVE	5 EA		
0160	5558000000-E	1515	12" VALVE	2 EA		
0161	5558600000-E	1515	16" VALVE	6 EA		
0162	5589200000-E	1515	2" AIR RELEASE VALVE	1 EA		
0163	5648000000-N	1515	RELOCATE WATER METER	19 EA		
0164	5672000000-N	1515	RELOCATE FIRE HYDRANT	4 EA		

County : Stanly

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0165	5691300000-E	1520	8" SANITARY GRAVITY SEWER	3,262.8 LF		
0166	5775000000-E	1525	4' DIA UTILITY MANHOLE	17 EA		
0167	5781000000-E	1525	UTILITY MANHOLE WALL, 4' DIA	76.6 LF		
0168	5800000000-E	1530	ABANDON 6" UTILITY PIPE	417 LF		
0169	5801000000-E	1530	ABANDON 8" UTILITY PIPE	657 LF		
0170	5804000000-E	1530	ABANDON 12" UTILITY PIPE	1,002.9 LF		
0171	5810000000-E	1530	ABANDON 16" UTILITY PIPE	2,519 LF		
0172	5816000000-N	1530	ABANDON UTILITY MANHOLE	13 EA		
0173	5882000000-N	SP	GENERIC UTILITY ITEM WATER METER VAULT	1 EA		
0174	6000000000-E	1605	TEMPORARY SILT FENCE	10,350 LF		
0175	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	2,500 TON		
0176	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	4,255 TON		
0177	6012000000-E	1610	SEDIMENT CONTROL STONE	2,385 TON		
0178	6015000000-E	1615	TEMPORARY MULCHING	77.5 ACR		
0179	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	3,550 LB		
0180	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	16 TON		
0181	6024000000-E	1622	TEMPORARY SLOPE DRAINS	1,700 LF		
0182	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	23 EA		
0183	6029000000-E	SP	SAFETY FENCE	1,300 LF		
0184	6030000000-E	1630	SILT EXCAVATION	30,450 CY		

County : Stanly

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0185	6036000000-E	1631	MATTING FOR EROSION CONTROL	17,100 SY		
0186	6037000000-E	SP	COIR FIBER MAT	970 SY		
0187	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	5,000 SY		
0188	6042000000-E	1632	1/4" HARDWARE CLOTH	2,350 LF		
0189	6069000000-E	1638	STILLING BASINS	170 CY		
0190	6071010000-E	SP	WATTLE	40 LF		
0191	6071020000-E	SP	POLYACRYLAMIDE (PAM)	23 LB		
0192	6071030000-E	SP	COIR FIBER BAFFLES	3,100 LF		
0193	6071050000-E	SP	*** SKIMMER (1-1/2")	18 EA		
0194	6071050000-E	SP	*** SKIMMER (2")	16 EA		
0195	6071050000-E	SP	*** SKIMMER (2-1/2")	2 EA		
0196	6071050000-E	SP	*** SKIMMER (3")	1 EA		
0197	6071050000-E	SP	*** SKIMMER (4")	1 EA		
0198	6084000000-E	1660	SEEDING & MULCHING	97.5 ACR		
0199	6087000000-E	1660	MOWING	48.5 ACR		
0200	6090000000-E	1661	SEED FOR REPAIR SEEDING	700 LB		
0201	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	1.75 TON		
0202	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	2,000 LB		
0203	6108000000-E	1665	FERTILIZER TOPDRESSING	58 TON		

County : Stanly

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0204	6111000000-E	SP	IMPERVIOUS DIKE	280 LF		
0205	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
0206	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	54 EA		
0207	6120000000-E	SP	CULVERT DIVERSION CHANNEL	260 CY		
0208	6123000000-E	1670	REFORESTATION	4 ACR		
0209	6126000000-E	SP	STREAMBANK REFORESTATION	0.29 ACR		
0210	7060000000-E	1705	SIGNAL CABLE	1,390 LF		
0211	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	16 EA		
0212	7132000000-E	1705	VEHICLE SIGNAL HEAD (12", 4 SECTION)	1 EA		
0213	7144000000-E	1705	VEHICLE SIGNAL HEAD (12", 5 SECTION)	1 EA		
0214	7264000000-E	1710	MESSENGER CABLE (3/8")	820 LF		
0215	7288000000-E	1715	PAVED TRENCHING (*****) (1, 2")	50 LF		
0216	7300000000-E	1715	UNPAVED TRENCHING (*****) (1, 2")	1,930 LF		
0217	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	11 EA		
0218	7360000000-N	1720	WOOD POLE	8 EA		
0219	7372000000-N	1721	GUY ASSEMBLY	16 EA		
0220	7408000000-E	1722	1" RISER WITH WEATHERHEAD	2 EA		
0221	7420000000-E	1722	2" RISER WITH WEATHERHEAD	9 EA		
0222	7432000000-E	1722	2" RISER WITH HEAT SHRINK TUBING	3 EA		

County : Stanly

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0223	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	1,650	LF	
0224	7456000000-E	1726	LEAD-IN CABLE (*****) (14-2)	3,800	LF	
0225	7575142000-N	SP	900MHZ WIRELESS RADIO SYSTEM	3	EA	
0226	7684000000-N	1750	SIGNAL CABINET FOUNDATION	2	EA	
0227	7688000000-N	1753	CABINET BASE ADAPTER	1	EA	
0228	7756000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED)	3	EA	
0229	7780000000-N	1751	DETECTOR CARD (TYPE 2070L)	18	EA	
0230	7901000000-N	1753	CABINET BASE EXTENDER	2	EA	
0231	7980000000-N	SP	GENERIC SIGNAL ITEM FURNISH WIRELESS LIGHTNING ARRESTOR	1	EA	
0232	7980000000-N	SP	GENERIC SIGNAL ITEM FURNISH WIRELESS RADIO MODEM	1	EA	
***** BEGIN SCHEDULE AA ***** ***** ( 3 ALTERNATES ) *****						
0233	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	4,098	LF	
<b>AA1</b>						
0234	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	1,588	LF	
<b>AA1</b>						
0235	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	1,108	LF	
<b>AA1</b>						
*** OR ***						
0236	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	3,550	LF	
<b>AA2</b>						
0237	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	1,004	LF	
<b>AA2</b>						
0238	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	1,028	LF	
<b>AA2</b>						

County : Stanly

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0239 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (15")	548 LF		
0240 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (18")	584 LF		
0241 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (24")	80 LF		
*** OR ***						
0242 AA3	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	3,550 LF		
0243 AA3	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	1,004 LF		
0244 AA3	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	1,028 LF		
0245 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (15", 0.064")	548 LF		
0246 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (18", 0.064")	584 LF		
0247 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (24", 0.064")	80 LF		
***** END SCHEDULE AA *****						
0265	5871500000-E	1550	TRENCHLESS INSTALLATION OF 8" IN SOIL	28 LF		
0266	5871510000-E	1550	TRENCHLESS INSTALLATION OF 8" NOT IN SOIL	28 LF		
<b>CULVERT ITEMS</b>						
0248	8056000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (9+10.00-Y4-)	Lump Sum	L.S.	

County : Stanly

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0249	8126000000-N	414	CULVERT EXCAVATION, STA ***** (118+95.00-L-)	Lump Sum	L.S.	
0250	8126000000-N	414	CULVERT EXCAVATION, STA ***** (9+10.00-Y4-)	Lump Sum	L.S.	
0251	8133000000-E	414	FOUNDATION CONDITIONING MATERIAL, BOX CULVERT	493 TON		
0252	8196000000-E	420	CLASS A CONCRETE (CULVERT)	950.5 CY		
0253	8245000000-E	425	REINFORCING STEEL (CULVERT)	117,750 LB		
<b>STRUCTURE ITEMS</b>						
0254	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	6,693 SF		
0255	8161000000-E	420	GROOVING BRIDGE FLOORS	7,413 SF		
0256	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	112 CY		
0257	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (77+90.57-L-)	Lump Sum	L.S.	
0258	8217000000-E	425	REINFORCING STEEL (BRIDGE)	14,576 LB		
0259	8280000000-E	440	APPROX ..... LBS STRUCTURAL STEEL	266,200 LS		
0260	8364000000-E	450	HP12X53 STEEL PILES	630 LF		
0261	8503000000-E	460	CONCRETE BARRIER RAIL	309.5 LF		
0262	8531000000-E	462	4" SLOPE PROTECTION	655 SY		
0263	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0264	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	

**Contract No**     **C201368**

**County (ies):**   **Stanly**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General