

County : Mitchell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (12+97.15)	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (19+80.00)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	100 CY		
0007	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	200 TON		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	500 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
001C	0199000000-E	SP	TEMPORARY SHORING	625 SF		
0011	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	30 TON		
0012	0343000000-E	310	15" SIDE DRAIN PIPE	64 LF		
0013	0408000000-E	310	54" RC PIPE CULVERTS, CLASS III	40 LF		
0014	0576000000-E	310	*** CS PIPE CULVERTS, ***** THICK (48", 0.109")	44 LF		
001E	0995000000-E	340	PIPE REMOVAL	118 LF		
0016	1121000000-E	520	AGGREGATE BASE COURSE	340 TON		
0017	1220000000-E	545	INCIDENTAL STONE BASE	30 TON		

County : Mitchell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	400 TON		
001E	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	430 TON		
002C	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	46 TON		
0021	2000000000-N	806	RIGHT OF WAY MARKERS	41 EA		
0022	2022000000-E	815	SUBDRAIN EXCAVATION	50 CY		
002E	2033000000-E	815	SUBDRAIN FINE AGGREGATE	40 CY		
0024	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	200 LF		
002E	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	6 EA		
002E	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0027	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
002E	2220000000-E	838	REINFORCED ENDWALLS	5 CY		
002E	2264000000-E	840	PIPE PLUGS	1 CY		
003C	2275000000-E	SP	FLOWABLE FILL	3 CY		
0031	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	4 EA		
0032	2297000000-E	840	MASONRY DRAINAGE STRUCTURES	22.4 CY		
003E	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	4 EA		
0034	2396000000-N	840	FRAME WITH COVER, STD 840.54	1 EA		
003E	2556000000-E	846	SHOULDER BERM GUTTER	175 LF		
003E	2580000000-E	846	CONCRETE VALLEY GUTTER	50 LF		

County : Mitchell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	3030000000-E	862	STEEL BM GUARDRAIL	375 LF		
003E	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	50 LF		
003E	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
004C	3165000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE ***** (TL-2)	1 EA		
0041	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		
0042	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	6 EA		
0043	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	8 EA		
0044	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	325 LF		
004E	3382000000-E	862	TEMPORARY STEEL BM GUARDRAIL (SHOP CURVED)	50 LF		
004E	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (AT-1)	1 EA		
0047	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (III)	8 EA		
004E	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	7 EA		
004E	3649000000-E	876	RIP RAP, CLASS B	33 TON		
005C	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	324 SY		
0051	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	316 SF		
0052	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	112 SF		
0053	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	82 SF		

County : Mitchell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	4430000000-N	1130	DRUMS	66	EA	
005E	4435000000-N	1135	CONES	52	EA	
005E	4445000000-E	1145	BARRICADES (TYPE III)	104	LF	
0057	4450000000-N	1150	FLAGGER	420	HR	
005E	4480000000-N	1165	TMIA	2	EA	
005E	4507000000-E	SP	WATER FILLED BARRIER	310	LF	
006C	4516000000-N	1180	SKINNY DRUM	82	EA	
0061	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	256	EA	
0062	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	29,340	LF	
0063	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	80	LF	
0064	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	2,500	LF	
006E	6000000000-E	1605	TEMPORARY SILT FENCE	2,390	LF	
006E	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	220	TON	
0067	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	570	TON	
006E	6012000000-E	1610	SEDIMENT CONTROL STONE	250	TON	
006E	6015000000-E	1615	TEMPORARY MULCHING	32	ACR	
007C	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	1,150	LB	
0071	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	5.5	TON	

County : Mitchell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	6029000000-E	SP	SAFETY FENCE	700 LF		
0073	6030000000-E	1630	SILT EXCAVATION	1,960 CY		
0074	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,100 SY		
0075	6037000000-E	SP	COIR FIBER MAT	10 SY		
0076	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	90 SY		
0077	6042000000-E	1632	1/4" HARDWARE CLOTH	80 LF		
0078	6071030000-E	SP	COIR FIBER BAFFLES	540 LF		
0079	6071050000-E	SP	*** SKIMMER (1-1/2")	1 EA		
0080	6084000000-E	1660	SEEDING & MULCHING	31 ACR		
0081	6087000000-E	1660	MOWING	19 ACR		
0082	6090000000-E	1661	SEED FOR REPAIR SEEDING	400 LB		
0083	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.75 TON		
0084	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	775 LB		
0085	6108000000-E	1665	FERTILIZER TOPDRESSING	22.75 TON		
0086	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
0087	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	27 EA		
0088	6123000000-E	1670	REFORESTATION	0.5 ACR		
0089	7060000000-E	1705	SIGNAL CABLE	800 LF		
0090	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	4 EA		
0091	7264000000-E	1710	MESSENGER CABLE (3/8")	720 LF		

County : Mitchell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0092	7360000000-N	1720	WOOD POLE	7 EA		
0093	7372000000-N	1721	GUY ASSEMBLY	4 EA		
0094	7408000000-E	1722	1" RISER WITH WEATHERHEAD	1 EA		
009E	7420000000-E	1722	2" RISER WITH WEATHERHEAD	3 EA		
009E	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	355 LF		
0097	7456000000-E	1726	LEAD-IN CABLE (***** (14-2)	760 LF		
009E	7768000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, POLE MOUNTED)	1 EA		
009E	7780000000-N	1751	DETECTOR CARD (TYPE 2070L)	2 EA		
***** BEGIN SCHEDULE AA ***** ***** ( 3 ALTERNATES ) *****						
010C AA1	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	44 LF		
0101 AA1	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	84 LF		
*** OR ***						
0102 AA2	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	36 LF		
0103 AA2	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	72 LF		
0104 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (15")	8 LF		
010E AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (18")	12 LF		
*** OR ***						
010E AA3	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	36 LF		
0107 AA3	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	72 LF		

County : Mitchell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0108 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (15", 0.064")	8 LF		
0109 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (18", 0.064")	12 LF		

\*\*\*\*\* END SCHEDULE AA \*\*\*\*\*

STRUCTURE ITEMS

0110	8007000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP STRUCTURE AT STA ***** (12+96.25-L-)	Lump Sum	L.S.	
0111	8007000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP STRUCTURE AT STA ***** (19+80.00-L-)	Lump Sum	L.S.	
0112	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (12+96.25-L-)	Lump Sum	L.S.	
0113	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (19+80.00-L-)	Lump Sum	L.S.	
0114	8070000000-E	410	FOUNDATION EXCAVATION (12+96.25-L-)	100 CY		
0115	8070000000-E	410	FOUNDATION EXCAVATION (19+80.00-L-)	95 CY		
0116	8096000000-E	SP	PILE EXCAVATION IN SOIL	96 LF		
0117	8097000000-E	SP	PILE EXCAVATION NOT IN SOIL	60 LF		
0118	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (12+96.25-L-)	Lump Sum	L.S.	
0119	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (19+80.00-L-)	Lump Sum	L.S.	

County : Mitchell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
012C	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	87.2 CY		
0121	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (12+96.25-L-)	Lump Sum	L.S.	
0122	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (19+80.00-L-)	Lump Sum	L.S.	
0123	8217000000-E	425	REINFORCING STEEL (BRIDGE)	14,185 LB		
0124	8364000000-E	450	HP12X53 STEEL PILES	180 LF		
012E	8503000000-E	460	CONCRETE BARRIER RAIL	210.31 LF		
0126	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	485 TON		
0127	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	545 SY		
012E	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0129	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	1,051.563 LF		
1315/May01/Q69523.973/D552155280000/E129			Total Amount Of Bid For Entire Project :			



**Contract No**     **C201852**

**County (ies):**   **Mitchell**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General