

County : Nash

| Line #               | Item Number  | Sec # | Description   | Quantity    | Unit Cost | Amount |
|----------------------|--------------|-------|---|-------------|-----------|--------|
| <b>ROADWAY ITEMS</b> |              |       |   |             |           |        |
| 0001                 | 0000100000-N | 800   | MOBILIZATION  | Lump Sum    | L.S.      |        |
| 0002                 | 0029000000-N | SP    | REINFORCED BRIDGE APPROACH<br>FILL, STATION *****<br>(13+50.00) | Lump Sum    | L.S.      |        |
| 0003                 | 0050000000-E | 226   | SUPPLEMENTARY CLEARING & GRUB-<br>BING                          | 1<br>ACR    |           |        |
| 0004                 | 0057000000-E | 226   | UNDERCUT EXCAVATION   | 200<br>CY   |           |        |
| 0005                 | 0063000000-N | SP    | GRADING   | Lump Sum    | L.S.      |        |
| 0006                 | 0106000000-E | 230   | BORROW EXCAVATION   | 4,650<br>CY |           |        |
| 0007                 | 0134000000-E | 240   | DRAINAGE DITCH EXCAVATION                                       | 62<br>CY    |           |        |
| 0008                 | 0195000000-E | 265   | SELECT GRANULAR MATERIAL  | 200<br>CY   |           |        |
| 0009                 | 0196000000-E | 270   | FABRIC FOR SOIL STABILIZATION                                   | 200<br>SY   |           |        |
| 0010                 | 0318000000-E | 300   | FOUNDATION CONDITIONING MATE-<br>RIAL, MINOR STRS               | 50<br>TON   |           |        |
| 0011                 | 0342000000-E | 310   | *** SIDE DRAIN PIPE<br>(30")                                    | 40<br>LF    |           |        |
| 0012                 | 0708000000-E | 310   | 15" BIT COAT CS PIPE CULVERTS,<br>TYPE B 0.064" THICK           | 52<br>LF    |           |        |
| 0013                 | 0806000000-E | 310   | 15" BIT COAT CS PIPE ELBOWS,<br>TYPE B 0.064" THICK             | 3<br>EA     |           |        |
| 0014                 | 0995000000-E | 340   | PIPE REMOVAL  | 29<br>LF    |           |        |
| 0015                 | 1121000000-E | 520   | AGGREGATE BASE COURSE   | 32<br>TON   |           |        |
| 0016                 | 1220000000-E | 545   | INCIDENTAL STONE BASE   | 200<br>TON  |           |        |
| 0017                 | 1489000000-E | 610   | ASPHALT CONC BASE COURSE, TYPE<br>B25.0B                        | 270<br>TON  |           |        |
| 0018                 | 1525000000-E | 610   | ASPHALT CONC SURFACE COURSE,<br>TYPE SF9.5A                     | 330<br>TON  |           |        |

County : Nash

| Line # | Item Number  | Sec # | Description                                     | Quantity    | Unit Cost | Amount |
|--------|--------------|-------|---|-------------|-----------|--------|
| 0019   | 1560000000-E | 620   | ASPHALT BINDER FOR PLANT MIX,<br>GRADE PG 64-22 | 34<br>TON   |           |        |
| 0020   | 1693000000-E | 654   | ASPHALT PLANT MIX, PAVEMENT<br>REPAIR           | 20<br>TON   |           |        |
| 0021   | 2000000000-N | 806   | RIGHT OF WAY MARKERS                            | 14<br>EA    |           |        |
| 0022   | 2022000000-E | 815   | SUBDRAIN EXCAVATION                             | 22.4<br>CY  |           |        |
| 0023   | 2033000000-E | 815   | SUBDRAIN FINE AGGREGATE                         | 16.8<br>CY  |           |        |
| 0024   | 2044000000-E | 815   | 6" PERFORATED SUBDRAIN PIPE                     | 100<br>LF   |           |        |
| 0025   | 2055000000-E | 815   | 6" SUBDRAIN PIPE WYES, TEES, &<br>ELBOWS        | 3<br>EA     |           |        |
| 0026   | 2066000000-N | 815   | CONCRETE PAD FOR SUBDRAIN PIPE<br>OUTLET        | 1<br>EA     |           |        |
| 0027   | 2077000000-E | 815   | 6" OUTLET PIPE (SUBDRAINS)                      | 6<br>LF     |           |        |
| 0028   | 2286000000-N | 840   | MASONRY DRAINAGE STRUCTURES                     | 6<br>EA     |           |        |
| 0029   | 2367000000-N | 840   | FRAME WITH TWO GRATES, STD<br>840.29            | 5<br>EA     |           |        |
| 0030   | 2396000000-N | 840   | FRAME WITH COVER, STD 840.54                    | 1<br>EA     |           |        |
| 0031   | 2556000000-E | 846   | SHOULDER BERM GUTTER                            | 300<br>LF   |           |        |
| 0032   | 2612000000-E | 848   | 6" CONCRETE DRIVEWAY                            | 120<br>SY   |           |        |
| 0033   | 3030000000-E | 862   | STEEL BM GUARDRAIL                              | 612.5<br>LF |           |        |
| 0034   | 3045000000-E | 862   | STEEL BM GUARDRAIL, SHOP<br>CURVED              | 87.5<br>LF  |           |        |
| 0035   | 3150000000-N | 862   | ADDITIONAL GUARDRAIL POSTS                      | 5<br>EA     |           |        |
| 0036   | 3195000000-N | 862   | GUARDRAIL ANCHOR UNITS, TYPE<br>AT-1            | 2<br>EA     |           |        |
| 0037   | 3270000000-N | SP    | GUARDRAIL ANCHOR UNITS, TYPE<br>350             | 4<br>EA     |           |        |

County : Nash

| Line # | Item Number  | Sec # | Description                                     | Quantity    | Unit Cost | Amount |
|--------|--------------|-------|---|-------------|-----------|--------|
| 0038   | 3317000000-N | 862   | GUARDRAIL ANCHOR UNITS, TYPE B-77               | 4<br>EA     |           |        |
| 0039   | 3649000000-E | 876   | RIP RAP, CLASS B                                | 9<br>TON    |           |        |
| 0040   | 3656000000-E | 876   | FILTER FABRIC FOR DRAINAGE                      | 271<br>SY   |           |        |
| 0041   | 3659000000-N | SP    | PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON | 1<br>EA     |           |        |
| 0042   | 4400000000-E | 1110  | WORK ZONE SIGNS (STATIONARY)                    | 310<br>SF   |           |        |
| 0043   | 4410000000-E | 1110  | WORK ZONE SIGNS (BARRICADE MOUNTED)             | 94<br>SF    |           |        |
| 0044   | 4445000000-E | 1145  | BARRICADES (TYPE III)                           | 80<br>LF    |           |        |
| 0045   | 4810000000-E | 1205  | PAINT PAVEMENT MARKING LINES (4")               | 5,600<br>LF |           |        |
| 0046   | 4900000000-N | 1251  | PERMANENT RAISED PAVEMENT MARKERS               | 10<br>EA    |           |        |
| 0047   | 6000000000-E | 1605  | TEMPORARY SILT FENCE                            | 1,065<br>LF |           |        |
| 0048   | 6006000000-E | 1610  | STONE FOR EROSION CONTROL, CLASS A              | 75<br>TON   |           |        |
| 0049   | 6009000000-E | 1610  | STONE FOR EROSION CONTROL, CLASS B              | 120<br>TON  |           |        |
| 0050   | 6012000000-E | 1610  | SEDIMENT CONTROL STONE                          | 65<br>TON   |           |        |
| 0051   | 6015000000-E | 1615  | TEMPORARY MULCHING                              | 2<br>ACR    |           |        |
| 0052   | 6018000000-E | 1620  | SEED FOR TEMPORARY SEEDING                      | 100<br>LB   |           |        |
| 0053   | 6021000000-E | 1620  | FERTILIZER FOR TEMPORARY SEEDING                | 1.25<br>TON |           |        |
| 0054   | 6024000000-E | 1622  | TEMPORARY SLOPE DRAINS                          | 220<br>LF   |           |        |
| 0055   | 6027000000-N | 1622  | INLET PROTECTION AT TEMPORARY SLOPE DRAINS      | 6<br>EA     |           |        |
| 0056   | 6029000000-E | SP    | SAFETY FENCE                                    | 240<br>LF   |           |        |

County : Nash

| Line # | Item Number  | Sec # | Description                      | Quantity | Unit Cost | Amount |
|--------|--------------|-------|----------------------------------|----------|-----------|--------|
| 0057   | 6030000000-E | 1630  | SILT EXCAVATION                  | 420      | CY        |        |
| 0058   | 6036000000-E | 1631  | MATTING FOR EROSION CONTROL      | 395      | SY        |        |
| 0059   | 6037000000-E | SP    | COIR FIBER MAT                   | 30       | SY        |        |
| 0060   | 6038000000-E | SP    | PERMANENT SOIL REINFORCEMENT MAT | 160      | SY        |        |
| 0061   | 6042000000-E | 1632  | 1/4" HARDWARE CLOTH              | 100      | LF        |        |
| 0062   | 6071030000-E | SP    | COIR FIBER BAFFLES               | 175      | LF        |        |
| 0063   | 6071050000-E | SP    | *** SKIMMER (1-1/2")             | 5        | EA        |        |
| 0064   | 6084000000-E | 1660  | SEEDING & MULCHING               | 2.5      | ACR       |        |
| 0065   | 6087000000-E | 1660  | MOWING                           | 1.5      | ACR       |        |
| 0066   | 6090000000-E | 1661  | SEED FOR REPAIR SEEDING          | 50       | LB        |        |
| 0067   | 6093000000-E | 1661  | FERTILIZER FOR REPAIR SEEDING    | 0.25     | TON       |        |
| 0068   | 6096000000-E | 1662  | SEED FOR SUPPLEMENTAL SEEDING    | 50       | LB        |        |
| 0069   | 6108000000-E | 1665  | FERTILIZER TOPDRESSING           | 1.5      | TON       |        |
| 0070   | 6114000000-N | SP    | SPECIALIZED HAND MOWING          | 2        | HR        |        |
| 0071   | 6117000000-N | SP    | RESPONSE FOR EROSION CONTROL     | 12       | EA        |        |
| 0072   | 6123000000-E | 1670  | REFORESTATION                    | 0.1      | ACR       |        |

\*\*\*\*\* BEGIN SCHEDULE AA \*\*\*\*\*  
 \*\*\*\*\* ( 3 ALTERNATES ) \*\*\*\*\*

|            |              |     |                                 |     |    |  |
|------------|--------------|-----|---------------------------------|-----|----|--|
| 0073       | 0366000000-E | 310 | 15" RC PIPE CULVERTS, CLASS III | 360 | LF |  |
| <b>AA1</b> |              |     |                                 |     |    |  |

\*\*\* OR \*\*\*

|            |              |     |                                 |    |    |  |
|------------|--------------|-----|---------------------------------|----|----|--|
| 0074       | 0366000000-E | 310 | 15" RC PIPE CULVERTS, CLASS III | 56 | LF |  |
| <b>AA2</b> |              |     |                                 |    |    |  |

County : Nash

| Line #                      | Item Number  | Sec # | Description   | Quantity     | Unit Cost | Amount |
|-----------------------------|--------------|-------|---|--------------|-----------|--------|
| 0075<br>AA2                 | 0536000000-E | SP    | **** HDPE PIPE CULVERTS<br>(15")  | 304<br>LF    |           |        |
| *** OR ***                  |              |       |   |              |           |        |
| 0076<br>AA3                 | 0366000000-E | 310   | 15" RC PIPE CULVERTS, CLASS<br>III  | 56<br>LF     |           |        |
| 0077<br>AA3                 | 0540000000-E | SP    | **** ALUMINIZED CORRUGATED<br>STEEL PIPE CULVERTS, ****<br>THICK<br>(15", 0.064") | 304<br>LF    |           |        |
| ***** END SCHEDULE AA ***** |              |       |   |              |           |        |
| <b>STRUCTURE ITEMS</b>      |              |       |   |              |           |        |
| 0078                        | 8035000000-N | 402   | REMOVAL OF EXISTING STRUCTURE<br>AT STATION *****<br>(13+50.00-L-)                | Lump Sum     | L.S.      |        |
| 0079                        | 8121000000-N | 412   | UNCLASSIFIED STRUCTURE EXCAVA-<br>TION AT STATION *****<br>(13+50.00-L-)          | Lump Sum     | L.S.      |        |
| 0080                        | 8182000000-E | 420   | CLASS A CONCRETE (BRIDGE)   | 37.6<br>CY   |           |        |
| 0081                        | 8210000000-N | 422   | BRIDGE APPROACH SLABS, STATION<br>*****<br>(13+50.00-L-)                          | Lump Sum     | L.S.      |        |
| 0082                        | 8217000000-E | 425   | REINFORCING STEEL (BRIDGE)  | 5,758<br>LB  |           |        |
| 0083                        | 8364000000-E | 450   | HP12X53 STEEL PILES   | 900<br>LF    |           |        |
| 0084                        | 8393000000-N | 450   | PILE REDRIVES   | 8<br>EA      |           |        |
| 0085                        | 8503000000-E | 460   | CONCRETE BARRIER RAIL   | 195.39<br>LF |           |        |
| 0086                        | 8608000000-E | 876   | RIP RAP CLASS II (2'-0" THICK)  | 350<br>TON   |           |        |
| 0087                        | 8622000000-E | 876   | FILTER FABRIC FOR DRAINAGE  | 390<br>SY    |           |        |
| 0088                        | 8657000000-N | 430   | ELASTOMERIC BEARINGS  | Lump Sum     | L.S.      |        |

County : Nash

| Line # | Item Number  | Sec # | Description                                 | Quantity       | Unit Cost | Amount |
|--------|--------------|-------|---|----------------|-----------|--------|
| 0089   | 8753200000-E | 430   | 3'-0" X 3'-3" PRESTRESSED CONC<br>BOX BEAMS | 1,074.62<br>LF |           |        |

0840/May08/Q27157.91/D352294380000/E89

Total Amount Of Bid For Entire Project :

**Contract No**     **C201854**

**County (ies):**   **Nash**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General