

County : Yancey

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0001000000-M	200	CLEARING & GRUBBING .. HECTACRE(S)	Lump Sum	L.S.	
0004	0008000000-M	200	SUPPLEMENTARY CLEARING & GRUB- BING	1.2 HA		
0005	0015000000-N	205	SEALING ABANDONED WELLS	2 EA		
0006	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (175 + 50)	Lump Sum	L.S.	
0007	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (191 + 92)	Lump Sum	L.S.	
0008	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (223 + 58)	Lump Sum	L.S.	
0009	0036000000-M	225	UNDERCUT EXCAVATION	1,000 M3		
0010	0080000000-M	SP	CLASS IV SUBGRADE STABILIZA- TION	2,400 MTN		
0011	0134000000-M	240	DRAINAGE DITCH EXCAVATION	13,487 M3		
0012	0141000000-M	240	BERM DITCH CONSTRUCTION	1,412 M		
0013	0156000000-M	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	34,500 M2		
0014	0177000000-M	250	BREAKING OF EXISTING ASPHALT PAVEMENT	2,500 M2		
0015	0192000000-N	260	PROOF ROLLING	43 HR		
0016	0195000000-M	265	SELECT GRANULAR MATERIAL	1,000 M3		
0017	0196000000-M	270	FABRIC FOR SOIL STABILIZATION	1,000 M2		

County : Yancey

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	0199000000-M	SP	TEMPORARY SHORING	285	M2	
0019	0241000000-M	SP	GENERIC GRADING ITEM ROCK PLATING	195	M2	
002C	0318000000-M	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	2,680	MTN	
0021	0343000000-M	310	375MM SIDE DRAIN PIPE	51.6	M	
0022	0344000000-M	310	450MM SIDE DRAIN PIPE	49.2	M	
0023	0378000000-M	310	600MM RC PIPE CULVERTS, CLASS III	563.6	M	
0024	0384000000-M	310	750MM RC PIPE CULVERTS, CLASS III	138	M	
002E	0390000000-M	310	900MM RC PIPE CULVERTS, CLASS III	363.6	M	
002E	0396000000-M	310	1050MM RC PIPE CULVERTS, CLASS III	46.8	M	
0027	0402000000-M	310	1200MM RC PIPE CULVERTS, CLASS III	16.8	M	
002E	0696000000-M	310	***MM BIT COAT CS PIPE CUL- VERTS, TYPE B ****MM THICK, (75 X 25MM CORRUGATIONS) (1700MM, 2.77MM)	21.6	M	
0029	0696000000-M	310	***MM BIT COAT CS PIPE CUL- VERTS, TYPE B ****MM THICK, (75 X 25MM CORRUGATIONS) (1700MM, 3.51MM)	25.2	M	
003C	0696000000-M	310	***MM BIT COAT CS PIPE CUL- VERTS, TYPE B ****MM THICK, (75 X 25MM CORRUGATIONS) (2300MM, 3.51MM)	86.4	M	
0031	0708000000-M	310	400MM BIT COAT CS PIPE CUL- VERTS, TYPE B 1.63MM THICK	583.2	M	
0032	0714000000-M	310	450MM BIT COAT CS PIPE CUL- VERTS, TYPE B 1.63MM THICK	138	M	

County : Yancey

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0033	0720000000-M	310	600MM BIT COAT CS PIPE CULVERTS, TYPE B 1.63MM THICK	82.8	M	
0034	0726000000-M	310	800MM BIT COAT CS PIPE CULVERTS, TYPE B 2.01MM THICK	91.2	M	
003E	0732000000-M	310	900MM BIT COAT CS PIPE CULVERTS, TYPE B 2.01MM THICK	64.8	M	
003E	0738000000-M	310	1000MM BIT COAT CS PIPE CULVERTS, TYPE B 2.77MM THICK	2.4	M	
0037	0744000000-M	310	1200MM BIT COAT CS PIPE CULVERTS, TYPE B 2.77MM THICK	34.8	M	
003E	0750000000-M	310	1400MM BIT COAT CS PIPE CULVERTS, TYPE B 2.77MM THICK	16.8	M	
0039	0804000000-M	310	***MM BIT COAT CS PIPE ELBOWS, TYPE B ***MM THICK (1200MM, 2.77MM)	2	EA	
004C	0804000000-M	310	***MM BIT COAT CS PIPE ELBOWS, TYPE B ***MM THICK (1700MM, 3.51MM)	2	EA	
0041	0804000000-M	310	***MM BIT COAT CS PIPE ELBOWS, TYPE B ***MM THICK (2300MM, 3.51MM)	2	EA	
0042	0804000000-M	310	***MM BIT COAT CS PIPE ELBOWS, TYPE B ***MM THICK (900MM, 2.01MM)	1	EA	
0043	0806000000-M	310	400MM BIT COAT CS PIPE ELBOWS, TYPE B 1.63MM THICK	40	EA	
0044	0807000000-M	310	450MM BIT COAT CS PIPE ELBOWS, TYPE B 1.63MM THICK	6	EA	
004E	0808000000-M	310	600MM BIT COAT CS PIPE ELBOWS, TYPE B 1.63MM THICK	2	EA	
004E	0908000000-M	310	**** X ****MM BIT COAT CS PIPE ARCH CULVERTS, TYPE B ****MM THICK (1425MM X 950MM, 2.77MM)	9.6	M	

County : Yancey

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0047	0908000000-M	310	**** X ****MM BIT COAT CS PIPE ARCH CULVERTS, TYPE B ****MM THICK (1780MM X 1360MM, 2.77MM)	15.6	M	
004E	0908000000-M	310	**** X ****MM BIT COAT CS PIPE ARCH CULVERTS, TYPE B ****MM THICK (1830MM X 1120MM, 2.77MM)	13.2	M	
0049	0908000000-M	310	**** X ****MM BIT COAT CS PIPE ARCH CULVERTS, TYPE B ****MM THICK (2080MM X 1530MM, 2.77MM)	24	M	
005C	0908000000-M	310	**** X ****MM BIT COAT CS PIPE ARCH CULVERTS, TYPE B ****MM THICK (2410MM X 1700MM, 2.77MM)	27.6	M	
0051	0908000000-M	310	**** X ****MM BIT COAT CS PIPE ARCH CULVERTS, TYPE B ****MM THICK (2500MM X 1830MM, 2.77MM)	12	M	
0052	0992000000-M	SP	GENERIC PIPE ITEM 1425MM X 950MM BCCS PIPE ARCH ELBOW, 10 DEGREE HORIZONTAL, 2.77MM THICK	1	EA	
0053	0992000000-M	SP	GENERIC PIPE ITEM 1780MM X 1360MM BCCS PIPE ARCH ELBOW, 3 DEGREE VERTICAL, 2.77MM THICK	1	EA	
0054	0992000000-M	SP	GENERIC PIPE ITEM 1830MM X 1120MM BCCS PIPE ARCH ELBOW, 1 DEGREE VERTICAL, 2.77MM THICK	1	EA	
005E	0992000000-M	SP	GENERIC PIPE ITEM 2080MM X 1530MM BCCS PIPE ARCH ELBOW, 2 DEGREE VERTICAL, 2.77MM THICK	2	EA	
005E	0992000000-M	SP	GENERIC PIPE ITEM 2410MM X 1700MM BCCS PIPE ARCH ELBOW, 4 DEGREE HORIZONTAL, 2.77MM THICK	1	EA	

County : Yancey

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	0995000000-M	340	PIPE REMOVAL	1,686 M		
0058	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
0059	1044000000-M	501	LIME TREATED SOIL (SLURRY METHOD)	41,120 M2		
006C	1066000000-M	501	LIME FOR LIME TREATED SOIL	470 MTN		
0061	1077000000-M	SP	#57 STONE	245 MTN		
0062	1110000000-M	510	STABILIZER AGGREGATE	800 MTN		
0063	1176000000-M	542	SOIL CEMENT BASE (180MM)	95,940 M2		
0064	1187000000-M	542	PORTLAND CEMENT FOR SOIL CEMENT BASE	2,910 MTN		
006E	1198000000-M	SP	AGGREGATE FOR SOIL CEMENT BASE	1,330 MTN		
006E	1209000000-M	543	ASPHALT CURING SEAL	93,210 L		
0067	1220000000-M	545	INCIDENTAL STONE BASE	250 MTN		
006E	1489000000-M	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	2,600 MTN		
0069	1498000000-M	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	1,300 MTN		
007C	1503000000-M	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	49,700 MTN		
0071	1519000000-M	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	3,000 MTN		
0072	1523000000-M	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	45,200 MTN		
0073	1565000000-M	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	2,712 MTN		
0074	1693000000-M	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	1,390 MTN		

County : Yancey

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0075	2000000000-N	806	RIGHT OF WAY MARKERS	146 EA		
0076	2022000000-M	815	SUBDRAIN EXCAVATION	165.6 M3		
0077	2033000000-M	815	SUBDRAIN FINE AGGREGATE	82.8 M3		
007E	2044000000-M	815	150MM PERFORATED SUBDRAIN PIPE	200 M		
0079	2055000000-M	815	150MM SUBDRAIN PIPE WYES, TEES, & ELBOWS	21 EA		
008C	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	2 EA		
0081	2077000000-M	815	150MM OUTLET PIPE (SUBDRAINS)	4 M		
0082	2143000000-M	818	BLOTTING SAND	20 MTN		
0083	2190000000-N	828	TEMPORARY STEEL PLATE COVERS FOR MASONRY DRAINAGE STRUCTURE	27 EA		
0084	2209000000-M	838	ENDWALLS	3.7 M3		
008E	2220000000-M	838	REINFORCED ENDWALLS	66.24 M3		
0086	2253000000-M	840	PIPE COLLARS	1.61 M3		
0087	2275000000-M	SP	FLOWABLE FILL	37.92 M3		
008E	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	304 EA		
008E	2308000000-M	840	MASONRY DRAINAGE STRUCTURES	26.81 M		
009C	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	105 EA		
0091	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	84 EA		
0092	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	57 EA		

County : Yancey

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0093	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	2 EA		
0094	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	20 EA		
009E	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	16 EA		
009E	2396000000-N	840	FRAME WITH COVER, STD 840.54	5 EA		
0097	2462000000-M	SP	***MM SLUICE GATE (800MM)	2 EA		
009E	2474000000-N	SP	GENERIC DRAINAGE ITEM HAZARDOUS SPILL RETENTION BASIN	Lump Sum	L.S.	
009E	2538000000-M	846	***MM CONCRETE CURB & GUTTER (825MM)	2,400 M		
010C	2542000000-M	846	450MM CONCRETE CURB & GUTTER	6,200 M		
0101	2549000000-M	846	750MM CONCRETE CURB & GUTTER	460 M		
0102	2556000000-M	846	SHOULDER BERM GUTTER	1,500 M		
0103	2577000000-M	846	CONCRETE EXPRESSWAY GUTTER	1,900 M		
0104	2612000000-M	848	150MM CONCRETE DRIVEWAY	12 M2		
010E	2619000000-M	850	100MM CONCRETE PAVED DITCH	112 M2		
010E	2655000000-M	852	125MM MONOLITHIC CONCRETE IS- LANDS (KEYED IN)	8,500 M2		
0107	2752000000-M	SP	GENERIC PAVING ITEM EMERGENCY VEHICLE ACCESS	15.2 M		
010E	2905000000-N	859	CONVERT EXISTING DROP INLET TO JUNCTION BOX	8 EA		

County : Yancey

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0109	3000000000-N	SP	IMPACT ATTENUATOR UNIT, TYPE 350	1	EA	
0110	3030000000-M	862	STEEL BM GUARDRAIL	5,006.34	M	
0111	3045000000-M	862	STEEL BM GUARDRAIL, SHOP CURVED	243.84	M	
0112	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10	EA	
0113	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	7	EA	
0114	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	2	EA	
0115	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	7	EA	
0116	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	78	EA	
0117	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	11	EA	
0118	3360000000-M	863	REMOVE EXISTING GUARDRAIL	4,258	M	
0119	3380000000-M	862	TEMPORARY STEEL BM GUARDRAIL	100	M	
0120	3503000000-M	866	WOVEN WIRE FENCE, 1200MM FABRIC	7,800	M	
0121	3509000000-M	866	100MM TIMBER FENCE POSTS, 2.30M LONG	1,520	EA	
0122	3515000000-M	866	125MM TIMBER FENCE POSTS, 2.50M LONG	568	EA	
0123	3536000000-M	866	CHAIN LINK FENCE, 1200MM FABRIC	80	M	
0124	3542000000-M	866	METAL LINE POSTS FOR 1200MM CHAIN LINK FENCE	22	EA	
0125	3548000000-M	866	METAL TERMINAL POSTS FOR 1200MM CHAIN LINK FENCE	2	EA	

County : Yancey

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
012E	3628000000-M	876	RIP RAP, CLASS I	356.1	MTN	
0127	3635000000-M	876	RIP RAP, CLASS II	425	MTN	
012E	3642000000-M	876	RIP RAP, CLASS A	160	MTN	
012E	3649000000-M	876	RIP RAP, CLASS B	1,338.1	MTN	
013C	3651000000-M	SP	BOULDERS	888	MTN	
0131	3656000000-M	876	FILTER FABRIC FOR DRAINAGE	10,614.6	M2	
0132	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	7	EA	
0133	4072000000-M	903	SUPPORTS, 4.5-KG STEEL U-CHANN EL	1,701	M	
0134	4096000000-N	904	SIGN ERECTION, TYPE D	2	EA	
013E	4102000000-N	904	SIGN ERECTION, TYPE E	353	EA	
013E	4108000000-N	904	SIGN ERECTION, TYPE F	11	EA	
0137	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (D)	8	EA	
013E	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	118	EA	
013E	4400000000-M	1110	WORK ZONE SIGNS (STATIONARY)	70	M2	
014C	4405000000-M	1110	WORK ZONE SIGNS (PORTABLE)	73	M2	
0141	4410000000-M	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	70	M2	
0142	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	2	EA	
0143	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	7	EA	
0144	4430000000-N	1130	DRUMS	1,500	EA	

County : Yancey

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
014E	4445000000-M	1145	BARRICADES (TYPE III)	549	M	
014E	4450000000-N	1150	FLAGGER	16,000	HR	
0147	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	10	EA	
014E	4470000000-N	1160	RESET TEMPORARY CRASH CUSHIONS	2	EA	
014E	4480000000-N	1165	TMIA	2	EA	
015C	4485000000-M	1170	PORTABLE CONCRETE BARRIER	470	M	
0151	4490000000-M	1170	PORTABLE CONCRETE BARRIER (ANCHORED)	124	M	
0152	4495000000-M	1170	PORTABLE CONCRETE BARRIER (DRAINAGE)	470	M	
015E	4500000000-M	1170	RESET PORTABLE CONCRETE BAR- RIER	88	M	
0154	4506000000-M	1170	RESET PORTABLE CONCRETE BAR- RIER (DRAINAGE)	88	M	
015E	4510000000-N	SP	POLICE	100	HR	
015E	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	1,000	EA	
0157	4810000000-M	1205	PAINT PAVEMENT MARKING LINES (100MM)	188,974	M	
015E	4820000000-M	1205	PAINT PAVEMENT MARKING LINES (200MM)	126	M	
015E	4835000000-M	1205	PAINT PAVEMENT MARKING LINES (600MM)	508	M	
016C	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	295	EA	
0161	4847000000-M	1205	POLYUREA PAVEMENT MARKING LINES (100MM, *****) (STANDARD GLASS BEADS)	36,366	M	

County : Yancey

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0162	4847140000-M	1205	POLYUREA PAVEMENT MARKING LINES (600MM, *****) (STANDARD GLASS BEADS)	254 M		
0163	4847220000-N	1205	POLYUREA PAVEMENT MARKING SYMBOL (*****) (STANDARD GLASS BEADS)	295 EA		
0164	4850000000-M	1205	REMOVAL OF PAVEMENT MARKING LINES (100MM)	7,000 M		
0165	4860000000-M	1205	REMOVAL OF PAVEMENT MARKING LINES (200MM)	63 M		
0166	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	1,526 EA		
0167	6000000000-M	1605	TEMPORARY SILT FENCE	11,300 M		
016E	6006000000-M	1610	STONE FOR EROSION CONTROL, CLASS A	6,200 MTN		
0169	6009000000-M	1610	STONE FOR EROSION CONTROL, CLASS B	11,200 MTN		
017C	6012000000-M	1610	SEDIMENT CONTROL STONE	11,000 MTN		
0171	6015000000-M	1615	TEMPORARY MULCHING	61 HA		
0172	6018000000-M	1620	SEED FOR TEMPORARY SEEDING	3,350 KG		
0173	6021000000-M	1620	FERTILIZER FOR TEMPORARY SEEDING	18 MTN		
0174	6024000000-M	1622	TEMPORARY SLOPE DRAINS	500 M		
017E	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	26 EA		
017E	6029000000-M	SP	SAFETY FENCE	16,000 M		
0177	6030000000-M	1630	SILT EXCAVATION	56,110 M3		
017E	6036000000-M	1631	MATTING FOR EROSION CONTROL	49,200 M2		
0179	6037000000-M	SP	COIR FIBER MAT	3,055 M2		

County : Yancey

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
018C	6038000000-M	SP	PERMANENT SOIL REINFORCEMENT MAT	17,650 M2		
0181	6042000000-M	1632	6.4MM HARDWARE CLOTH	1,825 M		
0182	6045000000-M	SP	***MM TEMPORARY PIPE (450MM)	55 M		
0183	6046000000-M	SP	TEMPORARY PIPE FOR STREAM CROSSING	100 M		
0184	6069000000-M	1638	STILLING BASINS	800 M3		
018E	6070000000-N	SP	SPECIAL STILLING BASINS	30 EA		
018F	6071010000-M	SP	WATTLE	1,025 M		
0187	6071020000-M	SP	POLYACRYLAMIDE (PAM)	1,000 KG		
018E	6071030000-M	SP	COIR FIBER BAFFLES	3,825 M		
018E	6071050000-M	SP	***MM SKIMMER (102MM)	1 EA		
019C	6071050000-M	SP	***MM SKIMMER (127MM)	2 EA		
0191	6071050000-M	SP	***MM SKIMMER (38MM)	83 EA		
0192	6071050000-M	SP	***MM SKIMMER (51MM)	37 EA		
0193	6071050000-M	SP	***MM SKIMMER (64MM)	22 EA		
0194	6071050000-M	SP	***MM SKIMMER (76MM)	5 EA		
019E	6084000000-M	1660	SEEDING & MULCHING	80 HA		
019E	6087000000-M	1660	MOWING	46.5 HA		
0197	6090000000-M	1661	SEED FOR REPAIR SEEDING	1,000 KG		

County : Yancey

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
019E	6093000000-M	1661	FERTILIZER FOR REPAIR SEEDING	3.5 MTN		
019E	6096000000-M	1662	SEED FOR SUPPLEMENTAL SEEDING	2,075 KG		
020C	6108000000-M	1665	FERTILIZER TOPDRESSING	124.25 MTN		
0201	6111000000-M	SP	IMPERVIOUS DIKE	410 M		
0202	6114000000-N	SP	SPECIALIZED HAND MOWING	37 HR		
0203	6118000000-N	SP	ROOTWADS	5 EA		
0204	6120000000-M	SP	CULVERT DIVERSION CHANNEL	170 M3		
020E	6123000000-M	1670	REFORESTATION	1 HA		
020E	6126000000-M	SP	STREAMBANK REFORESTATION	2.95 HA		
0207	6133000000-N	SP	GENERIC EROSION CONTROL ITEM CONSTRUCTION SURVEYING FOR MITIGATION	Lump Sum	L.S.	
020E	6133000000-N	SP	GENERIC EROSION CONTROL ITEM DIVERSION PUMPING FOR MITIGA- TION	Lump Sum	L.S.	
020E	6133000000-N	SP	GENERIC EROSION CONTROL ITEM GRADING FOR MITIGATION	Lump Sum	L.S.	
021C	7060000000-M	1705	SIGNAL CABLE	605 M		
0211	7120000000-M	1705	VEHICLE SIGNAL HEAD (300MM, 3 SECTION)	20 EA		
0212	7264000000-M	1710	MESSENGER CABLE (9.52MM)	328 M		
0213	7288000000-M	1715	PAVED TRENCHING (***** (2, 2"))	5 M		
0214	7300000000-M	1715	UNPAVED TRENCHING (***** (2, 2"))	472 M		
021E	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	10 EA		

County : Yancey

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0216	7360000000-N	1720	WOOD POLE	9	EA	
0217	7372000000-N	1721	GUY ASSEMBLY	16	EA	
021E	7408000000-M	1722	25MM RISER WITH WEATHERHEAD	3	EA	
0219	7420000000-M	1722	50MM RISER WITH WEATHERHEAD	8	EA	
022C	7444000000-M	1725	INDUCTIVE LOOP SAWCUT	590	M	
0221	7456000000-M	1726	LEAD-IN CABLE (***** (14-2)	1,055	M	
0222	7484000000-N	SP	MICROWAVE VEHICLE DETECTOR	1	EA	
0223	7684000000-N	1750	SIGNAL CABINET FOUNDATION	2	EA	
0224	7756000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED)	2	EA	
022E	7780000000-N	1751	DETECTOR CARD (TYPE 2070L)	13	EA	
022E	7901000000-N	1753	CABINET BASE EXTENDER	2	EA	
***** BEGIN SCHEDULE AA ***** ***** (3 ALTERNATES) *****						
0227 AA1	0366000000-M	310	375MM RC PIPE CULVERTS, CLASS III	4,430.4	M	
022E AA1	0372000000-M	310	450MM RC PIPE CULVERTS, CLASS III	1,530	M	
*** OR ***						
0229 AA2	0366000000-M	310	375MM RC PIPE CULVERTS, CLASS III	4,124.4	M	
023C AA2	0372000000-M	310	450MM RC PIPE CULVERTS, CLASS III	982.8	M	
0231 AA2	0536000000-M	SP	****MM HDPE PIPE CULVERTS (375MM)	306	M	

County : Yancey

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0232 AA2	0536000000-M	SP	****MM HDPE PIPE CULVERTS (450MM)	547.2 M		
*** OR ***						
0233 AA3	0366000000-M	310	375MM RC PIPE CULVERTS, CLASS III	4,124.4 M		
0234 AA3	0372000000-M	310	450MM RC PIPE CULVERTS, CLASS III	982.8 M		
023E AA3	0540000000-M	SP	****MM ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, ****MM THICK (375MM, 1.63MM)	306 M		
0236 AA3	0540000000-M	SP	****MM ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, ****MM THICK (450MM, 1.63MM)	547.2 M		
***** END SCHEDULE AA *****						
***** BEGIN SCHEDULE AB ***** (2 ALTERNATES) *****						
0237 AB1	0022000000-M	225	UNCLASSIFIED EXCAVATION	910,000 M3		
023E AB1	1121000000-M	520	AGGREGATE BASE COURSE	71,400 MTN		
023E AB1	1231000000-M	560	SHOULDER BORROW	14,800 M3		
024C AB1	1491000000-M	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	16,800 MTN		
0241 AB1	1560000000-M	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	3,420 MTN		
*** OR ***						
0242 AB2	0022000000-M	225	UNCLASSIFIED EXCAVATION	903,000 M3		
0243 AB2	1121000000-M	520	AGGREGATE BASE COURSE	1,820 MTN		
0244 AB2	1231000000-M	560	SHOULDER BORROW	11,700 M3		
024E AB2	1491000000-M	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	49,200 MTN		

County : Yancey

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0246 AB2	1560000000-M	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	4,805 MTN		

***** END SCHEDULE AB *****

CULVERT ITEMS

0247	8126000000-N	414	CULVERT EXCAVATION, STA ***** (134 + 72.000-L-)	Lump Sum	L.S.	
0248	8126000000-N	414	CULVERT EXCAVATION, STA ***** (138 + 05.000-L-)	Lump Sum	L.S.	
0249	8126000000-N	414	CULVERT EXCAVATION, STA ***** (156 + 63.000-L-)	Lump Sum	L.S.	
025C	8133000000-M	414	FOUNDATION CONDITIONING MATER- IAL, BOX CULVERT	312 MTN		
0251	8196000000-M	420	CLASS A CONCRETE (CULVERT)	465.1 M3		
0252	8245000000-M	425	REINFORCING STEEL (CULVERT)	51,451 KG		

WALL ITEMS

0253	8801000000-M	SP	MSE RETAINING WALL	222 M2		
------	--------------	----	--------------------	-----------	--	--

STRUCTURE ITEMS

0254	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (191 + 92.500-L-)	Lump Sum	L.S.	
0255	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (223 + 53.200-L-)	Lump Sum	L.S.	
0256	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (175 + 52.267-L-LT)	Lump Sum	L.S.	

County : Yancey

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0257	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (223 + 53.200-L-)	Lump Sum	L.S.	
025E	8105540000-M	SP	1066MM DIA DRILLED PIERS IN SOIL	60.1 M		
025E	8105640000-M	SP	1066MM DIA DRILLED PIERS NOT IN SOIL	26 M		
026C	8111400000-M	SP	PERMANENT STEEL CASING FOR 1066MM DRILLED PIER	10 M		
0261	8113000000-N	SP	SID INSPECTION	6 EA		
0262	8114000000-N	SP	SPT TESTING	3 EA		
026E	8115000000-N	SP	CROSSHOLE SONIC LOGGING	6 EA		
0264	8119000000-M	412	UNCLASSIFIED STRUCTURE EXCAVA- TION	2,740 M3		
026E	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (191 + 92.500-L-)	Lump Sum	L.S.	
026E	8147000000-M	420	REINFORCED CONCRETE DECK SLAB	2,435.2 M2		
0267	8161000000-M	420	GROOVING BRIDGE FLOORS	3,350.8 M2		
026E	8175000000-M	420	CLASS AA CONCRETE (BRIDGE)	94.9 M3		
026E	8182000000-M	420	CLASS A CONCRETE (BRIDGE)	374 M3		
027C	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (175 + 52.267-L-LT)	Lump Sum	L.S.	
0271	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (175 + 52.267-L-RT)	Lump Sum	L.S.	
0272	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (191 + 92.500-L-)	Lump Sum	L.S.	

County : Yancey

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0273	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (223 + 53.200-L-)	Lump Sum	L.S.	
0274	8217000000-M	425	REINFORCING STEEL (BRIDGE)	43,818 KG		
0275	8224000000-M	425	EPOXY COATED REINFORCING STEEL (BRIDGE)	1,945 KG		
0276	8238000000-M	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	5,109 KG		
0277	8262000000-M	430	1143MM PRESTRESSED CONCRETE GIRDERS	1,004.58 M		
027E	8364000000-M	450	HP310X79 STEEL PILES	623 M		
0279	8385200000-M	450	PP ** X **** GALVANIZED STEEL PILES (762MM X 12.7MM)	146.4 M		
028C	8391000000-N	450	STEEL PILE POINTS	18 EA		
0281	8503000000-M	460	CONCRETE BARRIER RAIL	234.45 M		
0282	8517000000-M	460	*** X ****MM CONCRETE PARAPET (483MM X 178MM)	172.408 M		
0283	8538000000-M	SP	CLASS I, SURFACE PREPARATION	743 M2		
0284	8559000000-M	SP	CLASS II, SURFACE PREPARATION	35 M2		
028E	8566000000-M	SP	CLASS III, SURFACE PREPARATION	10 M2		
028E	8573000000-M	SP	LATEX MODIFIED CONC OVERLAY	49 M3		
0287	8580000000-M	SP	PLACING & FINISHING OF LATEX MODIFIED CONC OVERLAY	1,535 M2		
028E	8608000000-M	876	RIP RAP CLASS II (600MM THICK)	2,074 MTN		
028E	8622000000-M	876	FILTER FABRIC FOR DRAINAGE	2,154 M2		
029C	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	

County : Yancey

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0291	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0292	8867000000-M	SP	GENERIC STRUCTURE ITEM SPECIAL STEEL 2 BAR METAL RAIL	180.316 M		
0822/May12/Q3048970.514/D1151434100000/E292			Total Amount Of Bid For Entire Project :			

Contract No: C202007

Count(ies): Yancey

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General

Signature Sheet (Bid - Acceptance by Department)